


| STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS AND MINING | | | | | | FORM 3 AMENDED REPORT <input checked="" type="checkbox"/> | | | | |
|--|------------------|--|--|---|---|--|----------------------------------|-------------------------|-------|--------|
| APPLICATION FOR PERMIT TO DRILL | | | | | | 1. WELL NAME and NUMBER Three Rivers 16-42L-820 | | | | |
| 2. TYPE OF WORK DRILL NEW WELL <input checked="" type="checkbox"/> REENTER P&A WELL <input type="checkbox"/> DEEPEN WELL <input type="checkbox"/> | | | | | | 3. FIELD OR WILDCAT THREE RIVERS | | | | |
| 4. TYPE OF WELL Oil Well Coalbed Methane Well: NO | | | | | | 5. UNIT or COMMUNITIZATION AGREEMENT NAME | | | | |
| 6. NAME OF OPERATOR ULTRA RESOURCES INC | | | | | | 7. OPERATOR PHONE 303 645-9810 | | | | |
| 8. ADDRESS OF OPERATOR 304 Inverness Way South #245, Englewood, CO, 80112 | | | | | | 9. OPERATOR E-MAIL dghani@ultrapetroleum.com | | | | |
| 10. MINERAL LEASE NUMBER (FEDERAL, INDIAN, OR STATE) ML-49319 | | | 11. MINERAL OWNERSHIP FEDERAL <input type="checkbox"/> INDIAN <input type="checkbox"/> STATE <input checked="" type="checkbox"/> FEE <input type="checkbox"/> | | | 12. SURFACE OWNERSHIP FEDERAL <input type="checkbox"/> INDIAN <input type="checkbox"/> STATE <input checked="" type="checkbox"/> FEE <input type="checkbox"/> | | | | |
| 13. NAME OF SURFACE OWNER (if box 12 = 'fee') | | | | | | 14. SURFACE OWNER PHONE (if box 12 = 'fee') | | | | |
| 15. ADDRESS OF SURFACE OWNER (if box 12 = 'fee') | | | | | | 16. SURFACE OWNER E-MAIL (if box 12 = 'fee') | | | | |
| 17. INDIAN ALLOTTEE OR TRIBE NAME (if box 12 = 'INDIAN') | | | 18. INTEND TO COMMINGLE PRODUCTION FROM MULTIPLE FORMATIONS YES <input type="checkbox"/> (Submit Commingling Application) NO <input checked="" type="checkbox"/> | | | 19. SLANT VERTICAL <input type="checkbox"/> DIRECTIONAL <input checked="" type="checkbox"/> HORIZONTAL <input type="checkbox"/> | | | | |
| 20. LOCATION OF WELL | FOOTAGES | QTR-QTR | SECTION | TOWNSHIP | RANGE | MERIDIAN | | | | |
| LOCATION AT SURFACE | 2006 FNL 607 FEL | SENE | 16 | 8.0 S | 20.0 E | S | | | | |
| Top of Uppermost Producing Zone | 1980 FNL 660 FEL | SENE | 16 | 8.0 S | 20.0 E | S | | | | |
| At Total Depth | 1980 FNL 660 FEL | SENE | 16 | 8.0 S | 20.0 E | S | | | | |
| 21. COUNTY UINTAH | | 22. DISTANCE TO NEAREST LEASE LINE (Feet) 607 | | 23. NUMBER OF ACRES IN DRILLING UNIT 40 | | | | | | |
| | | 25. DISTANCE TO NEAREST WELL IN SAME POOL (Applied For Drilling or Completed) 2710 | | 26. PROPOSED DEPTH MD: 6523 TVD: 6521 | | | | | | |
| 27. ELEVATION - GROUND LEVEL 4703 | | 28. BOND NUMBER 022046398 | | 29. SOURCE OF DRILLING WATER / WATER RIGHTS APPROVAL NUMBER IF APPLICABLE 49-2262 | | | | | | |
| Hole, Casing, and Cement Information | | | | | | | | | | |
| String | Hole Size | Casing Size | Length | Weight | Grade & Thread | Max Mud Wt. | Cement | Sacks | Yield | Weight |
| SURF | 11 | 8.625 | 0 - 1033 | 24.0 | J-55 LT&C | 8.8 | Premium Lite High Strength | 80 | 2.97 | 11.5 |
| | | | | | | | Class G | 115 | 1.16 | 15.8 |
| PROD | 7.875 | 5.5 | 0 - 6523 | 17.0 | J-55 LT&C | 10.0 | Halliburton Light , Type Unknown | 225 | 3.54 | 11.0 |
| | | | | | | | Premium Lite High Strength | 450 | 1.349 | 14.0 |
| ATTACHMENTS | | | | | | | | | | |
| VERIFY THE FOLLOWING ARE ATTACHED IN ACCORDANCE WITH THE UTAH OIL AND GAS CONSERVATION GENERAL RULES | | | | | | | | | | |
| <input checked="" type="checkbox"/> WELL PLAT OR MAP PREPARED BY LICENSED SURVEYOR OR ENGINEER | | | | | <input checked="" type="checkbox"/> COMPLETE DRILLING PLAN | | | | | |
| <input type="checkbox"/> AFFIDAVIT OF STATUS OF SURFACE OWNER AGREEMENT (IF FEE SURFACE) | | | | | <input type="checkbox"/> FORM 5. IF OPERATOR IS OTHER THAN THE LEASE OWNER | | | | | |
| <input checked="" type="checkbox"/> DIRECTIONAL SURVEY PLAN (IF DIRECTIONALLY OR HORIZONTALLY DRILLED) | | | | | <input checked="" type="checkbox"/> TOPOGRAPHICAL MAP | | | | | |
| NAME Don Hamilton | | | | | TITLE Permitting Agent | | | PHONE 435 719-2018 | | |
| SIGNATURE | | | | | DATE 02/04/2014 | | | EMAIL starpoint@etv.net | | |
| API NUMBER ASSIGNED 43047542690000 | | | | | APPROVAL  Permit Manager | | | | | |

ULTRA RESOURCES, INC.

MASTER
8 - POINT DRILLING PROGRAM

Slim Hole Design
8 5/8" Surface & 5 1/2" Production Casing Design

DATED: 03-27-14

**Directional Wells located on Ultra leases in
Three Rivers Project:**

Three Rivers Fed 16-42L-820

SHL: Sec 16 (SENE) T8S R20E

Uintah, Utah

ONSHORE OIL & GAS ORDER NO. 1
Approval of Operations on Onshore
Federal and Indian Oil and Gas Leases

All lease and/or unit operations are to be conducted in such a manner that full compliance is made with the applicable laws, regulations (CFR 43, Part 3160) and the approved Application for Permit to Drill. The operator is considered fully responsible for the actions of his subcontractors. A copy of the approved APD must be on location during construction, drilling, and completion operations.

RECEIVED: April 04, 2014

1. Formation Tops

The estimated tops of important geologic markers are as follows:

| <u>Formation Top</u> | <u>Top (TVD)</u> | <u>Comments</u> |
|----------------------|------------------------|----------------------|
| Uinta | Surface | |
| BMSW | 700' MD / 700' TVD | |
| Garden Gulch | 4,353' MD / 4,351' TVD | Oil & Associated Gas |
| Lower Green River* | 4,498' MD / 4,496' TVD | Oil & Associated Gas |
| Wasatch | 6,323' MD / 6,321' TVD | Oil & Associated Gas |
| TD | 6,523' MD / 6,521' TVD | |

Asterisks (*) denotes target pay intervals

All shows of fresh water and minerals will be reported and protected. A sample will be taken of any water flows and a water analysis furnished to the BLM. Oil and gas shows will be adequately tested for commercial possibilities, reported and protected by casing and cement.

2. BOP Equipment

- A) The BOPE shall be closed whenever the well is unattended. The Bureau of Land Management will be notified 24 hours prior to all BOPE pressure tests. The State of Utah, Division of Oil, Gas and Mining will be notified 24 hours prior to all BOPE pressure tests.
- B) The BOPE shall be closed whenever the well is unattended.
- C) As per 43 CFR 3160, Onshore Oil and Gas Order No. 2, Drilling Operations, Part A:
- 1) All BOPE connections subjected to well pressure will be flanged, welded, or clamped.
 - 2) Choke Manifold
 - 3) Tee blocks or targeted 'T's will be used and anchored to prevent slip and reduce vibration.
 - 4) Two adjustable chokes will be used in the choke manifold.
 - 5) All valves (except chokes) in kill line choke manifold and choke line will not restrict the flow.
 - 6) Pressure gauges in the well control system will be designed for drilling fluid.
- D) BOPE Testing:
- 1) BOPE shall be pressure tested when initially installed, whenever any seal subject to pressure testing is broken, or after repairs.
 - 2) All BOP tests will be performed with a test plug in place.
 - 3) BOP will be tested to full stack working pressure and annular preventer to 50% stack working pressure.

INTERVAL

0 1,033 MD / 1, 033' TVD

1,033 MD / 1, 033' TVD – 6,523' MD / 6,521' TVD

BOP EQUIPMENT

11" Diverter with Rotating Head

3,000# Ram Double BOP & Annular with Diverter & Rotating Head

NOTE: Drilling spool to accommodate choke and kill lines.

3. Casing and Float Equipment Program**CASING:**

| Directional Well | Hole Size | OD | Depth MD/TVD | Wt. | Grade & Connection | Cond. |
|-------------------------|------------------|-----------|------------------------|------------|-------------------------------|--------------|
| Surface | 11" | 8 5/8" | 1,033 MD / 1, 033' TVD | 24.0 ppf | J-55, LTC | New |
| Production | 7 7/8" | 5 1/2" | 6,523' MD / 6,521' TVD | 17.0 ppf | J-55, LTC | New |

CASING SPECIFICATIONS:

| Directional Well | Casing OD | Casing ID / Drift ID | Collapse (psi) | Int. Yield (psi) | Ten. Yield (lb) | Jt. Strength (lb) |
|------------------|-----------|----------------------|----------------|------------------|-----------------|-------------------|
| Surface | 8 5/8" | 8.097" / 7.972" | 1,370 | 2,950 | 381,000 | 244,000 |
| Production | 5 1/2" | 4.492" / 4.767" | 4,910 | 5,320 | 273,000 | 229,000 |

FLOAT EQUIPMENT:

SURFACE (8 5/8")

Float Shoe, 1 joint casing, float collar

Centralizers: 1 each 1st 4 Joints then every 4th joint to surface

PRODUCTION (5 1/2")

Float Shoe, 1 joint casing, float collar

Centralizers: 1 each 1st 4 Joints then every 3rd joint to 500' into surface casing**4. Cementing Programs**

CONDUCTOR (13 3/8"):

Ready Mix – Cement to surface

SURFACE (8 5/8")

Cement Top - Surface

Surface – 500'

Lead: 80 sks, Premium Lightweight Cmt w/ additives, 11.5 ppg, 2,97 cf/sk 50% excess

500' – 1,033 MD / 1, 033' TVD±

Tail: 115 sks Glass G Cement w/ additives, 15.8 ppg, 1.16 cf/sx, 50% excess

Note: The above volumes are based on a gauge-hole + 50% excess.

PRODUCTION (5 1/2")

Cement Top – 500'

500' - 4,000' TVD ±

Lead: 225 sks – Econocem Cement w/ 0.25 lbm Poly-E-Flake, 1% Granulite TR 1/4, 5 lbm Kol-Seal; 11.0 ppg; 3.54 cf/sx; 15% excess

4,000' – 6,523' MD / 6,521' TVD

Tail: 450 sks, Expandacem Cement w/ 0.25 lbm Poly-E-Flake, 1 lbm Granulite TR 1/4, 2 lbm Kol-Seal; 14.0 pp; 1.349 cf/sk; 15% excess

- A) For Surface casing, if cement falls or does not circulate to surface, cement will be topped off.
 B) Cement will not be placed down annulus with a 1" pipe unless BLM is contacted.
 C) The Bureau of Land Management will be notified 24 hours prior to running casing and cementing.
 D) As per 43 CFR 3160, Onshore Oil and Gas Order No.2, Drilling Operations, Part B:

- 1) All waiting on cement times shall be adequate to achieve a minimum of 500 psi compressive strength at the casing shoe (minimum of 8 hours) prior to drilling out.
- 2) Prior to drilling out cement, casing will be pressure tested to 1500 psi. Pressure decline must not be greater than 10% (150 psi) in 30 minutes.
- 3) Progress reports, Form 3160-5 "Sundry Notices and Reports on Wells", shall be filed with the Field Manager within 30 days after the work is completed.
- 4) Setting of each string of casing, size, grade, weight of casing set, hole size, setting depth, amounts and type of cement used, whether cement circulated or the top of the cement behind the casing, depth of cementing tools used, casing test method and results, and the date work was done. Show the spud date on the first reports submitted.
- 5) Temperature or bond logs must be submitted for each well where the casing cement was not circulated to the surface.
- 6) A pressure integrity test of each casing shoe shall be performed. Formation at the shoe shall be tested to a minimum of the mud weight equivalent anticipated to control the formation pressure to the next casing depth or at total depth of the well. This test shall be performed after drilling 5-10 feet of new hole.

5. Mud Program

The proposed circulating mediums to be employed in drilling are as follows:

| Interval | Mud Type | Viscosity | Fluid Loss | pH | Mud Wt. (ppg) |
|---|----------------|-----------|-----------------|----------|---------------|
| 0 – 1,033 MD / 1, 033' TVD | Water/Spud Mud | 32 | No Control (NC) | 7.0 -8.2 | <8.8 |
| 1,033 MD / 1, 033' TVD - 6,523' MD / 6,521' TVD | DAP System | 40 - 60 | 10 - 18 | 7.0-8.2 | <10.0 |

- A) For Surface Sufficient quantities of mud materials will be maintained or readily accessible for the purpose of assuring well control during the course of drilling operations. A mud test shall be performed every 24 hours after mudding up to determine, as applicable: density, viscosity, gel strength, filtration, and pH.
- B) The mud monitoring equipment on location will be installed by top of Green River and will be able to monitor at a minimum the pit volume totalizer (PVT), stroke counter, and flow sensor
- C) Flare line discharge will be located no less than 100 feet from the wellhead using straight or targeted 'T' and anchors.

6. Evaluation Program - Testing, Logging, and Coring

- A) Cores: None anticipated.
- B) Testing: None anticipated.
- C) Directional Drilling: Directional tools will be used to locate the bottom hole per the attached directional plan +/-.
- D) Open Hole Logs: TD to surface casing: resistivity, neutron density, gamma ray and caliper.
- E) Mud Logs: None anticipated.
- F) Formation to TD; record and monitor gas shows and record drill times (normal mud logging duties).

7. Anticipated Pressures and H.S.

- A) The expected bottom hole pressure is 3,500 – 3,650 psig. Normal pressures are anticipated from surface to approximately TD. These pressures will be controlled by a blowout preventer stack, annular BOP, choke manifold, mud/gas separator, surface equipment and drilling mud. A supply of barite to weight the mud to a balancing specific gravity, if necessary, will be on location.
- B) Maximum expected surface pressure will be based on the frac gradient of the casing shoe. The design of the casing assumes that the MASP will be the fracture pressure at the shoe less a column of gas.
- C) No hydrogen sulfide gas is anticipated, however if H₂S is encountered, the guidelines in Onshore Oil and Gas Order No. 6 will be complied with.

8. Other Information and Notification Requirements

- A) There shall be no deviation from the proposed drilling and/or workover program as approved. Any changes in operation must have prior approval from the **Utah Division of Oil, Gas and Mining**, and the BLM Vernal (when drilling on Federal leases).
 - 1) Anticipated starting date will be upon approval. It is anticipated that completion operations will begin within 15 days after the well has been drilled.
 - 2) It is anticipated that the drilling and completion of this well will take approximately 90 days.
- B) Notification Requirements for **Utah Division of Oil, Gas and Mining**:
 - **Within 24 hrs. of spud (Carol Daniels at 801/538-5284)**
 - **24 hrs. prior to testing BOP equipment (Dan Jarvis 801/538-5338 or 231-8956)**

- **24 hrs. prior to cementing or testing casing (Dan Jarvis)**
- **Within 24 hrs. of making any emergency changes to APD (Dustin Doucet 801/538-5281 or 733-0983)**

C) Notification Requirements BLM Vernal when drilling on Federal leases as follows: (Cade T Taylor @ cctaylor@blm.gov and [Blm ut vn opreport@blm.gov](mailto:Blm_ut_vn_opreport@blm.gov):

- **Within 24 hrs. of spud (Carol Daniels at 801/538-5284)**
- **24 hrs. prior to testing BOP equipment (Dan Jarvis 801/538-5338 or 231-8956)**
- **24 hrs. prior to cementing or testing casing (Dan Jarvis)**
- **Within 24 hrs. of making any emergency changes to APD (Dustin Doucet 801/538-5281 or 733-0983)**

D) Any changes in the program must be approved by the **Utah Division of Oil, Gas and Mining** and or the BLM Vernal Office. "Sundry Notices and Reports on Wells" (form 3160-5) must be filed for all changes of plans. Emergency approval may be obtained orally, but such approval does not waive the written report requirement.

1) Should the well be successfully completed for production, the BLM Pinedale Field Office must be notified when it is placed in a producing status. The notification shall provide, as a minimum, the following information items:

- Operator name, address, and telephone number.
- Well name and number.
- Well location (1/4 1/4, Section, Township, Range and P.M.)
- Date well was placed in a producing status (date of first production for which royalty will be paid).
- The nature of the well's production, (i.e., crude oil, or crude oil and casing head gas, or natural gas and entrained liquid hydrocarbons).
- The Federal or Indian lease prefix and number on which the well is located. As appropriate, the unit agreement name, number and participating area name. As appropriate, the communitization agreement number.

T8S, R20E, S.L.B.&M.**ULTRA RESOURCES, INC.**


Well location, THREE RIVERS #16-42L-820,
located as shown in the SE 1/4 NE 1/4 of
Section 16, T8S R20E, S.L.B.&M., Uintah County,
Utah.

BASIS OF ELEVATION

BENCH MARK (38EAM) LOCATED IN THE SW 1/4 OF SECTION
9, T7S, R20E, S.L.B.&M. TAKEN FROM THE PELICAN LAKE,
QUADRANGLE, UTAH, UTAH COUNTY, 7.5 MINUTE QUAD
(TOPOGRAPHIC MAP) PUBLISHED BY THE UNITED STATES
DEPARTMENT OF THE INTERIOR, GEOLOGICAL SURVEY. SAID
ELEVATION IS MARKED AS BEING 4942 FEET.

BASIS OF BEARINGS

BASIS OF BEARINGS IS A G.P.S. OBSERVATION.




SCALE
CERTIFICATE

THIS IS TO CERTIFY THAT THE ABOVE PLAT WAS PREPARED FROM
FIELD NOTES OF ACTUAL SURVEYS MADE BY ME OR UNDER MY
SUPERVISION AND THAT THE SAME ARE TRUE AND CORRECT TO THE
BEST OF MY KNOWLEDGE AND BELIEF.

REGISTERED LAND SURVEYOR
REGISTRATION NO. 161319
STATE OF UTAH

UINTAH ENGINEERING & LAND SURVEYING
85 SOUTH 200 EAST - VERNAL, UTAH 84078
(435) 789-1017

| | | |
|-------------------------|-------------------------------|-------------------------|
| SCALE 1" = 1000' | DATE SURVEYED: 01-13-14 | DATE DRAWN: 01-15-14 |
| PARTY B.H. M.P. S.S. | REFERENCES G.L.O. PLAT | |
| WEATHER COLD | FILE ULTRA RESOURCES, INC. | |

**LEGEND:**

- └─┘ = 90° SYMBOL
● = PROPOSED WELL HEAD.
▲ = SECTION CORNERS LOCATED.
△ = SECTION CORNERS RE-ESTABLISHED.
(Not Set on Ground.)

LINE TABLE

| LINE | DIRECTION | LENGTH |
|------|-------------|---------|
| L1 | N64°39'09"W | 571.35' |

NAD 83 (TARGET BOTTOM HOLE)

LATITUDE = 40°07'28.09" (40.124469)
LONGITUDE = 109°39'58.23" (109.666175)

NAD 27 (TARGET BOTTOM HOLE)

LATITUDE = 40°07'28.22" (40.124506)
LONGITUDE = 109°39'55.74" (109.665483)

NAD 83 (SURFACE LOCATION)

LATITUDE = 40°07'27.84" (40.124400)
LONGITUDE = 109°39'57.55" (109.665986)

NAD 27 (SURFACE LOCATION)


LATITUDE = 40°07'27.97" (40.124436)
LONGITUDE = 109°39'55.05" (109.665292)

RECEIVED: February 04, 2014

ULTRA RESOURCES, INC.
THREE RIVERS #16-42L-820 ON EXISTING #16-42-820
PAD
SECTION 16, T8S, R20E, U.S.B.&M.

PROCEED IN A WESTERLY DIRECTION FROM VERNAL, UTAH ALONG U.S. HIGHWAY 40 APPROXIMATELY 14.0 MILES TO THE JUNCTION OF THIS ROAD AND STATE HIGHWAY 88 TO THE SOUTH; EXIT LEFT AND PROCEED IN A SOUTHERLY DIRECTION APPROXIMATELY 7.0 MILES TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE SOUTHEAST; TURN LEFT AND PROCEED IN A SOUTHEASTERLY, THEN SOUTHERLY DIRECTION APPROXIMATELY 7.4 MILES TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE WEST; TURN RIGHT AND PROCEED IN A WESTERLY DIRECTION APPROXIMATELY 325' TO THE EXISTING ACCESS ROAD FOR THE THREE RIVERS #16-43-820 TO THE NORTH; PROCEED IN A NORTHERLY DIRECTION APPROXIMATELY 299' TO THE EXISTING ACCESS FOR THE THREE RIVERS #16-41-820 TO THE NORTHWEST; PROCEED IN A NORTHWESTERLY, THEN NORTHERLY DIRECTION APPROXIMATELY 1,337' TO THE EXISTING ACCESS TO THE NORTHEAST; PROCEED IN A NORTHEASTERLY DIRECTION APPROXIMATELY 294' TO THE PROPOSED LOCATION.

TOTAL DISTANCE FROM VERNAL, UTAH TO THE PROPOSED WELL LOCATION IS APPROXIMATELY 28.8 MILES.



**PROPOSED LOCATION:
THREE RIVERS #16-42L-820
ON EXISTING #16-42-820 PAD**

SEE TOPO "B"

LEGEND:

 **PROPOSED LOCATION**

ULTRA RESOURCES, INC.

**THREE RIVERS #16-42L-820 ON EXISTING #16-42-820 PAD
SECTION 16, T8S, R20E, S.L.B.&M.
2006' FNL 607' FEL**



Uintah Engineering & Land Surveying
85 South 200 East Vernal, Utah 84078
(435) 789-1017 * FAX (435) 789-1813




**ACCESS ROAD
MAP**

09 30 11
MONTH DAY YEAR

SCALE: 1:100,000 DRAWN BY: C.A.G. REV: 02-05-14L.S.

**A
TOPO**

**LEGEND:**

- EXISTING ROAD
 - - - - - PROPOSED ACCESS ROAD
 * * * * * EXISTING FENCE
 - . - . - . EXISTING POWER LINE
 ■ 18" CMP REQUIRED

ULTRA RESOURCES, INC.

THREE RIVERS #16-42L-820 ON EXISTING #16-42-820 PAD
 SECTION 16, T8S, R20E, S.L.B.&M.
 2006' FNL 607' FEL



Uintah Engineering & Land Surveying
 85 South 200 East Vernal, Utah 84078
 (435) 789-1017 * FAX (435) 789-1813




ACCESS ROAD
 MAP

09 30 11
 MONTH DAY YEAR

SCALE: 1" = 2000' DRAWN BY: C.A.G. REV: 02-05-14L.S.

B
 TOPO

**LEGEND:**

- | | |
|-------------------|-------------------------|
| ⊗ DISPOSAL WELLS | ● ABANDONED WELLS |
| ● PRODUCING WELLS | ● TEMPORARILY ABANDONED |
| ● SHUT IN WELLS | |

ULTRA RESOURCES, INC.

THREE RIVERS #16-42L-820 ON EXISTING #16-42-820 PAD
SECTION 16, T8S, R20E, S.L.B.&M.
2006' FNL 607' FEL



Uintah Engineering & Land Surveying
 85 South 200 East Vernal, Utah 84078
 (435) 789-1017 * FAX (435) 789-1813



TOPOGRAPHIC MAP
 09 30 11
 MONTH DAY YEAR
 SCALE: 1" = 2000' DRAWN BY: C.A.G. REV: 02-05-14L.S.





ULTRA RESOURCES, INC

Location: Three Rivers Slot: Three Rivers 16-42L-820 (2006' FNL & 607' FEL)
 Field: UINTAH COUNTY Well: Three Rivers 16-42L-820
 Facility: Sec.16-T8S-R20E Wellbore: Three Rivers 16-42L-820 PWB

Targets



| Name | MD (ft) | TVD (ft) | Local N (ft) | Local E (ft) | Grid East (US ft) | Grid North (US ft) | Latitude | Longitude |
|---|---------|----------|--------------|--------------|-------------------|--------------------|---------------|----------------|
| Three Rivers 16-42L-820 Target On Plat 1980' FNL & 660' FEL | | 4200.00 | 25.30 | -52.82 | 2153171.26 | 7219318.99 | 40°07'28.08"N | 109°39'58.23"W |

Well Profile Data

| Design Comment | MD (ft) | Inc (°) | Az (°) | TVD (ft) | Local N (ft) | Local E (ft) | DLS (°/100ft) | VS (ft) |
|--------------------|---------|---------|---------|----------|--------------|--------------|---------------|---------|
| Tie On | 13.00 | 0.000 | 295.591 | 13.00 | 0.00 | 0.00 | 0.00 | 0.00 |
| End of Tangent | 1000.00 | 0.000 | 295.591 | 1000.00 | 0.00 | 0.00 | 0.00 | 0.00 |
| Build (S) | 1250.00 | 5.000 | 295.591 | 1249.68 | 4.71 | -9.83 | 2.00 | 10.90 |
| End of Tangent (S) | 1671.85 | 5.000 | 295.591 | 1669.92 | 20.59 | -42.99 | 0.00 | 47.67 |
| Drop (S) | 1921.85 | 0.000 | 295.591 | 1919.61 | 25.30 | -52.82 | 2.00 | 58.57 |
| End of Tangent | 6523.24 | 0.000 | 295.591 | 6521.00 | 25.30 | -52.82 | 0.00 | 58.57 |

Location Information

| | | | | | | |
|--|--------------|--------------|--|--------------------|----------------|-----------------|
| City Name | | | Grid East (US ft) | Grid North (US ft) | Latitude | Longitude |
| Sec. 16-T8S-R20E | | | 2150638.025 | 7217204.539 | 40°07'07.709"N | 109°40'31.379"W |
| Slot | Local N (ft) | Local E (ft) | Grid East (US ft) | Grid North (US ft) | Latitude | Longitude |
| Three Rivers 16-42L-820 (2006' FNL & 607' FEL) | 2037.25 | 2627.90 | 2153324.586 | 7219294.783 | 40°07'27.840"N | 109°39'57.550"W |
| Capstar 321 (RT) to Mud line (At Slot: Three Rivers 16-42L-820 (2006' FNL & 607' FEL)) | | | | | | 4716ft |
| Mean Sea Level to Mud line (At Slot: Three Rivers 16-42L-820 (2006' FNL & 607' FEL)) | | | | | | 0ft |
| Capstar 321 (RT) to Mean Sea Level | | | | | | 4716ft |
| Plot reference wellpath is Three Rivers 16-42L-820 PWB | | | | | | |
| True vertical depths are referenced to Capstar 321 (RT) | | | Grid System: NAD83 / Lambert Utah SP, Central Zone (4302), US feet | | | |
| Measured depths are referenced to Capstar 321 (RT) | | | North Reference: True north | | | |
| Capstar 321 (RT) to Mean Sea Level: 4716 feet | | | Scale: True distance | | | |
| Mean Sea Level to Mud line (At Slot: Three Rivers 16-42L-820 (2006' FNL & 607' FEL)): 0 feet | | | Depths are in feet | | | |
| Coordinates are in feet referenced to Slot | | | Created by: ewilliams on 1/29/2014 | | | |





Planned Wellpath Report

Three Rivers 16-42L-820 PWP

Page 1 of 5



REFERENCE WELLPATH IDENTIFICATION

| | | | |
|----------|----------------------|----------|--|
| Operator | ULTRA RESOURCES, INC | Slot | Three Rivers 16-42L-820 (2006' FNL & 607' FEL) |
| Area | Three Rivers | Well | Three Rivers 16-42L-820 |
| Field | UINTAH COUNTY | Wellbore | Three Rivers 16-42L-820 PWB |
| Facility | Sec.16-T8S-R20E | | |

REPORT SETUP INFORMATION

| | | | |
|---------------------|---|----------------------|---|
| Projection System | NAD83 / Lambert Utah SP, Central Zone (4302), US feet | Software System | WellArchitect® 3.0.0 |
| North Reference | True | User | Ewilliams |
| Scale | 0.999912 | Report Generated | 1/29/2014 at 11:05:37 AM |
| Convergence at slot | 1.17° East | Database/Source file | WellArchitectDB/Three_Rivers_16-42L-820_PWB.xml |

WELLPATH LOCATION

| | Local coordinates | | Grid coordinates | | Geographic coordinates | |
|-----------------------|-------------------|----------|------------------|-----------------|------------------------|-----------------|
| | North[ft] | East[ft] | Easting[US ft] | Northing[US ft] | Latitude | Longitude |
| Slot Location | 2037.25 | 2627.90 | 2153224.59 | 7219294.78 | 40°07'27.840"N | 109°39'57.550"W |
| Facility Reference Pt | | | 2150639.03 | 7217204.54 | 40°07'07.709"N | 109°40'31.379"W |
| Field Reference Pt | | | 2156630.96 | 7236613.42 | 40°10'18.270"N | 109°39'09.100"W |

WELLPATH DATUM

| | | | |
|--------------------------|-------------------|---|-------------------|
| Calculation method | Minimum curvature | Capstar 321 (RT) to Facility Vertical Datum | 4716.00ft |
| Horizontal Reference Pt | Slot | Capstar 321 (RT) to Mean Sea Level | 4716.00ft |
| Vertical Reference Pt | Capstar 321 (RT) | Capstar 321 (RT) to Mud Line at Slot (Three Rivers 16-42L-820 (2006' FNL & 607' FEL)) | 4716.00ft |
| MD Reference Pt | Capstar 321 (RT) | Section Origin | N 0.00, E 0.00 ft |
| Field Vertical Reference | Mean Sea Level | Section Azimuth | 295.59° |



Planned Wellpath Report

Three Rivers 16-42L-820 PWP

Page 2 of 5



REFERENCE WELLPATH IDENTIFICATION

| | | | |
|----------|----------------------|----------|--|
| Operator | ULTRA RESOURCES, INC | Slot | Three Rivers 16-42L-820 (2006' FNL & 607' FEL) |
| Area | Three Rivers | Well | Three Rivers 16-42L-820 |
| Field | UINTAH COUNTY | Wellbore | Three Rivers 16-42L-820 PWB |
| Facility | Sec.16-T8S-R20E | | |

WELLPATH DATA (77 stations) † = interpolated/extrapolated station

| MD [ft] | Inclination [°] | Azimuth [°] | TVD [ft] | Vert Sect [ft] | North [ft] | East [ft] | DLS [°/100ft] | Comments |
|------------|--------------------|----------------|----------------------|-------------------|---------------|--------------|------------------|-------------|
| 0.00† | 0.000 | 295.591 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | |
| 13.00 | 0.000 | 295.591 | 13.00 | 0.00 | 0.00 | 0.00 | 0.00 | |
| 113.00† | 0.000 | 295.591 | 113.00 | 0.00 | 0.00 | 0.00 | 0.00 | |
| 120.00† | 0.000 | 295.591 | 120.00 | 0.00 | 0.00 | 0.00 | 0.00 | Base Gravel |
| 213.00† | 0.000 | 295.591 | 213.00 | 0.00 | 0.00 | 0.00 | 0.00 | |
| 313.00† | 0.000 | 295.591 | 313.00 | 0.00 | 0.00 | 0.00 | 0.00 | |
| 413.00† | 0.000 | 295.591 | 413.00 | 0.00 | 0.00 | 0.00 | 0.00 | |
| 513.00† | 0.000 | 295.591 | 513.00 | 0.00 | 0.00 | 0.00 | 0.00 | |
| 613.00† | 0.000 | 295.591 | 613.00 | 0.00 | 0.00 | 0.00 | 0.00 | |
| 700.00† | 0.000 | 295.591 | 700.00 | 0.00 | 0.00 | 0.00 | 0.00 | BMSW |
| 713.00† | 0.000 | 295.591 | 713.00 | 0.00 | 0.00 | 0.00 | 0.00 | |
| 813.00† | 0.000 | 295.591 | 813.00 | 0.00 | 0.00 | 0.00 | 0.00 | |
| 913.00† | 0.000 | 295.591 | 913.00 | 0.00 | 0.00 | 0.00 | 0.00 | |
| 1000.00 | 0.000 | 295.591 | 1000.00 | 0.00 | 0.00 | 0.00 | 0.00 | |
| 1013.00† | 0.260 | 295.591 | 1013.00 | 0.03 | 0.01 | -0.03 | 2.00 | |
| 1113.00† | 2.260 | 295.591 | 1112.97 | 2.23 | 0.96 | -2.01 | 2.00 | |
| 1213.00† | 4.260 | 295.591 | 1212.80 | 7.91 | 3.42 | -7.14 | 2.00 | |
| 1250.00 | 5.000 | 295.591 | 1249.68 | 10.90 | 4.71 | -9.83 | 2.00 | |
| 1313.00† | 5.000 | 295.591 | 1312.44 | 16.39 | 7.08 | -14.78 | 0.00 | |
| 1413.00† | 5.000 | 295.591 | 1412.06 | 25.11 | 10.85 | -22.64 | 0.00 | |
| 1513.00† | 5.000 | 295.591 | 1511.68 | 33.82 | 14.61 | -30.51 | 0.00 | |
| 1613.00† | 5.000 | 295.591 | 1611.30 | 42.54 | 18.37 | -38.37 | 0.00 | |
| 1671.85 | 5.000 | 295.591 | 1669.92 | 47.67 | 20.59 | -42.99 | 0.00 | |
| 1713.00† | 4.177 | 295.591 | 1710.95 | 50.96 | 22.01 | -45.96 | 2.00 | |
| 1813.00† | 2.177 | 295.591 | 1810.79 | 56.50 | 24.41 | -50.96 | 2.00 | |
| 1913.00† | 0.177 | 295.591 | 1910.76 | 58.56 | 25.29 | -52.81 | 2.00 | |
| 1921.85 | 0.000 | 295.591 | 1919.61 ¹ | 58.57 | 25.30 | -52.82 | 2.00 | |
| 2013.00† | 0.000 | 295.591 | 2010.76 | 58.57 | 25.30 | -52.82 | 0.00 | |
| 2113.00† | 0.000 | 295.591 | 2110.76 | 58.57 | 25.30 | -52.82 | 0.00 | |
| 2213.00† | 0.000 | 295.591 | 2210.76 | 58.57 | 25.30 | -52.82 | 0.00 | |
| 2313.00† | 0.000 | 295.591 | 2310.76 | 58.57 | 25.30 | -52.82 | 0.00 | |
| 2413.00† | 0.000 | 295.591 | 2410.76 | 58.57 | 25.30 | -52.82 | 0.00 | |
| 2513.00† | 0.000 | 295.591 | 2510.76 | 58.57 | 25.30 | -52.82 | 0.00 | |
| 2613.00† | 0.000 | 295.591 | 2610.76 | 58.57 | 25.30 | -52.82 | 0.00 | |
| 2713.00† | 0.000 | 295.591 | 2710.76 | 58.57 | 25.30 | -52.82 | 0.00 | |
| 2813.00† | 0.000 | 295.591 | 2810.76 | 58.57 | 25.30 | -52.82 | 0.00 | |
| 2913.00† | 0.000 | 295.591 | 2910.76 | 58.57 | 25.30 | -52.82 | 0.00 | |
| 3013.00† | 0.000 | 295.591 | 3010.76 | 58.57 | 25.30 | -52.82 | 0.00 | |
| 3113.00† | 0.000 | 295.591 | 3110.76 | 58.57 | 25.30 | -52.82 | 0.00 | |
| 3213.00† | 0.000 | 295.591 | 3210.76 | 58.57 | 25.30 | -52.82 | 0.00 | |
| 3313.00† | 0.000 | 295.591 | 3310.76 | 58.57 | 25.30 | -52.82 | 0.00 | |
| 3413.00† | 0.000 | 295.591 | 3410.76 | 58.57 | 25.30 | -52.82 | 0.00 | |
| 3513.00† | 0.000 | 295.591 | 3510.76 | 58.57 | 25.30 | -52.82 | 0.00 | |
| 3613.00† | 0.000 | 295.591 | 3610.76 | 58.57 | 25.30 | -52.82 | 0.00 | |
| 3713.00† | 0.000 | 295.591 | 3710.76 | 58.57 | 25.30 | -52.82 | 0.00 | |



Planned Wellpath Report

Three Rivers 16-42L-820 PWP

Page 3 of 5



| REFERENCE WELLPATH IDENTIFICATION | | | |
|-----------------------------------|----------------------|----------|--|
| Operator | ULTRA RESOURCES, INC | Slot | Three Rivers 16-42L-820 (2006' FNL & 607' FEL) |
| Area | Three Rivers | Well | Three Rivers 16-42L-820 |
| Field | UINTAH COUNTY | Wellbore | Three Rivers 16-42L-820 PWB |
| Facility | Sec.16-T8S-R20E | | |

| WELLPATH DATA (77 stations) † = interpolated/extrapolated station | | | | | | | | |
|---|--------------------|----------------|-------------|-------------------|---------------|--------------|------------------|-------------------|
| MD [ft] | Inclination [°] | Azimuth [°] | TVD [ft] | Vert Sect [ft] | North [ft] | East [ft] | DLS [°/100ft] | Comments |
| 3813.00† | 0.000 | 295.591 | 3810.76 | 58.57 | 25.30 | -52.82 | 0.00 | |
| 3913.00† | 0.000 | 295.591 | 3910.76 | 58.57 | 25.30 | -52.82 | 0.00 | |
| 4013.00† | 0.000 | 295.591 | 4010.76 | 58.57 | 25.30 | -52.82 | 0.00 | |
| 4113.00† | 0.000 | 295.591 | 4110.76 | 58.57 | 25.30 | -52.82 | 0.00 | |
| 4213.00† | 0.000 | 295.591 | 4210.76 | 58.57 | 25.30 | -52.82 | 0.00 | |
| 4313.00† | 0.000 | 295.591 | 4310.76 | 58.57 | 25.30 | -52.82 | 0.00 | |
| 4353.24† | 0.000 | 295.591 | 4351.00 | 58.57 | 25.30 | -52.82 | 0.00 | Garden Gulch |
| 4413.00† | 0.000 | 295.591 | 4410.76 | 58.57 | 25.30 | -52.82 | 0.00 | |
| 4498.24† | 0.000 | 295.591 | 4496.00 | 58.57 | 25.30 | -52.82 | 0.00 | Lower Green River |
| 4513.00† | 0.000 | 295.591 | 4510.76 | 58.57 | 25.30 | -52.82 | 0.00 | |
| 4613.00† | 0.000 | 295.591 | 4610.76 | 58.57 | 25.30 | -52.82 | 0.00 | |
| 4713.00† | 0.000 | 295.591 | 4710.76 | 58.57 | 25.30 | -52.82 | 0.00 | |
| 4813.00† | 0.000 | 295.591 | 4810.76 | 58.57 | 25.30 | -52.82 | 0.00 | |
| 4913.00† | 0.000 | 295.591 | 4910.76 | 58.57 | 25.30 | -52.82 | 0.00 | |
| 5013.00† | 0.000 | 295.591 | 5010.76 | 58.57 | 25.30 | -52.82 | 0.00 | |
| 5113.00† | 0.000 | 295.591 | 5110.76 | 58.57 | 25.30 | -52.82 | 0.00 | |
| 5213.00† | 0.000 | 295.591 | 5210.76 | 58.57 | 25.30 | -52.82 | 0.00 | |
| 5313.00† | 0.000 | 295.591 | 5310.76 | 58.57 | 25.30 | -52.82 | 0.00 | |
| 5413.00† | 0.000 | 295.591 | 5410.76 | 58.57 | 25.30 | -52.82 | 0.00 | |
| 5513.00† | 0.000 | 295.591 | 5510.76 | 58.57 | 25.30 | -52.82 | 0.00 | |
| 5613.00† | 0.000 | 295.591 | 5610.76 | 58.57 | 25.30 | -52.82 | 0.00 | |
| 5713.00† | 0.000 | 295.591 | 5710.76 | 58.57 | 25.30 | -52.82 | 0.00 | |
| 5813.00† | 0.000 | 295.591 | 5810.76 | 58.57 | 25.30 | -52.82 | 0.00 | |
| 5913.00† | 0.000 | 295.591 | 5910.76 | 58.57 | 25.30 | -52.82 | 0.00 | |
| 6013.00† | 0.000 | 295.591 | 6010.76 | 58.57 | 25.30 | -52.82 | 0.00 | |
| 6113.00† | 0.000 | 295.591 | 6110.76 | 58.57 | 25.30 | -52.82 | 0.00 | |
| 6213.00† | 0.000 | 295.591 | 6210.76 | 58.57 | 25.30 | -52.82 | 0.00 | |
| 6313.00† | 0.000 | 295.591 | 6310.76 | 58.57 | 25.30 | -52.82 | 0.00 | |
| 6323.24† | 0.000 | 295.591 | 6321.00 | 58.57 | 25.30 | -52.82 | 0.00 | Wasatch |
| 6413.00† | 0.000 | 295.591 | 6410.76 | 58.57 | 25.30 | -52.82 | 0.00 | |
| 6513.00† | 0.000 | 295.591 | 6510.76 | 58.57 | 25.30 | -52.82 | 0.00 | |
| 6523.24 | 0.000 | 295.591 | 6521.00 | 58.57 | 25.30 | -52.82 | 0.00 | TD |



Planned Wellpath Report

Three Rivers 16-42L-820 PWP

Page 4 of 5



REFERENCE WELLPATH IDENTIFICATION

| | | | |
|----------|----------------------|----------|--|
| Operator | ULTRA RESOURCES, INC | Slot | Three Rivers 16-42L-820 (2006' FNL & 607' FEL) |
| Area | Three Rivers | Well | Three Rivers 16-42L-820 |
| Field | UINTAH COUNTY | Wellbore | Three Rivers 16-42L-820 PWB |
| Facility | Sec.16-T8S-R20E | | |

HOLE & CASING SECTIONS - Ref Wellbore: Three Rivers 16-42L-820 PWB Ref Wellpath: Three Rivers 16-42L-820 PWP

| String/Diameter | Start MD [ft] | End MD [ft] | Interval [ft] | Start TVD [ft] | End TVD [ft] | Start N/S [ft] | Start E/W [ft] | End N/S [ft] | End E/W [ft] |
|-------------------------|---------------|-------------|---------------|----------------|--------------|----------------|----------------|--------------|--------------|
| 16in Conductor | 13.00 | 120.00 | 107.00 | 13.00 | 120.00 | 0.00 | 0.00 | 0.00 | 0.00 |
| 12.25in Open Hole | 120.00 | 1000.00 | 880.00 | 120.00 | 1000.00 | 0.00 | 0.00 | 0.00 | 0.00 |
| 8.625in Casing Surface | 13.00 | 1000.00 | 987.00 | 13.00 | 1000.00 | 0.00 | 0.00 | 0.00 | 0.00 |
| 7.875in Open Hole | 1000.00 | 6523.24 | 5523.24 | 1000.00 | 6521.00 | 0.00 | 0.00 | 25.30 | -52.82 |
| 5.5in Casing Production | 13.00 | 6523.24 | 6510.24 | 13.00 | 6521.00 | 0.00 | 0.00 | 25.30 | -52.82 |

TARGETS

| Name | MD [ft] | TVD [ft] | North [ft] | East [ft] | Grid East [US ft] | Grid North [US ft] | Latitude | Longitude | Shape |
|---|---------|----------|------------|-----------|-------------------|--------------------|----------------|-----------------|-------|
| 1) Three Rivers 16-42L-820 Target On Plat 1980' FNL & 660' FEL | | 4200.00 | 25.30 | -52.82 | 2153171.26 | 7219318.99 | 40°07'28.090"N | 109°39'58.230"W | point |

CONFIDENTIAL



Planned Wellpath Report

Three Rivers 16-42L-820 PWP

Page 5 of 5

**REFERENCE WELLPATH IDENTIFICATION**

| | | | |
|----------|----------------------|----------|--|
| Operator | ULTRA RESOURCES, INC | Slot | Three Rivers 16-42L-820 (2006' FNL & 607' FEL) |
| Area | Three Rivers | Well | Three Rivers 16-42L-820 |
| Field | UINTAH COUNTY | Wellbore | Three Rivers 16-42L-820 PWB |
| Facility | Sec.16-T8S-R20E | | |

WELLPATH COMMENTS

| MD [ft] | Inclination [°] | Azimuth [°] | TVD [ft] | Comment |
|------------|--------------------|----------------|-------------|-------------------|
| 120.00 | 0.000 | 295.591 | 120.00 | Base Gravel |
| 700.00 | 0.000 | 295.591 | 700.00 | BMSW |
| 4353.24 | 0.000 | 295.591 | 4351.00 | Garden Gulch |
| 4498.24 | 0.000 | 295.591 | 4496.00 | Lower Green River |
| 6323.24 | 0.000 | 295.591 | 6321.00 | Wasatch |
| 6523.24 | 0.000 | 295.591 | 6521.00 | TD |

CONFIDENTIAL

BOP Equipment

3000psi WP




EXHIBIT "F"



2580 Creekview Road
Moab, Utah 84532
435/719-2018

February 4, 2014

Mrs. Diana Mason
State of Utah
Division of Oil Gas and Mining
P.O. Box 145801
Salt Lake City, Utah 84114-5801

RE: Request for Exception to Spacing – Ultra Resources, Inc. **Three Rivers 16-42L-820**

Surface Location: 2006' FNL & 607' FEL, SE/4 NE/4, Section 16, T8S, R20E,

Target Location: 1980' FNL & 660' FEL, SE/4 NE/4, Section 16, T8S, R20E,
SLB&M, Uintah County, Utah

Dear Diana:

Ultra Resources, Inc. respectfully submits this request for exception to spacing (R649-3-11) based on geology since the well is located less than 460 feet to the drilling unit boundary. Ultra Resources, Inc. is the only owner and operator within 460 feet of the surface and target location as well as all points along the intended well bore path, and neither the surface nor target locations are within 460 feet of any uncommitted tracts or a unit boundary.

Thank you very much for your timely consideration of this application. Please feel free to contact Debbie Ghani of Ultra Resources, Inc. at 303-645-9810 or myself should you have any questions or need additional information.

Sincerely,

A handwritten signature in blue ink that reads "Don Hamilton".

Don Hamilton
Agent for Ultra Resources, Inc.

cc: Cally McKee, Ultra Resources, Inc.
Debbie Ghani, Ultra Resources, Inc.

RECEIVED: February 04, 2014

ULTRA RESOURCES, INC.

LOCATION LAYOUT FOR


THREE RIVERS #16-42L-820 ON EXISTING #16-42-820 PAD
SECTION 16, T8S, R20E, S.L.B.&M.
2006' FNL 607' FEL

FIGURE #1

SCALE: 1" = 50'

DATE: 01-14-13

DRAWN BY: S.S.



FINISHED GRADE ELEV. AT LOC. STAKE = 4702.6'

UINTAH ENGINEERING & LAND SURVEYING

85 So. 200 East * Vernal, Utah 84078 * (435) 789-1017

RECEIVED: February 04, 2014

ULTRA RESOURCES, INC.



TYPICAL CROSS SECTIONS FOR

THREE RIVERS #16-42L-820 ON EXISTING #16-42-820 PAD
SECTION 16, T8S, R20E, S.L.B.&M.
2006' FNL 607' FEL

FIGURE #2

X-Section
Scale
1" = 50'

DATE: 01-14-13
DRAWN BY: S.S.



* NOTE:
FILL QUANTITY INCLUDES
5% FOR COMPACTION

APPROXIMATE ACREAGE

WELL SITE DISTURBANCE NEW CONSTRUCTION = ± 0.294 ACRES
EXISTING WELL SITE DISTURBANCE = ± 1.533 ACRES
TOTAL = ± 1.827 ACRES

APPROXIMATE YARDAGES

(6") Topsoil Stripping = 230 Cu. Yds.
(New Construction Only)
Remaining Location = 540 Cu. Yds.
TOTAL CUT = 770 CU. YDS.
FILL = 920 CU. YDS.

DEFICIT MATERIAL = <150> Cu. Yds.
Topsoil & Pit Backfill = 420 Cu. Yds.
(1/2 Pit Vol.)
DEFICIT UNBALANCE = <570> Cu. Yds.
(After Interim Rehabilitation)

UINTAH ENGINEERING & LAND SURVEYING
85 So. 200 East * Vernal, Utah 84078 * (435) 789-1017

RECEIVED: February 04, 2014

ULTRA RESOURCES, INC.

TYPICAL RIG LAYOUT FOR


THREE RIVERS #16-42L-820 ON EXISTING #16-42-820 PAD
SECTION 16, T8S, R20E, S.L.B.&M.
2006' FNL 607' FEL

FIGURE #3

SCALE: 1" = 50'

DATE: 01-14-13


DRAWN BY: S.S.



UINTAH ENGINEERING & LAND SURVEYING

85 So. 200 East * Vernal, Utah 84078 * (435) 789-1017

RECEIVED: February 04, 2014



API Number: 4304754269

Well Name: Three Rivers 16-42L-820



Township: T08.0S Range: R20.0E Section: 16 Meridian: S

Operator: ULTRA RESOURCES INC

Map Prepared: 3/6/2014
Map Produced by Diana Mason

| Wells Query | | Units | |
|------------------------------------|--|--------------|--|
| Status | | STATUS | |
| APD - Approved Permit | | ACTIVE | |
| DRL - Spudded (Drilling Commenced) | | EXPLORATORY | |
| GRW - Gas Injection | | GAS STORAGE | |
| GS - Gas Storage | | NF PP OIL | |
| LOC - New Location | | NF SECONDARY | |
| OPS - Operation Suspended | | PI OIL | |
| PA - Plugged Abandoned | | PP GAS | |
| PQW - Producing Gas Well | | PP GEOTHERML | |
| PQW - Producing Oil Well | | PP OIL | |
| SGW - Shut-in Gas Well | | SECONDARY | |
| SGW - Shut-in Oil Well | | TERMINATED | |
| TA - Temp. Abandoned | | | |
| TW - Test Well | | | |
| WOW - Water Disposal | | | |
| WW - Water Injection Well | | | |
| WSW - Water Supply Well | | | |

| Fields | STATUS |
|------------|--------|
| Unknown | |
| ABANDONED | |
| ACTIVE | |
| COMBINED | |
| INACTIVE | |
| STORAGE | |
| TERMINATED | |





Diana Mason <dianawhitney@utah.gov>

Ultra Petroleum Wells Part 2

Jeff Conley <jconley@utah.gov>

Wed, Mar 12, 2014 at 10:31 AM

To: Diana Mason <dianawhitney@utah.gov>, Bradley Hill <bradhill@utah.gov>

Cc: starpoint <starpoint@etv.net>, Jim Davis <jimdavis1@utah.gov>

Hello,

The following wells have been approved by SITLA including arch and paleo:

(4304754269) Three Rivers 16-42L-820

(4304754290) Three Rivers 16-32T-820

(4304754292) Three Rivers 16-42T-820

Thank you,

Jeff Conley
SITLA Resource Specialist
jconley@utah.gov
801-538-5157

CONFIDENTIAL

| | | | | |
|--|--|-------|--|--|
| Well Name | ULTRA RESOURCES INC Three Rivers 16-42L-820 43047542690000 | | | |
| String | SURF | PROD | | |
| Casing Size(") | 8.625 | 5.500 | | |
| Setting Depth (TVD) | 1033 | 6521 | | |
| Previous Shoe Setting Depth (TVD) | 0 | 1033 | | |
| Max Mud Weight (ppg) | 8.8 | 10.0 | | |
| BOPE Proposed (psi) | 1000 | 3000 | | |
| Casing Internal Yield (psi) | 2950 | 5320 | | |
| Operators Max Anticipated Pressure (psi) | 3500 | 10.3 | | |

| | | | |
|---|--|-------|--|
| Calculations | SURF String | 8.625 | " |
| Max BHP (psi) | .052*Setting Depth*MW= | 473 | |
| | | | BOPE Adequate For Drilling And Setting Casing at Depth? |
| MASP (Gas) (psi) | Max BHP-(0.12*Setting Depth)= | 349 | YES <input type="checkbox"/> diverter with rotating head |
| MASP (Gas/Mud) (psi) | Max BHP-(0.22*Setting Depth)= | 246 | YES <input type="checkbox"/> OK |
| | | | *Can Full Expected Pressure Be Held At Previous Shoe? |
| Pressure At Previous Shoe | Max BHP-.22*(Setting Depth - Previous Shoe Depth)= | 246 | NO <input type="checkbox"/> OK |
| Required Casing/BOPE Test Pressure= | | 1033 | psi |
| *Max Pressure Allowed @ Previous Casing Shoe= | | 0 | psi *Assumes 1psi/ft frac gradient |


| | | | |
|---|--|-------|---|
| Calculations | PROD String | 5.500 | " |
| Max BHP (psi) | .052*Setting Depth*MW= | 3391 | |
| | | | BOPE Adequate For Drilling And Setting Casing at Depth? |
| MASP (Gas) (psi) | Max BHP-(0.12*Setting Depth)= | 2608 | YES <input type="checkbox"/> 3M BOP, dbl ram, annular with diverter and rotating head |
| MASP (Gas/Mud) (psi) | Max BHP-(0.22*Setting Depth)= | 1956 | YES <input type="checkbox"/> Ok |
| | | | *Can Full Expected Pressure Be Held At Previous Shoe? |
| Pressure At Previous Shoe | Max BHP-.22*(Setting Depth - Previous Shoe Depth)= | 2184 | NO <input type="checkbox"/> OK |
| Required Casing/BOPE Test Pressure= | | 3000 | psi |
| *Max Pressure Allowed @ Previous Casing Shoe= | | 1033 | psi *Assumes 1psi/ft frac gradient |

| | | | |
|---|--|--|---|
| Calculations | String | | " |
| Max BHP (psi) | .052*Setting Depth*MW= | | |
| | | | BOPE Adequate For Drilling And Setting Casing at Depth? |
| MASP (Gas) (psi) | Max BHP-(0.12*Setting Depth)= | | NO <input type="checkbox"/> |
| MASP (Gas/Mud) (psi) | Max BHP-(0.22*Setting Depth)= | | NO <input type="checkbox"/> |
| | | | *Can Full Expected Pressure Be Held At Previous Shoe? |
| Pressure At Previous Shoe | Max BHP-.22*(Setting Depth - Previous Shoe Depth)= | | NO <input type="checkbox"/> |
| Required Casing/BOPE Test Pressure= | | | psi |
| *Max Pressure Allowed @ Previous Casing Shoe= | | | psi *Assumes 1psi/ft frac gradient |

| | | | |
|---|--|--|---|
| Calculations | String | | " |
| Max BHP (psi) | .052*Setting Depth*MW= | | |
| | | | BOPE Adequate For Drilling And Setting Casing at Depth? |
| MASP (Gas) (psi) | Max BHP-(0.12*Setting Depth)= | | NO <input type="checkbox"/> |
| MASP (Gas/Mud) (psi) | Max BHP-(0.22*Setting Depth)= | | NO <input type="checkbox"/> |
| | | | *Can Full Expected Pressure Be Held At Previous Shoe? |
| Pressure At Previous Shoe | Max BHP-.22*(Setting Depth - Previous Shoe Depth)= | | NO <input type="checkbox"/> |
| Required Casing/BOPE Test Pressure= | | | psi |
| *Max Pressure Allowed @ Previous Casing Shoe= | | | psi *Assumes 1psi/ft frac gradient |

43047542690000 Three Rivers 16-42L-820

Casing Schematic



| | | | |
|--------------|---|-------------|--------------|
| Well name: | 43047542690000 Three Rivers 16-42L-820 | | |
| Operator: | ULTRA RESOURCES INC | | |
| String type: | Surface | Project ID: | 43-047-54269 |
| Location: | UINTAH COUNTY | | |

Design parameters:**Collapse**

Mud weight: 8.800 ppg
Design is based on evacuated pipe.

Minimum design factors:**Collapse:**

Design factor 1.125

Burst:

Design factor 1.00

Environment:

H2S considered? No
Surface temperature: 74 °F
Bottom hole temperature: 88 °F
Temperature gradient: 1.40 °F/100ft
Minimum section length: 100 ft

Cement top: 239 ft

Burst

Max anticipated surface pressure: 909 psi
Internal gradient: 0.120 psi/ft
Calculated BHP 1,033 psi

No backup mud specified.

Tension:

8 Round STC: 1.80 (J)
8 Round LTC: 1.70 (J)
Buttress: 1.60 (J)
Premium: 1.50 (J)
Body yield: 1.50 (B)

Tension is based on buoyed weight.
Neutral point: 897 ft

Completion type is subs

Directional well information:

Kick-off point 1000 ft
Departure at shoe: 0 ft
Maximum dogleg: 2 °/100ft
Inclination at shoe: .66 °

Re subsequent strings:

Next setting depth: 6,399 ft
Next mud weight: 10.000 ppg
Next setting BHP: 3,324 psi
Fracture mud wt: 19.250 ppg
Fracture depth: 1,033 ft
Injection pressure: 1,033 psi

| Run Seq | Segment Length (ft) | Size (in) | Nominal Weight (lbs/ft) | Grade | End Finish | True Vert Depth (ft) | Measured Depth (ft) | Drift Diameter (in) | Est. Cost (\$) |
|---------|---------------------|-------------------------|-------------------------|------------------|----------------------|----------------------|---------------------|-------------------------|-----------------------|
| 1 | 1033 | 8.625 | 24.00 | J-55 | ST&C | 1033 | 1033 | 7.972 | 5318 |
| Run Seq | Collapse Load (psi) | Collapse Strength (psi) | Collapse Design Factor | Burst Load (psi) | Burst Strength (psi) | Burst Design Factor | Tension Load (kips) | Tension Strength (kips) | Tension Design Factor |
| 1 | 472 | 1343 | 2.843 | 1033 | 2950 | 2.86 | 21.5 | 244 | 11.34 J |

Prepared Helen Sadik-Macdonald
by: Div of Oil, Gas & Mining

Phone: 801 538-5357
FAX: 801-359-3940

Date: April 3, 2014
Salt Lake City, Utah

Remarks:

Collapse is based on a vertical depth of 1033 ft, a mud weight of 8.8 ppg. The casing is considered to be evacuated for collapse purposes. Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.

Burst strength is not adjusted for tension.

Collapse strength is (biaxially) derated for doglegs in directional wells by multiplying the tensile stress by the cross section area to calculate a

| | | | |
|--------------|---|-------------|--------------|
| Well name: | 43047542690000 Three Rivers 16-42L-820 | | |
| Operator: | ULTRA RESOURCES INC | | |
| String type: | Production | Project ID: | 43-047-54269 |
| Location: | UINTAH COUNTY | | |

Design parameters:**Collapse**

Mud weight: 10.000 ppg
Design is based on evacuated pipe.

Minimum design factors:**Collapse:**

Design factor 1.125

Environment:

H2S considered? No
Surface temperature: 74 °F
Bottom hole temperature: 165 °F
Temperature gradient: 1.40 °F/100ft
Minimum section length: 1,000 ft

Burst:

Design factor 1.00

Cement top: 1,108 ft

Burst

Max anticipated surface pressure: 1,953 psi
Internal gradient: 0.220 psi/ft
Calculated BHP 3,387 psi

No backup mud specified.

Tension:

8 Round STC: 1.80 (J)
8 Round LTC: 1.80 (J)
Buttress: 1.60 (J)
Premium: 1.50 (J)
Body yield: 1.60 (B)

Tension is based on air weight.
Neutral point: 5,534 ft

Completion type is subs

Directional Info - Build & Drop

Kick-off point 1000 ft
Departure at shoe: 59 ft
Maximum dogleg: 2 °/100ft
Inclination at shoe: 0 °

| Run Seq | Segment Length (ft) | Size (in) | Nominal Weight (lbs/ft) | Grade | End Finish | True Vert Depth (ft) | Measured Depth (ft) | Drift Diameter (in) | Est. Cost (\$) |
|---------|---------------------|-------------------------|-------------------------|------------------|----------------------|----------------------|---------------------|-------------------------|-----------------------|
| 1 | 6523 | 5.5 | 17.00 | J-55 | LT&C | 6521 | 6523 | 4.767 | 25271 |
| Run Seq | Collapse Load (psi) | Collapse Strength (psi) | Collapse Design Factor | Burst Load (psi) | Burst Strength (psi) | Burst Design Factor | Tension Load (kips) | Tension Strength (kips) | Tension Design Factor |
| 1 | 3387 | 4910 | 1.449 | 3387 | 5320 | 1.57 | 110.9 | 247 | 2.23 J |

Prepared Helen Sadik-Macdonald
by: Div of Oil, Gas & Mining

Phone: 801 538-5357
FAX: 801-359-3940

Date: April 3, 2014
Salt Lake City, Utah

Remarks:

Collapse is based on a vertical depth of 6521 ft, a mud weight of 10 ppg. The casing is considered to be evacuated for collapse purposes. Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.

Burst strength is not adjusted for tension.

Collapse strength is (biaxially) derated for doglegs in directional wells by multiplying the tensile stress by the cross section area to calculate a

Engineering responsibility for use of this design will be that of the purchaser.

ON-SITE PREDRILL EVALUATION

Utah Division of Oil, Gas and Mining

Operator ULTRA RESOURCES INC
Well Name Three Rivers 16-42L-820
API Number 43047542690000 **APD No** 9379 **Field/Unit** THREE RIVERS
Location: 1/4,1/4 SENE **Sec** 16 **Tw** 8.0S **Rng** 20.0E 2006 FNL 607 FEL
GPS Coord (UTM) 613665 4442420 **Surface Owner**

Participants

Jim Burns (permit contractor), Ben Williams (DWR), Jim Davis (SITLA), Bart Hunting (surveyor), Richard Powell (UDOGM)

Regional/Local Setting & Topography

This proposed well sits on an existing well location. It is located approximately midway between the Green River bridge in Ouray to the south and Pelican Lake to the north and sits less than a half mile west of highway 88.

Surface Use Plan

Current Surface Use
Existing Well Pad

| New Road Miles | Well Pad | Src Const Material | Surface Formation |
|-----------------------|------------------------------------|---------------------------|--------------------------|
| 0 | Width 212 Length 322 | Offsite | ALLU |

Ancillary Facilities N

Waste Management Plan Adequate? Y

Environmental Parameters

Affected Floodplains and/or Wetlands

Flora / Fauna

Existing well pad surrounded by high desert vegetation including small sage, rabbit brush and sparse grasses.

Antelope habitat

Soil Type and Characteristics

Sandy loam

Erosion Issues

Sedimentation Issues

Site Stability Issues

Drainage Diversion Required?

Berm Required?

Erosion Sedimentation Control Required?

Paleo Survey Run? **Paleo Potential Observed?** **Cultural Survey Run?** **Cultural Resources?**

Reserve Pit**Site-Specific Factors****Site Ranking**

| | | |
|--|-------------------|---------------------|
| Distance to Groundwater (feet) | 100 to 200 | 5 |
| Distance to Surface Water (feet) | >1000 | 0 |
| Dist. Nearest Municipal Well (ft) | >5280 | 0 |
| Distance to Other Wells (feet) | | 20 |
| Native Soil Type | High permeability | 20 |
| Fluid Type | Air/mist | 0 |
| Drill Cuttings | Normal Rock | 0 |
| Annual Precipitation (inches) | | 0 |
| Affected Populations | | |
| Presence Nearby Utility Conduits | Unknown | 10 |
| Final Score | 55 | 1 Sensitivity Level |

Characteristics / Requirements

Old reserve pit has been reclaimed. A new smaller 40' x 40' pit is proposed. This will require a 16 mil liner for fluids containment.

Closed Loop Mud Required? N **Liner Required? Y** **Liner Thickness 16** **Pit Underlayment Required? Y**

Other Observations / Comments

Richard Powell
Evaluator

3/6/2014
Date / Time

Application for Permit to Drill Statement of Basis Utah Division of Oil, Gas and Mining

| | | | | | |
|------------------|---|---------------|--------------------------|-------------------|------------|
| APD No | API WellNo | Status | Well Type | Surf Owner | CBM |
| 9379 | 43047542690000 | REVISED | OW | S | No |
| Operator | ULTRA RESOURCES INC | | Surface Owner-APD | | |
| Well Name | Three Rivers 16-42L-820 | | Unit | | |
| Field | THREE RIVERS | | Type of Work | DRILL | |
| Location | SENE 16 8S 20E S 2006 FNL (UTM) 613669E 4442417N | | 607 FEL GPS Coord | | |

Geologic Statement of Basis

Ultra proposes to set 1,033 feet of surface pipe, cemented to surface. The depth to the base of the moderately saline water at this location is estimated to be at approximately 400 feet. A search of Division of Water Rights records shows no water wells within a 10,000 foot radius of the center of Section 16. The surface formation at this site is the Uinta Formation and alluvium derived from the Uinta Formation. The Uinta Formation is made up of interbedded shales and sandstones. The sandstones are mostly lenticular and discontinuous and should not be a significant source of useable ground water. The proposed casing and cement should adequately protect ground water in this area.

Brad Hill
APD Evaluator

3/17/2014
Date / Time

Surface Statement of Basis

This proposed well is to be placed on an existing oil well location. The surface and minerals are controlled by SITLA. SITLA representative Jim Davis was in attendance for this presite and stated that he no concerns with the placement of this additional well and that the condition of the existing well pad is acceptable to SITLA. Ben Williams of the Utah DWR also attended this inspection and stated that this area is antelope habitat but made no recommendations regarding wildlife for this site. The previous reserve pit has been reclaimed and a new small 40ft by 40ft reserve pit is proposed. This will require a 16 mil liner and felt subliner for fluid containment. It is also proposed that the south east side of the location be extended an additional 24 feet and it does not appear that this additional will cause any problem.

Richard Powell
Onsite Evaluator

3/6/2014
Date / Time

Conditions of Approval / Application for Permit to Drill

| | |
|-----------------|---|
| Category | Condition |
| Pits | A synthetic liner with a minimum thickness of 16 mils with a felt subliner shall be properly installed and maintained in the reserve pit. |
| Surface | The reserve pit shall be fenced upon completion of drilling operations. |

WORKSHEET APPLICATION FOR PERMIT TO DRILL

APD RECEIVED: 2/4/2014

API NO. ASSIGNED: 43047542690000

WELL NAME: Three Rivers 16-42L-820

OPERATOR: ULTRA RESOURCES INC (N4045)

PHONE NUMBER: 435 719-2018

CONTACT: Don Hamilton

PROPOSED LOCATION: SENE 16 080S 200E

Permit Tech Review: ☒

SURFACE: 2006 FNL 0607 FEL

Engineering Review: ☒

BOTTOM: 1980 FNL 0660 FEL

Geology Review: ☒

COUNTY: UINTAH

LATITUDE: 40.12440

LONGITUDE: -109.66595

UTM SURF EASTINGS: 613669.00

NORTHINGS: 4442417.00

FIELD NAME: THREE RIVERS

LEASE TYPE: 3 - State

LEASE NUMBER: ML-49319

PROPOSED PRODUCING FORMATION(S): GREEN RIVER - LOWER

SURFACE OWNER: 3 - State

COALBED METHANE: NO

RECEIVED AND/OR REVIEWED:

- ☒ PLAT
- ☒ Bond: STATE - 022046398
- ☐ Potash
- ☐ Oil Shale 190-5
- ☐ Oil Shale 190-3
- ☐ Oil Shale 190-13
- ☒ Water Permit: 49-2262
- ☐ RDCC Review:
- ☐ Fee Surface Agreement
- ☐ Intent to Commingle

Commingle Approved

LOCATION AND SITING:

- ☐ R649-2-3.
- Unit:
- ☐ R649-3-2. General
- ☐ R649-3-3. Exception
- ☒ Drilling Unit
- Board Cause No: Cause 270-02
- Effective Date: 11/9/2013
- Siting: (2) Wells Per Drilling Unit
- ☒ R649-3-11. Directional Drill

Comments: Presite Completed

Stipulations: 5 - Statement of Basis - bhill
12 - Cement Volume (3) - hmadonald
15 - Directional - dmason
25 - Surface Casing - hmadonald

RECEIVED: April 07, 2014



GARY R. HERBERT
Governor

SPENCER J. COX
Lieutenant Governor

State of Utah

DEPARTMENT OF NATURAL RESOURCES

MICHAEL R. STYLER
Executive Director

Division of Oil, Gas and Mining

JOHN R. BAZA
Division Director

Permit To Drill

Well Name: Three Rivers 16-42L-820

API Well Number: 43047542690000

Lease Number: ML-49319

Surface Owner: STATE

Approval Date: 4/7/2014

Issued to:

ULTRA RESOURCES INC, 304 Inverness Way South #245, Englewood, CO 80112

Authority:

Pursuant to Utah Code Ann. 40-6-1 et seq., and Utah Administrative Code R649-3-1 et seq., the Utah Division of Oil, Gas and Mining issues conditions of approval, and permit to drill the listed well. This permit is issued in accordance with the requirements of Cause 270-02. The expected producing formation or pool is the GREEN RIVER - LOWER Formation(s), completion into any other zones will require filing a Sundry Notice (Form 9). Completion and commingling of more than one pool will require approval in accordance with R649-3-22.

Duration:

This approval shall expire one year from the above date unless substantial and continuous operation is underway, or a request for extension is made prior to the expiration date

General:

Compliance with the requirements of Utah Admin. R. 649-1 et seq., the Oil and Gas Conservation General Rules, and the applicable terms and provisions of the approved Application for permit to drill.

Conditions of Approval:

In accordance with Utah Admin. R. 649-3-11, Directional Drilling, the operator shall submit a complete angular deviation and directional survey report to the Division within 30 days following completion of the well.

Compliance with the Conditions of Approval/Application for Permit to Drill outlined in the Statement of Basis (copy attached).

Cement volume for the 5 1/2" production string shall be determined from actual hole diameter in order to place lead cement from the pipe setting depth back to 500' MD as indicated in the submitted drilling plan and the tail cement to 500' above the Garden Gulch.

Surface casing shall be cemented to the surface.

Additional Approvals:

The operator is required to obtain approval from the Division of Oil, Gas and mining before performing any of the following actions during the drilling of this well:

- Any changes to the approved drilling plan - contact Dustin Doucet
- Significant plug back of the well - contact Dustin Doucet
- Plug and abandonment of the well - contact Dustin Doucet

Notification Requirements:

The operator is required to notify the Division of Oil, Gas and Mining of the following actions during drilling of this well:

- Within 24 hours following the spudding of the well - contact Carol Daniels
OR
submit an electronic sundry notice (pre-registration required) via the Utah Oil & Gas website
at <http://oilgas.ogm.utah.gov>
- 24 hours prior to testing blowout prevention equipment - contact Dan Jarvis
- 24 hours prior to cementing or testing casing - contact Dan Jarvis
- Within 24 hours of making any emergency changes to the approved drilling program
- contact Dustin Doucet
- 24 hours prior to commencing operations to plug and abandon the well - contact Dan Jarvis

Contact Information:

The following are Division of Oil, Gas and Mining contacts and their telephone numbers (please leave a voicemail message if the person is not available to take the call):

- Carol Daniels 801-538-5284 - office
- Dustin Doucet 801-538-5281 - office
801-733-0983 - after office hours
- Dan Jarvis 801-538-5338 - office
801-231-8956 - after office hours

Reporting Requirements:

All reports, forms and submittals as required by the Utah Oil and Gas Conservation General Rules will be promptly filed with the Division of Oil, Gas and Mining, including but not limited to:

- Entity Action Form (Form 6) - due within 5 days of spudding the well
- Monthly Status Report (Form 9) - due by 5th day of the following calendar month
- Requests to Change Plans (Form 9) - due prior to implementation
- Written Notice of Emergency Changes (Form 9) - due within 5 days
- Notice of Operations Suspension or Resumption (Form 9) - due prior to implementation
- Report of Water Encountered (Form 7) - due within 30 days after completion
- Well Completion Report (Form 8) - due within 30 days after completion or plugging

Approved By:

Approved By:

A handwritten signature in black ink, appearing to read 'J. Rogers', written over a horizontal line.

For John Rogers
Associate Director, Oil & Gas

| | | |
|--|---|--|
| STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING | | FORM 9 |
| SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals. | | 5. LEASE DESIGNATION AND SERIAL NUMBER: ML-49319 |
| 1. TYPE OF WELL Oil Well | | 6. IF INDIAN, ALLOTTEE OR TRIBE NAME: |
| 2. NAME OF OPERATOR: ULTRA RESOURCES INC | | 7. UNIT or CA AGREEMENT NAME: |
| 3. ADDRESS OF OPERATOR: 304 Inverness Way South #245, Englewood, CO, 80112 | | 8. WELL NAME and NUMBER: Three Rivers 16-42L-820 |
| 4. LOCATION OF WELL FOOTAGES AT SURFACE: 2006 FNL 0607 FEL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: SENE Section: 16 Township: 08.0S Range: 20.0E Meridian: S | | 9. API NUMBER: 43047542690000 |
| PHONE NUMBER: 303 645-9810 Ext | | 9. FIELD and POOL or WILDCAT: THREE RIVERS |
| COUNTY: UINTAH | | STATE: UTAH |
| 11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA | | |
| TYPE OF SUBMISSION | TYPE OF ACTION | |
| <input type="checkbox"/> NOTICE OF INTENT Approximate date work will start: | <input type="checkbox"/> ACIDIZE | |
| <input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: | <input type="checkbox"/> ALTER CASING | |
| <input checked="" type="checkbox"/> SPUD REPORT Date of Spud: 5/1/2014 | <input type="checkbox"/> CASING REPAIR | |
| <input type="checkbox"/> DRILLING REPORT Report Date: | <input type="checkbox"/> CHANGE TO PREVIOUS PLANS | |
| | <input type="checkbox"/> CHANGE TUBING | |
| | <input type="checkbox"/> CHANGE WELL STATUS | |
| | <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS | |
| | <input type="checkbox"/> DEEPEN | |
| | <input type="checkbox"/> FRACTURE TREAT | |
| | <input type="checkbox"/> OPERATOR CHANGE | |
| | <input type="checkbox"/> PLUG AND ABANDON | |
| | <input type="checkbox"/> PRODUCTION START OR RESUME | |
| | <input type="checkbox"/> RECLAMATION OF WELL SITE | |
| | <input type="checkbox"/> REPERFORATE CURRENT FORMATION | |
| | <input type="checkbox"/> SIDETRACK TO REPAIR WELL | |
| | <input type="checkbox"/> TUBING REPAIR | |
| | <input type="checkbox"/> VENT OR FLARE | |
| | <input type="checkbox"/> WATER SHUTOFF | |
| | <input type="checkbox"/> SI TA STATUS EXTENSION | |
| | <input type="checkbox"/> WILDCAT WELL DETERMINATION | |
| | <input type="checkbox"/> OTHER | |
| | OTHER: <input style="width: 100px;" type="text"/> | |
| 12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. Ultra will be moving ProPetro onto the Three Rivers 16-42L-820 (API # 43-047-54259) to drill and set surface on 5/1/2014. | | |
| Accepted by the Utah Division of Oil, Gas and Mining FOR RECORD ONLY May 01, 2014 | | |
| NAME (PLEASE PRINT) Jenna Anderson | PHONE NUMBER 303 645-9804 | TITLE Permitting Assistant |
| SIGNATURE N/A | DATE 5/1/2014 | |

| | | |
|--|--|--|
| STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING | | FORM 9 |
| SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals. | | 5. LEASE DESIGNATION AND SERIAL NUMBER: ML-49319 |
| 1. TYPE OF WELL Oil Well | | 6. IF INDIAN, ALLOTTEE OR TRIBE NAME: |
| 2. NAME OF OPERATOR: ULTRA RESOURCES INC | | 7. UNIT or CA AGREEMENT NAME: |
| 3. ADDRESS OF OPERATOR: 304 Inverness Way South #245, Englewood, CO, 80112 | | 8. WELL NAME and NUMBER: Three Rivers 16-42L-820 |
| 4. LOCATION OF WELL FOOTAGES AT SURFACE: 2006 FNL 0607 FEL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: SENE Section: 16 Township: 08.0S Range: 20.0E Meridian: S | | 9. API NUMBER: 43047542690000 |
| PHONE NUMBER: 303 645-9810 Ext | | 9. FIELD and POOL or WILDCAT: THREE RIVERS |
| COUNTY: UINTAH | | STATE: UTAH |
| 11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA | | |
| TYPE OF SUBMISSION | TYPE OF ACTION | |
| <input type="checkbox"/> NOTICE OF INTENT Approximate date work will start: | <input type="checkbox"/> ACIDIZE | |
| <input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: | <input type="checkbox"/> ALTER CASING | |
| <input type="checkbox"/> SPUD REPORT Date of Spud: | <input type="checkbox"/> CASING REPAIR | |
| <input checked="" type="checkbox"/> DRILLING REPORT Report Date: 6/5/2014 | <input type="checkbox"/> CHANGE TO PREVIOUS PLANS | |
| | <input type="checkbox"/> CHANGE TUBING | |
| | <input type="checkbox"/> CHANGE WELL STATUS | |
| | <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS | |
| | <input type="checkbox"/> DEEPEN | |
| | <input type="checkbox"/> FRACTURE TREAT | |
| | <input type="checkbox"/> OPERATOR CHANGE | |
| | <input type="checkbox"/> PLUG AND ABANDON | |
| | <input type="checkbox"/> PRODUCTION START OR RESUME | |
| | <input type="checkbox"/> RECLAMATION OF WELL SITE | |
| | <input type="checkbox"/> REPERFORATE CURRENT FORMATION | |
| | <input type="checkbox"/> SIDETRACK TO REPAIR WELL | |
| | <input type="checkbox"/> TUBING REPAIR | |
| | <input type="checkbox"/> VENT OR FLARE | |
| | <input type="checkbox"/> WATER SHUTOFF | |
| | <input type="checkbox"/> SI TA STATUS EXTENSION | |
| | <input type="checkbox"/> WILDCAT WELL DETERMINATION | |
| | <input type="checkbox"/> OTHER: <input style="width: 100px;" type="text"/> | |
| 12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. Monthly status report of drilling and completion attached. | | |
| Accepted by the Utah Division of Oil, Gas and Mining FOR RECORD ONLY June 05, 2014 | | |
| NAME (PLEASE PRINT) Jenna Anderson | PHONE NUMBER 303 645-9804 | TITLE Permitting Assistant |
| SIGNATURE N/A | DATE 6/5/2014 | |

ULTRA RESOURCES, INC.
DAILY DRILLING REPORT DATE: 04/30/2014

WELL NAME

THREE RIVERS 16-42L-820

AFE#

140625

SPUD DATE

04/21/2014

WELL SITE CONSULTANT

JOHN FREITAS

PHONE#

435-828-5550

CONTRACTOR

Other

TD AT REPORT

1.059'

FOOTAGE

980'

PRATE

CUM. DRLG. HRS

DRLG DAYS SINCE SPUD

0

ANTICIPATED TD

PRESENT OPS

Drilling at 1.059'

GEOLOGIC SECT.

DAILY MUD LOSS

SURF:

DH:

CUM. MUD LOSS

SURF:

DH:

MUD COMPANY:

MUD ENGINEER:

LAST BOP TEST

NEXT CASING SIZE

5 1/2

NEXT CASING DEPTH

SSE

SSED

AFE Days vs Depth:

DWOP Days vs Depth:

AFE Cost Vs Depth:

LL/BP Received Today:

| | | | | | | | | | | | |
|-----------------------|------|---------|------------|------------|------------|--------|-----------|----------|-----------|-----------------|----------|
| RECENT CASINGS RUN: | | | Date Set | | Size | Grade | Weight | Depth | FIT Depth | FIT ppg | |
| Conductor | | | 04/21/2014 | | 16 | ARJ-55 | 45 | 118 | | | |
| RECENT BITS: | | | | | | | | | | | |
| BIT | SIZE | MANUF | TYPE | SERIAL NO. | | JETS | TFA | DEPTH IN | DEPTH OUT | I-O-D-L-B-G-O-R | |
| BIT OPERATIONS: | | | | | | | | | | | |
| BIT | WOB | RPM | GPM | PRESS | HHP | HRS | 24hr DIST | 24HR ROP | CUM HRS | CUM DIST | CUM ROP |
| RECENT MUD MOTORS: | | | | | | | | | | | |
| # | SIZE | MANUF | TYPE | | SERIAL NO. | | LOBES | DEPTH IN | DEPTH OUT | DATE IN | DATE OUT |
| MUD MOTOR OPERATIONS: | | | | | | | | | | | |
| # | WOB | REV/GAL | HRS | | 24hr DIST | | 24HR ROP | CUM HRS | CUM DIST | CUM ROP | |
| SURVEYS | | | | | | | | | | | |
| Date | TMD | Incl | Azimuth | | TVD | VS | NS | EW | DLS | Tool Type | |

| | | | | | | | |
|--------------------------------|-------|--------|---------|--------------------------------|-------|--------|---------|
| DAILY COSTS | DAILY | CUM | AFE | | DAILY | CUM | AFE |
| 8100..100: Permits & Fees | | | 4,500 | 8100..105: Insurance | | | 2,500 |
| 8100..110: Staking & Surveying | | | 1,500 | 8100..120: Surface Damages & R | | | |
| 8100..200: Location Roads | | | 30,000 | 8100..210: Reclamation | | | |
| 8100..220: Secondary Reclamati | | | | 8100..230: Pit Solidification | | | 5,000 |
| 8100..300: Water Well | | | | 8100..310: Water/Water Disposa | | | 10,000 |
| 8100..320: Mud & Chemicals | | | 55,000 | 8100..325: Oil Base Mud Diesel | | | 35,000 |
| 8100..400: Drilling Rig | | | 135,000 | 8100..402: Drilling Rig Cleani | | | 5,000 |
| 8100..405: Rig Fuel | | | 20,000 | 8100..410: Mob/Demob | | | |
| 8100..420: Bits & Reamers | | | 17,500 | 8100..500: Roustabout Services | | | 4,000 |
| 8100..510: Testing/Inspection/ | | | 1,000 | 8100..520: Trucking & Hauling | | | 23,000 |
| 8100..530: Equipment Rental | | | 17,000 | 8100..531: Down Hole Motor Ren | | | 1,500 |
| 8100..532: Solids Control Equi | | | 10,000 | 8100..535: Directional Drillin | | | 65,000 |
| 8100..540: Fishing | | | | 8100..600: Surface Casing/Inte | | | 35,000 |
| 8100..605: Cementing Work | | 13,740 | 25,000 | 8100..610: P & A | | | |
| 8100..700: Logging - Openhole | | | 14,000 | 8100..705: Logging - Mud | | | |
| 8100..800: Supervision/Consult | | | 35,000 | 8100..810: Engineering/Evaluat | | | |
| 8100..900: Contingencies | | | | 8100..950: Administrative O/H | | | |
| 8100..999: Non Operated IDC | | | | 8200..510: Testing/Inspection/ | | | 2,000 |
| 8200..520: Trucking & Hauling | | | 11,500 | 8200..530: Equipment Rental | | | 20,000 |
| 8200..605: Cementing Work | | | 25,000 | 8210..600: Production Casing | | | 50,000 |
| 8210..620: Wellhead/Casing Hea | | | 15,000 | Total Cost | | 13,740 | 675,000 |

ULTRA RESOURCES, INC.
DAILY DRILLING REPORT DATE: 05/01/2014

| | | | | | | | | | |
|----------------------|-------------------------|---------|------|--------------------|-------------------|----------------|----------------|----------------------|---|
| WELL NAME | THREE RIVERS 16-42L-820 | | | AFE# | 140625 | | SPUD DATE | 04/21/2014 | |
| WELL SITE CONSULTANT | KING BROWN | | | PHONE# | 435-828-5550 | | CONTRACTOR | Other | |
| TD AT REPORT | 1,059' | FOOTAGE | 980' | PRATE | 65.3 | CUM. DRLG. HRS | 15.0 | DRLG DAYS SINCE SPUD | 1 |
| ANTICIPATED TD | PRESENT OPS | | | Drilling at 1,059' | | | GEOLOGIC SECT. | | |
| DAILY MUD LOSS | SURF: | | DH: | | CUM. MUD LOSS | SURF: | | DH: | |
| MUD COMPANY: | | | | MUD ENGINEER: | | | | | |
| LAST BOP TEST | NEXT CASING SIZE | | | 5 1/2 | NEXT CASING DEPTH | | SSE | SSD | |

| | | |
|----------------|----------|-------|
| TIME BREAKDOWN | DRILLING | 15.00 |
|----------------|----------|-------|

| | | | | |
|---------|-------|-------|-------|--|
| DETAILS | Start | End | Hrs | |
| | 15:00 | 06:00 | 15:00 | MI&RU PRO PETRO RIG 10. DRILL F/100' T/1080. RU & RUN 8 5/8" CASING T/1059.53'. CEMENT CASING IN PLACE W/ PRO PETRO. |

| | | | |
|---------------------|--|-------------------------|--|
| AFE Days vs Depth: | | AFE Cost Vs Depth: | |
| DWOP Days vs Depth: | | # LL/BP Received Today: | |

| | | | | | |
|----------------------|------|----------|-------------|---------|----------|
| FUEL AND WATER USAGE | Used | Received | Transferred | On Hand | Cum.Used |
| Fluid | | | | | |
| Fuel | | | | 0.0 | |
| Gas | | | | | |
| Fresh Well Water | | | | | |
| Nano Water | | | | | |
| Frac Water | | | | | |
| Reserve Pit Water | | | | | |
| Boiler Hours | | | | | |
| Air Heater Hours | | | | | |
| Urea | | | | 0.0 | |
| Urea Sys 1 Hrs | | | | | |
| Urea Sys 2 Hrs | | | | | |
| Urea Sys 3 Hrs | | | | | |

| | |
|------------------|-------------------------------------|
| CASING EQUIPMENT | SHOE,1 JOINT, FLOAT, 23 JOINTS CSG. |
|------------------|-------------------------------------|

| | | | | | | | |
|---------------------|------------|-------|--------|--------|-------|-----------|---------|
| RECENT CASINGS RUN: | Date Set | Size | Grade | Weight | Depth | FIT Depth | FIT ppg |
| Surface | 05/01/2014 | 8 5/8 | J-55 | 24 | 1,060 | | |
| Conductor | 04/21/2014 | 16 | ARJ-55 | 45 | 118 | | |

| | | | | | | | | | | |
|--------------|-----|------|-------|------|------------|------|-----|----------|-----------|-----------------|
| RECENT BITS: | BIT | SIZE | MANUF | TYPE | SERIAL NO. | JETS | TFA | DEPTH IN | DEPTH OUT | I-O-D-L-B-G-O-R |
|--------------|-----|------|-------|------|------------|------|-----|----------|-----------|-----------------|

| | | | | | | | | | | | | |
|-----------------|-----|-----|-----|-----|-------|-----|-----|-----------|----------|---------|----------|---------|
| BIT OPERATIONS: | BIT | WOB | RPM | GPM | PRESS | HHP | HRS | 24hr DIST | 24HR ROP | CUM HRS | CUM DIST | CUM ROP |
|-----------------|-----|-----|-----|-----|-------|-----|-----|-----------|----------|---------|----------|---------|

| | | | | | | | | | | |
|--------------------|---|------|-------|------|------------|-------|----------|-----------|---------|----------|
| RECENT MUD MOTORS: | # | SIZE | MANUF | TYPE | SERIAL NO. | LOBES | DEPTH IN | DEPTH OUT | DATE IN | DATE OUT |
|--------------------|---|------|-------|------|------------|-------|----------|-----------|---------|----------|

| | | | | | | | | | |
|-----------------------|---|-----|---------|-----|-----------|----------|---------|----------|---------|
| MUD MOTOR OPERATIONS: | # | WOB | REV/GAL | HRS | 24hr DIST | 24HR ROP | CUM HRS | CUM DIST | CUM ROP |
|-----------------------|---|-----|---------|-----|-----------|----------|---------|----------|---------|

| | | | | | | | | | | |
|---------|------|-----|------|---------|-----|----|----|----|-----|-----------|
| SURVEYS | Date | TMD | Incl | Azimuth | TVD | VS | NS | EW | DLS | Tool Type |
|---------|------|-----|------|---------|-----|----|----|----|-----|-----------|

| | | | | | | | |
|--------------------------------|--------|--------|---------|--------------------------------|--------|--------|---------|
| DAILY COSTS | DAILY | CUM | AFE | | DAILY | CUM | AFE |
| 8100..100: Permits & Fees | | | 4,500 | 8100..105: Insurance | | | 2,500 |
| 8100..110: Staking & Surveying | | | 1,500 | 8100..120: Surface Damages & R | | | |
| 8100..200: Location Roads | | | 30,000 | 8100..210: Reclamation | | | |
| 8100..220: Secondary Reclamat | | | | 8100..230: Pit Solidification | | | 5,000 |
| 8100..300: Water Well | | | | 8100..310: Water/Water Disposa | 5,666 | 5,666 | 10,000 |
| 8100..320: Mud & Chemicals | | | 55,000 | 8100..325: Oil Base Mud Diesel | | | 35,000 |
| 8100..400: Drilling Rig | 31,360 | 31,360 | 135,000 | 8100..402: Drilling Rig Cleani | | | 5,000 |
| 8100..405: Rig Fuel | | | 20,000 | 8100..410: Mob/Demob | | | |
| 8100..420: Bits & Reamers | | | 17,500 | 8100..500: Roustabout Services | | | 4,000 |
| 8100..510: Testing/Inspection/ | | | 1,000 | 8100..520: Trucking & Hauling | | | 23,000 |
| 8100..530: Equipment Rental | | | 17,000 | 8100..531: Down Hole Motor Ren | | | 1,500 |
| 8100..532: Solids Control Equi | | | 10,000 | 8100..535: Directional Drillin | | | 65,000 |
| 8100..540: Fishing | | | | 8100..600: Surface Casing/Inte | 19,591 | 19,591 | 35,000 |
| 8100..605: Cementing Work | | 13,740 | 25,000 | 8100..610: P & A | | | |
| 8100..700: Logging - Openhole | | | 14,000 | 8100..705: Logging - Mud | | | |
| 8100..800: Supervision/Consult | | | 35,000 | 8100..810: Engineering/Evaluat | | | |
| 8100..900: Contingencies | | | | 8100..950: Administrative O/H | | | |
| 8100..999: Non Operated IDC | | | | 8200..510: Testing/Inspection/ | | | 2,000 |
| 8200..520: Trucking & Hauling | | | 11,500 | 8200..530: Equipment Rental | | | 20,000 |
| 8200..605: Cementing Work | 19,156 | 19,156 | 25,000 | 8210..600: Production Casing | | | 50,000 |
| 8210..620: Wellhead/Casing Hea | | | 15,000 | Total Cost | 75,773 | 89,513 | 675,000 |

CONFIDENTIAL

BLM - Vernal Field Office - Notification Form

Submitted By JARED MEJORADO Phone Number 435-219-4933
Well Name/Number Three Rivers 16-42L-820
Qtr/Qtr SE/NE Section 16 Township 78S Range 120E
Lease Serial Number ML-49319
API Number 43-047-54269

Spud Notice – Spud is the initial spudding of the well, not drilling out below a casing string.

Date/Time _____ AM ☐ PM ☐

Casing – Please report time casing run starts, not cementing times.

- ☐ Surface Casing
- ☐ Intermediate Casing
- ☒ Production Casing
- ☐ Liner
- ☐ Other

Date/Time 7/22/2014 9:00 AM ☒ PM ☐

BOPE

- ☐ Initial BOPE test at surface casing point
- ☐ BOPE test at intermediate casing point
- ☐ 30 day BOPE test
- ☐ Other

Date/Time _____ AM ☐ PM ☐

Remarks If you have any questions please call.

| | | |
|--|--|--|
| STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING | | FORM 9 |
| SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals. | | 5. LEASE DESIGNATION AND SERIAL NUMBER: ML-49319 |
| 1. TYPE OF WELL Oil Well | | 6. IF INDIAN, ALLOTTEE OR TRIBE NAME: |
| 2. NAME OF OPERATOR: ULTRA RESOURCES INC | | 7. UNIT or CA AGREEMENT NAME: |
| 3. ADDRESS OF OPERATOR: 304 Inverness Way South #295, Englewood, CO, 80112 | | 8. WELL NAME and NUMBER: Three Rivers 16-42L-820 |
| 4. LOCATION OF WELL FOOTAGES AT SURFACE: 2006 FNL 0607 FEL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: SENE Section: 16 Township: 08.0S Range: 20.0E Meridian: S | | 9. API NUMBER: 43047542690000 |
| PHONE NUMBER: 303 645-9810 Ext | | 9. FIELD and POOL or WILDCAT: THREE RIVERS |
| COUNTY: UTAH | | STATE: UTAH |

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

| TYPE OF SUBMISSION | TYPE OF ACTION | | | |
|---|--|---|---|--|
| <input type="checkbox"/> NOTICE OF INTENT Approximate date work will start: | <input type="checkbox"/> ACIDIZE | <input type="checkbox"/> ALTER CASING | <input type="checkbox"/> CASING REPAIR | |
| <input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: | <input type="checkbox"/> CHANGE TO PREVIOUS PLANS | <input type="checkbox"/> CHANGE TUBING | <input type="checkbox"/> CHANGE WELL NAME | |
| <input type="checkbox"/> SPUD REPORT Date of Spud: | <input type="checkbox"/> CHANGE WELL STATUS | <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS | <input type="checkbox"/> CONVERT WELL TYPE | |
| <input checked="" type="checkbox"/> DRILLING REPORT Report Date: 8/5/2014 | <input type="checkbox"/> DEEPEN | <input type="checkbox"/> FRACTURE TREAT | <input type="checkbox"/> NEW CONSTRUCTION | |
| | <input type="checkbox"/> OPERATOR CHANGE | <input type="checkbox"/> PLUG AND ABANDON | <input type="checkbox"/> PLUG BACK | |
| | <input type="checkbox"/> PRODUCTION START OR RESUME | <input type="checkbox"/> RECLAMATION OF WELL SITE | <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION | |
| | <input type="checkbox"/> REPERFORATE CURRENT FORMATION | <input type="checkbox"/> SIDETRACK TO REPAIR WELL | <input type="checkbox"/> TEMPORARY ABANDON | |
| | <input type="checkbox"/> TUBING REPAIR | <input type="checkbox"/> VENT OR FLARE | <input type="checkbox"/> WATER DISPOSAL | |
| | <input type="checkbox"/> WATER SHUTOFF | <input type="checkbox"/> SI TA STATUS EXTENSION | <input type="checkbox"/> APD EXTENSION | |
| | <input type="checkbox"/> WILDCAT WELL DETERMINATION | <input type="checkbox"/> OTHER | OTHER: <input style="width: 100px;" type="text"/> | |

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.
 Monthly status report of drilling and completion attached.

Accepted by the
 Utah Division of
 Oil, Gas and Mining
FOR RECORD ONLY
 August 11, 2014

| | | |
|--|-------------------------------------|--------------------------------------|
| NAME (PLEASE PRINT) Jenna Anderson | PHONE NUMBER 303 645-9804 | TITLE Permitting Assistant |
| SIGNATURE N/A | DATE 8/5/2014 | |

ULTRA RESOURCES, INC.
DAILY DRILLING REPORT DATE: 07/19/2014

| | | | | | | | | | | |
|----------------------|-------------------------|------------------|-------|-------------------|--------------|----------------|----------------|------------|----------------------|---|
| WELL NAME | THREE RIVERS 16-42L-820 | | | AFE# | 140625 | | SPUD DATE | 07/20/2014 | | |
| WELL SITE CONSULTANT | JOHN FREITAS | | | PHONE# | 435-828-5550 | | CONTRACTOR | Other | | |
| TD AT REPORT | 0' | FOOTAGE | 0' | PRATE | | | CUM. DRLG. HRS | 15.0 | DRLG DAYS SINCE SPUD | 0 |
| ANTICIPATED TD | 6,443' | PRESENT OPS | at 0' | | | GEOLOGIC SECT. | | | | |
| DAILY MUD LOSS | SURF: | DH: | | CUM. MUD LOSS | | SURF: | | DH: | | |
| MUD COMPANY: | | | | MUD ENGINEER: | | | | | | |
| LAST BOP TEST | 07/19/2014 | NEXT CASING SIZE | | NEXT CASING DEPTH | | SSE | | SSED | | |

| | | | |
|---------------------|--|-------------------------|--|
| AFE Days vs Depth: | | AFE Cost Vs Depth: | |
| DWOP Days vs Depth: | | # LL/BP Received Today: | |

FUEL AND WATER USAGE

| | | | | | |
|-------------------|------|----------|-------------|---------|----------|
| Fluid | Used | Received | Transferred | On Hand | Cum.Used |
| Fuel | | | | 0.0 | |
| Gas | | | | | |
| Fresh Well Water | | | | | |
| Nano Water | | | | | |
| Frac Water | | | | | |
| Reserve Pit Water | | | | | |
| Boiler Hours | | | | | |
| Air Heater Hours | | | | | |
| Urea | | | | 0.0 | |
| Urea Sys 1 Hrs | | | | | |
| Urea Sys 2 Hrs | | | | | |
| Urea Sys 3 Hrs | | | | | |

| | | | | | | | |
|---------------------|------------|-------|--------|--------|-------|-----------|---------|
| RECENT CASINGS RUN: | Date Set | Size | Grade | Weight | Depth | FIT Depth | FIT ppg |
| Surface | 05/01/2014 | 8 5/8 | J-55 | 24 | 1,060 | | |
| Conductor | 04/21/2014 | 16 | ARJ-55 | 45 | 118 | | |

| | | | | | | | | | | | |
|--------------|------|-------|------|------------|------|-----|----------|-----------|-----------------|--|--|
| RECENT BITS: | | | | | | | | | | | |
| BIT | SIZE | MANUF | TYPE | SERIAL NO. | JETS | TFA | DEPTH IN | DEPTH OUT | I-O-D-L-B-G-O-R | | |

| | | | | | | | | | | | |
|-----------------|-----|-----|-----|-------|-----|-----|-----------|----------|---------|----------|---------|
| BIT OPERATIONS: | | | | | | | | | | | |
| BIT | WOB | RPM | GPM | PRESS | HHP | HRS | 24hr DIST | 24HR ROP | CUM HRS | CUM DIST | CUM ROP |

| | | | | | | | | | | | |
|--------------------|------|-------|------|------------|-------|----------|-----------|---------|----------|--|--|
| RECENT MUD MOTORS: | | | | | | | | | | | |
| # | SIZE | MANUF | TYPE | SERIAL NO. | LOBES | DEPTH IN | DEPTH OUT | DATE IN | DATE OUT | | |

| | | | | | | | | | | | |
|-----------------------|-----|---------|-----|-----------|----------|---------|----------|---------|--|--|--|
| MUD MOTOR OPERATIONS: | | | | | | | | | | | |
| # | WOB | REV/GAL | HRS | 24hr DIST | 24HR ROP | CUM HRS | CUM DIST | CUM ROP | | | |

| | | | | | | | | | | | |
|---------|-----|------|---------|-----|----|----|----|-----|-----------|--|--|
| SURVEYS | | | | | | | | | | | |
| Date | TMD | Incl | Azimuth | TVD | VS | NS | EW | DLS | Tool Type | | |

SURFACE PUMP/BHA INFORMATION

| | | | | | | | | | | | | |
|---------------|-----|------------|-----|-----------|-----|-----|--------|-------|-----|-----|----------------|---|
| Pump 1 Liner | 6.5 | Stroke Len | 9.0 | SPM | 114 | PSI | 2,100 | GPM | 400 | SPR | Slow PSI | |
| Pump 2 Liner | 6.5 | Stroke Len | 9.0 | SPM | | PSI | | GPM | | SPR | Slow PSI | |
| Pump 32 Liner | | Stroke Len | | SPM | | PSI | | GPM | | SPR | Slow PSI | |
| BHA Makeup | | STEERABLE | | | | | Length | 920.7 | | | Hours on BHA | 0 |
| Up Weight | | Dn Weight | | RT Weight | | | Torque | | | | Hours on Motor | 0 |

| | | | | | | | | | | | | |
|-------------|--------------|-------|-------|--------|----------------|---------------|----------------------------|--|--|--|--|--|
| BHA MAKEUP: | | | | | | | | | | | | |
| # | Component | OD | ID | Length | Weight (ft/lb) | Serial Number | Description | | | | | |
| 1 | BIT | 7.875 | 1.000 | 1.00 | | JJ5062 | SMITHMDSI516 | | | | | |
| 2 | MUD MOTOR | 6.500 | 1.000 | 32.12 | | 650-077 | 1.5 DEG FBH 7/8 5.7 .24 | | | | | |
| 3 | MONEL | 6.500 | 3.250 | 30.61 | | EN122-1 | 4.5 XH P x B | | | | | |
| 4 | GAP SUB | 6.500 | 3.250 | 5.20 | | 650-0053 | 4.5 XH P x B | | | | | |
| 5 | MONEL | 6.500 | 2.813 | 30.28 | | EN0815-12 | 4.5 XH P x B | | | | | |
| 6 | MONEL | 6.500 | 2.813 | 30.22 | | EN0814-12 | 4.5 XH P x B | | | | | |
| 7 | DC | 6.500 | 2.250 | 31.06 | | RIG | 4.5 XH P x B | | | | | |
| 8 | (18) HWDP | 4.500 | 2.313 | 547.01 | | RIG | 4.5 XH P x B | | | | | |
| 9 | DRILLING JAR | 6.500 | 2.813 | 31.11 | | SR-2056 | 4.5 XH P x B(SMITH)HE JARS | | | | | |
| 10 | (6) HWDP | 4.500 | 2.313 | 182.09 | | RIG | 4.5 XH P x B | | | | | |

| | | | | | | | |
|--------------------------------|--------|--------|---------|--------------------------------|--------|---------|---------|
| DAILY COSTS | DAILY | CUM | AFE | | DAILY | CUM | AFE |
| 8100..100: Permits & Fees | | | 4,500 | 8100..105: Insurance | | | 2,500 |
| 8100..110: Staking & Surveying | | | 1,500 | 8100..120: Surface Damages & R | | | |
| 8100..200: Location Roads | | | 30,000 | 8100..210: Reclamation | | | |
| 8100..220: Secondary Reclamat | | | | 8100..230: Pit Solidification | | | 5,000 |
| 8100..300: Water Well | | | | 8100..310: Water/Water Dispos | 6,716 | | 10,000 |
| 8100..320: Mud & Chemicals | | | 55,000 | 8100..325: Oil Base Mud Diesel | | | 35,000 |
| 8100..400: Drilling Rig | 19,425 | 50,785 | 135,000 | 8100..402: Drilling Rig Cleani | | | 5,000 |
| 8100..405: Rig Fuel | | | 20,000 | 8100..410: Mob/Demob | | | |
| 8100..420: Bits & Reamers | | | 17,500 | 8100..500: Roustabout Services | | | 4,000 |
| 8100..510: Testing/Inspection/ | | | 1,000 | 8100..520: Trucking & Hauling | | | 23,000 |
| 8100..530: Equipment Rental | 4,497 | 4,497 | 17,000 | 8100..531: Down Hole Motor Ren | | | 1,500 |
| 8100..532: Solids Control Equi | 390 | 390 | 10,000 | 8100..535: Directional Drillin | | | 65,000 |
| 8100..540: Fishing | | | | 8100..600: Surface Casing/Inte | 19,591 | | 35,000 |
| 8100..605: Cementing Work | | 13,740 | 25,000 | 8100..610: P & A | | | |
| 8100..700: Logging - Openhole | | | 14,000 | 8100..705: Logging - Mud | | | |
| 8100..800: Supervision/Consult | 2,750 | 2,750 | 35,000 | 8100..810: Engineering/Evaluat | | | |
| 8100..900: Contingencies | 2,977 | 2,977 | | 8100..950: Administrative O/H | | | |
| 8100..999: Non Operated IDC | | | | 8200..510: Testing/Inspection/ | | | 2,000 |
| 8200..520: Trucking & Hauling | | | 11,500 | 8200..530: Equipment Rental | | | 20,000 |
| 8200..605: Cementing Work | | 19,156 | 25,000 | 8210..600: Production Casing | | | 50,000 |
| 8210..620: Wellhead/Casing Hea | | | 15,000 | Total Cost | 30,039 | 120,602 | 675,000 |

ULTRA RESOURCES, INC.
DAILY DRILLING REPORT DATE: 07/20/2014

| | | | | | | | | | |
|----------------------|-------------------------|------------------|-------|----------------------|---------------------|----------------|----------------------|------------|--------|
| WELL NAME | THREE RIVERS 16-42L-820 | | | AFE# | 140625 | | SPUD DATE | 07/20/2014 | |
| WELL SITE CONSULTANT | JOHN FREITAS | | | PHONE# | 435-828-5550 | | CONTRACTOR | Ensign 122 | |
| TD AT REPORT | (no data) | FOOTAGE | | PRATE | CUM. DRLG. HRS 15.0 | | DRLG DAYS SINCE SPUD | 0 | |
| ANTICIPATED TD | 6.443' | PRESENT OPS | | Directional Drilling | | GEOLOGIC SECT. | | | |
| DAILY MUD LOSS | SURF: | 0 | DH: | 0 | CUM. MUD LOSS | SURF: | 0 | DH: | 0 |
| MUD COMPANY: | NEWPARK | | | MUD ENGINEER: | | NICK LATHAM | | | |
| LAST BOP TEST | 07/19/2014 | NEXT CASING SIZE | 5 1/2 | NEXT CASING DEPTH | | 6.423 | SSE | 3 | SSED 1 |

| | | | | | | | | | |
|------------------|--|------|----------------------|--|-------|----------|--|------|--|
| TIME BREAKDOWN | | | | | | | | | |
| NIPPLE UP B.O.P. | | 3.00 | PRESSURE TEST B.O.P. | | 12.00 | RIG MOVE | | 2.50 | |
| RIG REPAIRS | | 1.50 | RIG UP / TEAR DOWN | | 2.00 | TRIPPING | | 2.00 | |
| WORK BHA | | 1.00 | | | | | | | |

| | | | | |
|---------|-------|-------|---|--|
| DETAILS | | | | |
| Start | End | Hrs | | |
| 06:00 | 08:30 | 02:30 | SKID RIG 40' | |
| 08:30 | 10:30 | 02:00 | RIG UP BACK YARD - ELECTRICAL SKID AND SUB | |
| 10:30 | 13:30 | 03:00 | NIPPLE UP B.O.P. | |
| 13:30 | 16:30 | 03:00 | TEST B.O.P. | |
| 16:30 | 18:00 | 01:30 | CHANGE OUT MANUAL VALVE ON KILL LINE | |
| 18:00 | 03:00 | 09:00 | SAFETY MEETING - RIG UP TESTER (WALKER TESTING) AND TEST TEST BOP (MUD SAVER, PIPE RAMS, BLIND RAMS, CHOKE LINE & CHOKE VALVES, FOSV, INSIDE BOP, KILL LINE AND VALVES, CHECK VALVE, CHOKE MANIFOLD, HCR & MANUAL VALVE ALL @ 10 MIN 3000 PSI HIGH 10 MIN 250 PSI LOW - ANNULAR @ 10 MIN 1500 PSI HIGH 10 MIN 250 PSI LOW - CASING @ 30 MIN 1500 PSI - ACCUMULATOR FUNCTION TEST - RIG DOWN TESTER. | |
| 03:00 | 04:00 | 01:00 | P/U DIRECTIONAL TOOLS | |
| 04:00 | 06:00 | 02:00 | T.I.H. TO DRILL OUT FLOAT EQUIPMENT | |
| 05:55 | 05:55 | 00:00 | SAFETY MEETING DAYS:UNLOADING CASING WITH 3RD PARTY TRUCKS, MIXING CHEMICALS,WORKING AROUND FORKLIFT. | |
| | | | SAFETY MEETING NIGHTS:MIXING CHEMICALS, TRIPPING PIPE | |
| | | | REGULATORY NOTICES: NONE. | |
| | | | REGULATORY VISITS:NONE. | |
| | | | INCIDENTS:NONE. | |
| | | | SAFETY DRILLS:NONE. | |

| | | | |
|---------------------|--|-------------------------|--|
| AFE Days vs Depth: | | AFE Cost Vs Depth: | |
| DWOP Days vs Depth: | | # LL/BP Received Today: | |

| | | | | | |
|----------------------|------|----------|-------------|---------|----------|
| FUEL AND WATER USAGE | | | | | |
| Fluid | Used | Received | Transferred | On Hand | Cum.Used |
| Fuel | | 3,850.0 | | 3,850.0 | |
| Gas | | | | | |
| Fresh Well Water | | | | | |
| Nano Water | | | | | |
| Frac Water | | | | | |
| Reserve Pit Water | | | | | |
| Boiler Hours | | | | | |
| Air Heater Hours | | | | | |
| Urea | | | | 0.0 | |
| Urea Sys 1 Hrs | | | | | |
| Urea Sys 2 Hrs | | | | | |
| Urea Sys 3 Hrs | | | | | |

| | | | | | | | |
|---------------------|------------|-------|--------|--------|-------|-----------|---------|
| RECENT CASINGS RUN: | Date Set | Size | Grade | Weight | Depth | FIT Depth | FIT ppg |
| Surface | 05/01/2014 | 8 5/8 | J-55 | 24 | 1,060 | | |
| Conductor | 04/21/2014 | 16 | ARJ-55 | 45 | 118 | | |

| | | | | | | | | | |
|--------------|-------|-------|-------|------------|----------------|-------|----------|-----------|-----------------|
| RECENT BITS: | | | | | | | | | |
| BIT | SIZE | MANUF | TYPE | SERIAL NO. | JETS | TFA | DEPTH IN | DEPTH OUT | I-O-D-L-B-G-O-R |
| 1 | 7.875 | SEC | MM55M | 12450966 | 12/12/12/12/12 | 0.552 | 1,070 | | ----- |

| | | | | | | | | | | | |
|-----------------|-----|--------|-----|-------|------|------|-----------|----------|---------|----------|---------|
| BIT OPERATIONS: | | | | | | | | | | | |
| BIT | WOB | RPM | GPM | PRESS | HHP | HRS | 24hr DIST | 24HR ROP | CUM HRS | CUM DIST | CUM ROP |
| 1 | | 63/107 | 447 | 1,750 | 3.27 | 0.00 | 0 | | 0.00 | 0 | |

| | | | | | | | | | | | |
|--------------------|-------|------------|-----------|------------|-------|----------|-----------|------------|----------|--|--|
| RECENT MUD MOTORS: | | | | | | | | | | | |
| # | SIZE | MANUF | TYPE | SERIAL NO. | LOBES | DEPTH IN | DEPTH OUT | DATE IN | DATE OUT | | |
| 1 | 6.750 | DYNA DRILL | 1.5 FIXED | EN650684 | 7/8 5 | 1,070 | | 07/20/2014 | | | |

| | | | | | | | | | | | |
|-----------------------|-----|---------|------|-----------|----------|---------|----------|---------|--|--|--|
| MUD MOTOR OPERATIONS: | | | | | | | | | | | |
| # | WOB | REV/GAL | HRS | 24hr DIST | 24HR ROP | CUM HRS | CUM DIST | CUM ROP | | | |
| 1 | 20 | 0.24 | 0.00 | 0 | | 0.00 | 0 | | | | |

| | | | | | | | | | | |
|---------|-----|------|---------|-----|----|----|----|-----|-----------|--|
| SURVEYS | | | | | | | | | | |
| Date | TMD | Incl | Azimuth | TVD | VS | NS | EW | DLS | Tool Type | |

| | | | | | | | | | | | |
|----------------|------|----------------|------|--------|-------|----------|------|----------------|--|--|--|
| MUD PROPERTIES | | | | | | | | | | | |
| Type | LSND | Mud Wt | 9.8 | Alk. | | Sand % | 0.0 | XS Lime lb/bbl | | | |
| Temp. | 87 | Gels 10sec | 4 | Cl ppm | 4,500 | Solids % | 10.7 | Salt bbls | | | |
| Visc | | Gels 10min | 6 | Ca ppm | 80 | LGS % | 10.7 | LCM ppb | | | |
| PV | 8 | pH | 10.1 | pF | 1.0 | Oil % | | API WL cc | | | |
| YP | 8 | Filter Cake/32 | 38 | Mf | 2.7 | Water % | | HTHP WL cc | | | |
| O/W Ratio | 93.6 | ES | | WPS | | | | | | | |
| Comments: | | | | | | | | | | | |

| | | | | | | |
|----------|--------------------|---|------------|-----|-----------------|-----|
| Flaring: | Flare Foot-Minutes | 0 | Flared MCF | 0.0 | Cum. Flared MCF | 0.0 |
|----------|--------------------|---|------------|-----|-----------------|-----|

| | | | | | | | | | | | |
|------------------------------|-----|------------|-----|-----------|-----|-----|-------|--------|-------|-----|----------------|
| SURFACE PUMP/BHA INFORMATION | | | | | | | | | | | |
| Pump 1 Liner | 6.5 | Stroke Len | 9.0 | SPM | 114 | PSI | 2,100 | GPM | 400 | SPR | Slow PSI |
| Pump 2 Liner | 6.5 | Stroke Len | 9.0 | SPM | | PSI | | GPM | | SPR | Slow PSI |
| Pump 32 Liner | | Stroke Len | | SPM | | PSI | | GPM | | SPR | Slow PSI |
| BHA Makeup | | STEERABLE | | | | | | Length | 920.7 | | Hours on BHA |
| Up Weight | | Dn Weight | | RT Weight | | | | Torque | | | Hours on Motor |

BHA MAKEUP:

| # | Component | OD | ID | Length | Weight (ft/lb) | Serial Number | Description |
|----|--------------|-------|-------|--------|----------------|---------------|----------------------------|
| 1 | BIT | 7.875 | 1.000 | 1.00 | | JJ5062 | SMITHMDSI516 |
| 2 | MUD MOTOR | 6.500 | 1.000 | 32.12 | | 650-077 | 1.5 DEG FBH 7/8 5.7 .24 |
| 3 | MONEL | 6.500 | 3.250 | 30.61 | | EN122-1 | 4.5 XH P x B |
| 4 | GAP SUB | 6.500 | 3.250 | 5.20 | | 650-0053 | 4.5 XH P x B |
| 5 | MONEL | 6.500 | 2.813 | 30.28 | | EN0815-12 | 4.5 XH P x B |
| 6 | MONEL | 6.500 | 2.813 | 30.22 | | EN0814-12 | 4.5 XH P x B |
| 7 | DC | 6.500 | 2.250 | 31.06 | | RIG | 4.5 XH P x B |
| 8 | (18) HWDP | 4.500 | 2.313 | 547.01 | | RIG | 4.5 XH P x B |
| 9 | DRILLING JAR | 6.500 | 2.813 | 31.11 | | SR-2056 | 4.5 XH P x B(SMITH)HE JARS |
| 10 | (6) HWDP | 4.500 | 2.313 | 182.09 | | RIG | 4.5 XH P x B |

| DAILY COSTS | DAILY | CUM | AFE | | DAILY | CUM | AFE |
|--------------------------------|--------|--------|---------|--------------------------------|--------|---------|---------|
| 8100..100: Permits & Fees | | | 4,500 | 8100..105: Insurance | | | 2,500 |
| 8100..110: Staking & Surveying | | | 1,500 | 8100..120: Surface Damages & R | | | |
| 8100..200: Location Roads | | | 30,000 | 8100..210: Reclamation | | | |
| 8100..220: Secondary Reclamati | | | | 8100..230: Pit Solidification | | | 5,000 |
| 8100..300: Water Well | | | | 8100..310: Water/Water Disposa | | 6,716 | 10,000 |
| 8100..320: Mud & Chemicals | | | 55,000 | 8100..325: Oil Base Mud Diesel | | | 35,000 |
| 8100..400: Drilling Rig | 19,425 | 70,210 | 135,000 | 8100..402: Drilling Rig Cleani | | | 5,000 |
| 8100..405: Rig Fuel | | | 20,000 | 8100..410: Mob/Demob | | | |
| 8100..420: Bits & Reamers | | | 17,500 | 8100..500: Roustabout Services | | | 4,000 |
| 8100..510: Testing/Inspection/ | | | 1,000 | 8100..520: Trucking & Hauling | | | 23,000 |
| 8100..530: Equipment Rental | 4,497 | 8,994 | 17,000 | 8100..531: Down Hole Motor Ren | | | 1,500 |
| 8100..532: Solids Control Equi | 390 | 780 | 10,000 | 8100..535: Directional Drillin | | | 65,000 |
| 8100..540: Fishing | | | | 8100..600: Surface Casing/Inte | | 19,591 | 35,000 |
| 8100..605: Cementing Work | | 13,740 | 25,000 | 8100..610: P & A | | | |
| 8100..700: Logging - Openhole | | | 14,000 | 8100..705: Logging - Mud | | | |
| 8100..800: Supervision/Consult | 2,750 | 5,500 | 35,000 | 8100..810: Engineering/Evaluat | | | |
| 8100..900: Contingencies | 2,977 | 5,954 | | 8100..950: Administrative O/H | | | |
| 8100..999: Non Operated IDC | | | | 8200..510: Testing/Inspection/ | | | 2,000 |
| 8200..520: Trucking & Hauling | | | 11,500 | 8200..530: Equipment Rental | | | 20,000 |
| 8200..605: Cementing Work | | 19,156 | 25,000 | 8210..600: Production Casing | | | 50,000 |
| 8210..620: Wellhead/Casing Hea | | | 15,000 | Total Cost | 30,039 | 150,640 | 675,000 |

ULTRA RESOURCES, INC.
DAILY DRILLING REPORT DATE: 07/21/2014

| | | | | | | | | | | |
|----------------------|-------------------------|------------------|--------------------------------|-------------------|---------------|----------------|-------------|----------------------|------|---|
| WELL NAME | THREE RIVERS 16-42L-820 | | | AFE# | 140625 | | SPUD DATE | 07/20/2014 | | |
| WELL SITE CONSULTANT | JARED MEJORADO | | | PHONE# | 435-828-5550 | | CONTRACTOR | Ensign 122 | | |
| TD AT REPORT | 4,362' | FOOTAGE | 3,292' | PRATE | 153.1 | CUM. DRLG. HRS | 36.5 | DRLG DAYS SINCE SPUD | 1 | |
| ANTICIPATED TD | 6,443' | PRESNET OPS | Directional Drilling at 4,362' | | | GEOLOGIC SECT. | | | | |
| DAILY MUD LOSS | SURF: | 22 | DH: | 0 | CUM. MUD LOSS | SURF: | 22 | DH: | 0 | |
| MUD COMPANY: | NEWPARK | | | MUD ENGINEER: | | | NICK LATHAM | | | |
| LAST BOP TEST | 07/19/2014 | NEXT CASING SIZE | 5 1/2 | NEXT CASING DEPTH | | 6,400 | SSE | 1 | SSED | 3 |

| | | | | | | | | | |
|----------------------|-------|--|--|-----------------|------|--|--|-------------|------|
| TIME BREAKDOWN | | | | | | | | | |
| DIRECTIONAL DRILLING | 21.50 | | | DRILLING CEMENT | 2.00 | | | RIG SERVICE | 0.50 |

| DETAILS | | | |
|---------|-------|-------|--|
| Start | End | Hrs | |
| 06:00 | 08:00 | 02:00 | DRILL OUT CEMENT & FLOAT EQUIPMENT - TAG FLOAT @ 1010 SHOE @ 1055' |
| 08:00 | 17:30 | 09:30 | DRILL F/ 1055' T/ 2958' 1903'@ 200'HR W/ 20-24K WT ON BIT - 470GPM - 60-65RPM - 350-450 DIFF - 10-12K TORQUE - 2000PSI SPP |
| 17:30 | 18:00 | 00:30 | DAILY RIG SERVICE |
| 18:00 | 06:00 | 12:00 | DRILL F/ 2958' T/ 4362' 1404'@ 117'HR W/ 20-24K WT ON BIT - 470GPM - 60-65RPM - 350-450 DIFF - 10-12K TORQUE - 2100PSI SPP |
| 05:55 | 05:55 | 00:00 | SAFETY MEETING DAYS:MAKING CONNECTIONS |
| | | | SAFETY MEETING NIGHTS:MIXING CHEMICALS |
| | | | REGULATORY NOTICES: NONE. |
| | | | REGULATORY VISITS:NONE. |
| | | | INCIDENTS:NONE. |
| | | | SAFETY DRILLS:NONE. |

| | | | |
|---------------------|--|-------------------------|--|
| AFE Days vs Depth: | | AFE Cost Vs Depth: | |
| DWOP Days vs Depth: | | # LL/BP Received Today: | |

| | | | | | |
|----------------------|---------|----------|-------------|---------|----------|
| FUEL AND WATER USAGE | | | | | |
| Fluid | Used | Received | Transferred | On Hand | Cum.Used |
| Fuel | 1,400.0 | | | 2,450.0 | 1,400.0 |
| Gas | | | | | |
| Fresh Well Water | | | | | |
| Nano Water | | | | | |
| Frac Water | | | | | |
| Reserve Pit Water | | | | | |
| Boiler Hours | | | | | |
| Air Heater Hours | | | | | |
| Urea | | | | 0.0 | |
| Urea Sys 1 Hrs | | | | | |
| Urea Sys 2 Hrs | | | | | |
| Urea Sys 3 Hrs | | | | | |

| | | | | | | | |
|---------------------|------------|-------|--------|--------|-------|-----------|---------|
| RECENT CASINGS RUN: | Date Set | Size | Grade | Weight | Depth | FIT Depth | FIT ppg |
| Surface | 05/01/2014 | 8 5/8 | J-55 | 24 | 1,060 | | |
| Conductor | 04/21/2014 | 16 | ARJ-55 | 45 | 118 | | |

| | | | | | | | | | | |
|--------------|-------|-------|-------|------------|----------------|-------|----------|-----------|-----------------|--|
| RECENT BITS: | | | | | | | | | | |
| BIT | SIZE | MANUF | TYPE | SERIAL NO. | JETS | TFA | DEPTH IN | DEPTH OUT | I-O-D-L-B-G-O-R | |
| 1 | 7.875 | SEC | MM55M | 12450966 | 12/12/12/12/12 | 0.552 | 1,070 | | ----- | |

| | | | | | | | | | | | |
|-----------------|-----|--------|-----|-------|------|-------|-----------|----------|---------|----------|---------|
| BIT OPERATIONS: | | | | | | | | | | | |
| BIT | WOB | RPM | GPM | PRESS | HHP | HRS | 24hr DIST | 24HR ROP | CUM HRS | CUM DIST | CUM ROP |
| 1 | | 63/107 | 447 | 2,000 | 3.20 | 21.50 | 3,292 | 153.12 | 21.50 | 3,292 | 153.12 |

| | | | | | | | | | | | |
|--------------------|-------|------------|-----------|------------|-------|----------|-----------|------------|----------|--|--|
| RECENT MUD MOTORS: | | | | | | | | | | | |
| # | SIZE | MANUF | TYPE | SERIAL NO. | LOBES | DEPTH IN | DEPTH OUT | DATE IN | DATE OUT | | |
| 1 | 6.750 | DYNA DRILL | 1.5 FIXED | EN650684 | 7/8 5 | 1,070 | | 07/20/2014 | | | |

| | | | | | | | | | | | |
|-----------------------|-----|---------|-------|-----------|----------|---------|----------|---------|--|--|--|
| MUD MOTOR OPERATIONS: | | | | | | | | | | | |
| # | WOB | REV/GAL | HRS | 24hr DIST | 24HR ROP | CUM HRS | CUM DIST | CUM ROP | | | |
| 1 | 20 | 0.24 | 21.50 | 3,292 | 153.12 | 21.50 | 3,292 | 153.12 | | | |

| | | | | | | | | | | |
|------------|-------|------|---------|-------|-------|--------|------|-----|-----------|--|
| SURVEYS | | | | | | | | | | |
| Date | TMD | Incl | Azimuth | TVD | VS | NS | EW | DLS | Tool Type | |
| 07/21/2014 | 4,222 | 0.9 | 157.10 | 4,222 | -13.9 | -16.13 | 0.90 | 0.2 | | |
| 07/21/2014 | 4,131 | 0.7 | 163.10 | 4,131 | -12.7 | -14.94 | 0.46 | 0.4 | | |
| 07/21/2014 | 4,041 | 0.4 | 178.80 | 4,041 | -11.9 | -14.10 | 0.30 | 0.0 | | |

| MUD PROPERTIES | | | | | | | | | |
|----------------|--|----------------|------|--------|-------|----------|------|----------------|--|
| Type | LSND | Mud Wt | 9.6 | Alk. | 1.5 | Sand % | 0.0 | XS Lime lb/bbl | |
| Temp. | 94 | Gels 10sec | 3 | Cl ppm | 4,500 | Solids % | 11.0 | Salt bbls | |
| Visc | 41 | Gels 10min | 6 | Ca ppm | 80 | LGS % | 11.0 | LCM ppb | |
| PV | 8 | pH | 11.2 | pF | 1.0 | Oil % | | API WL cc | |
| YP | 7 | Filter Cake/32 | 2 | Mf | 3.0 | Water % | 96.0 | HTHP WL cc | |
| O/W Ratio | | ES | | WPS | | | | | |
| Comments: | EVOTROL 8 - EXWATE 20 - EVOLUBE S 1 - LIME 1 - NEWGEL 17 - NEWPAC R 4 - NEWPHPA 2 - NEWZAN D 4 - PALLETS 12 - SAPP 1 - SHRINKWRAP 12 | | | | | | | | |

| | | | | | | |
|----------|--------------------|---|------------|-----|-----------------|-----|
| Flaring: | Flare Foot-Minutes | 0 | Flared MCF | 0.0 | Cum. Flared MCF | 0.0 |
|----------|--------------------|---|------------|-----|-----------------|-----|

| | | | | | | | | | | | |
|------------------------------|-----------|------------|-----|-----------|-----|--------|--------|--------------|-----|----------------|----------|
| SURFACE PUMP/BHA INFORMATION | | | | | | | | | | | |
| Pump 1 Liner | 6.5 | Stroke Len | 9.0 | SPM | 114 | PSI | 2,100 | GPM | 400 | SPR | Slow PSI |
| Pump 2 Liner | 6.5 | Stroke Len | 9.0 | SPM | | PSI | | GPM | | SPR | Slow PSI |
| Pump 32 Liner | | Stroke Len | | SPM | | PSI | | GPM | | SPR | Slow PSI |
| BHA Makeup | STEERABLE | | | | | | | | | | |
| Up Weight | 120 | Dn Weight | 90 | RT Weight | 100 | Length | 920.7 | Hours on BHA | 22 | Hours on Motor | 22 |
| | | | | | | Torque | 11,600 | | | | |

BHA MAKEUP:

| # | Component | OD | ID | Length | Weight (ft/lb) | Serial Number | Description |
|----|--------------|-------|-------|--------|----------------|---------------|----------------------------|
| 1 | BIT | 7.875 | 1.000 | 1.00 | | JJ5062 | SMITHMDSI516 |
| 2 | MUD MOTOR | 6.500 | 1.000 | 32.12 | | 650-077 | 1.5 DEG FBH 7/8 5.7 .24 |
| 3 | MONEL | 6.500 | 3.250 | 30.61 | | EN122-1 | 4.5 XH P x B |
| 4 | GAP SUB | 6.500 | 3.250 | 5.20 | | 650-0053 | 4.5 XH P x B |
| 5 | MONEL | 6.500 | 2.813 | 30.28 | | EN0815-12 | 4.5 XH P x B |
| 6 | MONEL | 6.500 | 2.813 | 30.22 | | EN0814-12 | 4.5 XH P x B |
| 7 | DC | 6.500 | 2.250 | 31.06 | | RIG | 4.5 XH P x B |
| 8 | (18) HWDP | 4.500 | 2.313 | 547.01 | | RIG | 4.5 XH P x B |
| 9 | DRILLING JAR | 6.500 | 2.813 | 31.11 | | SR-2056 | 4.5 XH P x B(SMITH)HE JARS |
| 10 | (6) HWDP | 4.500 | 2.313 | 182.09 | | RIG | 4.5 XH P x B |

| DAILY COSTS | DAILY | CUM | AFE | | DAILY | CUM | AFE |
|--------------------------------|--------|--------|---------|--------------------------------|---------|---------|---------|
| 8100..100: Permits & Fees | | | 4,500 | 8100..105: Insurance | | | 2,500 |
| 8100..110: Staking & Surveying | | | 1,500 | 8100..120: Surface Damages & R | | | |
| 8100..200: Location Roads | | | 30,000 | 8100..210: Reclamation | | | |
| 8100..220: Secondary Reclamati | | | | 8100..230: Pit Solidification | | | 5,000 |
| 8100..300: Water Well | | | | 8100..310: Water/Water Disposa | 6,716 | 10,000 | |
| 8100..320: Mud & Chemicals | | | 55,000 | 8100..325: Oil Base Mud Diesel | | 35,000 | |
| 8100..400: Drilling Rig | 19,425 | 89,635 | 135,000 | 8100..402: Drilling Rig Cleani | | 5,000 | |
| 8100..405: Rig Fuel | | | 20,000 | 8100..410: Mob/Demob | | | |
| 8100..420: Bits & Reamers | | | 17,500 | 8100..500: Roustabout Services | | 4,000 | |
| 8100..510: Testing/Inspection/ | | | 1,000 | 8100..520: Trucking & Hauling | | 23,000 | |
| 8100..530: Equipment Rental | 4,497 | 13,491 | 17,000 | 8100..531: Down Hole Motor Ren | | 1,500 | |
| 8100..532: Solids Control Equi | 390 | 1,170 | 10,000 | 8100..535: Directional Drillin | | 65,000 | |
| 8100..540: Fishing | | | | 8100..600: Surface Casing/Inte | 19,591 | 35,000 | |
| 8100..605: Cementing Work | | 13,740 | 25,000 | 8100..610: P & A | | | |
| 8100..700: Logging - Openhole | | | 14,000 | 8100..705: Logging - Mud | | | |
| 8100..800: Supervision/Consult | 2,750 | 8,250 | 35,000 | 8100..810: Engineering/Evaluat | | | |
| 8100..900: Contingencies | 2,977 | 8,930 | | 8100..950: Administrative O/H | | | |
| 8100..999: Non Operated IDC | | | | 8200..510: Testing/Inspection/ | | 2,000 | |
| 8200..520: Trucking & Hauling | | | 11,500 | 8200..530: Equipment Rental | | 20,000 | |
| 8200..605: Cementing Work | | 19,156 | 25,000 | 8210..600: Production Casing | 79,879 | 79,879 | 50,000 |
| 8210..620: Wellhead/Casing Hea | | | 15,000 | Total Cost | 109,918 | 260,558 | 675,000 |

ULTRA RESOURCES, INC.
DAILY DRILLING REPORT DATE: 07/22/2014

| | | | | | | | | | |
|----------------------|-------------------------|------------------|---------------------|-------------------|--------------|----------------|------------|----------------------|---|
| WELL NAME | THREE RIVERS 16-42L-820 | | | AFE# | 140625 | SPUD DATE | 07/20/2014 | | |
| WELL SITE CONSULTANT | JARED MEJORADO | | | PHONE# | 435-828-5550 | CONTRACTOR | Ensign 122 | | |
| TD AT REPORT | 6,420' | FOOTAGE | 2,058' | PRATE | 93.5 | CUM. DRLG. HRS | 58.5 | DRLG DAYS SINCE SPUD | 2 |
| ANTICIPATED TD | 6,443' | PRESNET OPS | Circulate at 6,420' | | | GEOLOGIC SECT. | | | |
| DAILY MUD LOSS | SURF: 22 | DH: | 0 | CUM. MUD LOSS | SURF: 44 | | | DH: | 0 |
| MUD COMPANY: | NEWPARK | | | MUD ENGINEER: | NICK LATHAM | | | | |
| LAST BOP TEST | 07/19/2014 | NEXT CASING SIZE | 5 1/2 | NEXT CASING DEPTH | 6,406 | SSE | 1 | SSED | 3 |

| | | | | | | | | | |
|----------------------|------|----------------------|-------|-------------|------|--|--|--|--|
| TIME BREAKDOWN | | | | | | | | | |
| COND MUD & CIRCULATE | 0.50 | DIRECTIONAL DRILLING | 22.00 | RIG REPAIRS | 1.00 | | | | |
| RIG SERVICE | 0.50 | | | | | | | | |

| | | | | | | | | | |
|---------|-------|-------|---|--|--|--|--|--|--|
| DETAILS | | | | | | | | | |
| Start | End | Hrs | | | | | | | |
| 06:00 | 16:30 | 10:30 | DRILL F/ 4362' T/ 5495' 1133'@ 108'HR W/ 20-24K WT ON BIT - 470GPM - 60-65RPM - 350-450 DIFF - 10-12K TORQUE - 2000PSI SPP | | | | | | |
| 16:30 | 17:00 | 00:30 | DAILY RIG SERVICE | | | | | | |
| 17:00 | 18:00 | 01:00 | * REPLACE FAN BELT ON #1 MUDPUMP & LINER ON #2 MUDPUMP * | | | | | | |
| 18:00 | 05:30 | 11:30 | DRILL F/ 5495' T/ 6420' 925'@ 80'HR W/ 20-24K WT ON BIT - 470GPM - 60-65RPM - 350-450 DIFF - 10-12K TORQUE - 2200PSI SPP, TD @ 0530 7/22/2014 | | | | | | |
| 05:30 | 06:00 | 00:30 | PUMP HIGH VIS SWEEP & CIRCULATE SHAKERS CLEAN | | | | | | |
| 05:55 | 05:55 | 00:00 | SAFETY MEETING DAYS:LAST DAY STAY FOCUSED | | | | | | |
| | | | SAFETY MEETING NIGHTS:LAST DAY STAY FOCUSED | | | | | | |
| | | | REGULATORY NOTICES: NONE. | | | | | | |
| | | | REGULATORY VISITS:NONE. | | | | | | |
| | | | INCIDENTS:NONE. | | | | | | |
| | | | SAFETY DRILLS:NONE. | | | | | | |

| | | | |
|---------------------|--|-------------------------|--|
| AFE Days vs Depth: | | AFE Cost Vs Depth: | |
| DWOP Days vs Depth: | | # LL/BP Received Today: | |

| | | | | | | | | | |
|----------------------|---------|----------|-------------|---------|----------|--|--|--|--|
| FUEL AND WATER USAGE | | | | | | | | | |
| Fluid | Used | Received | Transferred | On Hand | Cum.Used | | | | |
| Fuel | 2,280.0 | 2,000.0 | | 2,170.0 | 3,680.0 | | | | |
| Gas | | | | | | | | | |
| Fresh Well Water | | | | | | | | | |
| Nano Water | | | | | | | | | |
| Frac Water | | | | | | | | | |
| Reserve Pit Water | | | | | | | | | |
| Boiler Hours | | | | | | | | | |
| Air Heater Hours | | | | | | | | | |
| Urea | | | | 0.0 | | | | | |
| Urea Sys 1 Hrs | | | | | | | | | |
| Urea Sys 2 Hrs | | | | | | | | | |
| Urea Sys 3 Hrs | | | | | | | | | |

| | | | | | | | | | |
|---------------------|------------|-------|--------|--------|-------|-----------|---------|--|--|
| RECENT CASINGS RUN: | Date Set | Size | Grade | Weight | Depth | FIT Depth | FIT ppg | | |
| Surface | 05/01/2014 | 8 5/8 | J-55 | 24 | 1,060 | | | | |
| Conductor | 04/21/2014 | 16 | ARJ-55 | 45 | 118 | | | | |

| | | | | | | | | | | | | |
|--------------|-------|-------|-------|------------|----------------|-------|----------|-----------|-----------------------|--|--|--|
| RECENT BITS: | | | | | | | | | | | | |
| BIT | SIZE | MANUF | TYPE | SERIAL NO. | JETS | TFA | DEPTH IN | DEPTH OUT | I-O-D-L-B-G-O-R | | | |
| 1 | 7.875 | SEC | MM55M | 12450966 | 12/12/12/12/12 | 0.552 | 1,070 | 6,420 | 1-2-CT-A-X-1/16-WT-TD | | | |

| | | | | | | | | | | | | |
|-----------------|-----|--------|-----|-------|------|-------|-----------|----------|---------|----------|---------|--|
| BIT OPERATIONS: | | | | | | | | | | | | |
| BIT | WOB | RPM | GPM | PRESS | HHP | HRS | 24hr DIST | 24HR ROP | CUM HRS | CUM DIST | CUM ROP | |
| 1 | | 63/107 | 447 | 2,200 | 3.27 | 22.50 | 2,058 | 91.47 | 44.00 | 5,350 | 121.59 | |

| | | | | | | | | | | | | |
|--------------------|-------|------------|-----------|------------|-------|----------|-----------|------------|------------|--|--|--|
| RECENT MUD MOTORS: | | | | | | | | | | | | |
| # | SIZE | MANUF | TYPE | SERIAL NO. | LOBES | DEPTH IN | DEPTH OUT | DATE IN | DATE OUT | | | |
| 1 | 6.750 | DYNA DRILL | 1.5 FIXED | EN650684 | 7/8 5 | 1,070 | 6,420 | 07/20/2014 | 07/22/2014 | | | |

| | | | | | | | | | | | | |
|-----------------------|-----|---------|-------|-----------|----------|---------|----------|---------|--|--|--|--|
| MUD MOTOR OPERATIONS: | | | | | | | | | | | | |
| # | WOB | REV/GAL | HRS | 24hr DIST | 24HR ROP | CUM HRS | CUM DIST | CUM ROP | | | | |
| 1 | 24 | 0.24 | 22.50 | 2,058 | 91.47 | 44.00 | 5,350 | 121.59 | | | | |

| | | | | | | | | | | | | |
|------------|-------|------|---------|-------|-------|--------|-------|-----|-----------|--|--|--|
| SURVEYS | | | | | | | | | | | | |
| Date | TMD | Incl | Azimuth | TVD | VS | NS | EW | DLS | Tool Type | | | |
| 07/22/2014 | 6,420 | 1.2 | 162.80 | 6,420 | -52.8 | -54.72 | 13.03 | 0.0 | | | | |
| 07/22/2014 | 6,370 | 1.2 | 162.80 | 6,370 | -51.8 | -53.72 | 12.72 | 0.1 | | | | |
| 07/22/2014 | 6,305 | 1.2 | 166.50 | 6,305 | -50.5 | -52.41 | 12.36 | 0.0 | | | | |

| | | | | | | | | | | | | |
|----------------|--|----------------|------|--------|-------|----------|------|----------------|--|--|--|--|
| MUD PROPERTIES | | | | | | | | | | | | |
| Type | LSND | Mud Wt | 9.8 | Alk. | 1.0 | Sand % | 0.0 | XS Lime lb/bbl | | | | |
| Temp. | 94 | Gels 10sec | 3 | Cl ppm | 4,500 | Solids % | 11.0 | Salt bbls | | | | |
| Visc | 46 | Gels 10min | 6 | Ca ppm | 80 | LGS % | 11.0 | LCM ppb | | | | |
| PV | 8 | pH | 11.2 | pF | 1.0 | Oil % | | API WL cc | | | | |
| YP | 7 | Filter Cake/32 | 2 | Mf | 3.0 | Water % | 96.0 | HTHP WL cc | | | | |
| O/W Ratio | | ES | | WPS | | | | | | | | |
| Comments: | EVOTROL 8 - EXWATE 20 - EVOLUBE S 1 - LIME 1 - NEWGEL 17 - NEWPAC R 4 - NEWPHPA 2 - NEWZAN D 4 - PALLETS 12 - SAPP 1 - SHRINKWRAP 12 | | | | | | | | | | | |

| | | | | | | |
|----------|--------------------|---|------------|-----|-----------------|-----|
| Flaring: | Flare Foot-Minutes | 0 | Flared MCF | 0.0 | Cum. Flared MCF | 0.0 |
|----------|--------------------|---|------------|-----|-----------------|-----|

| | | | | | | | | | | | | |
|------------------------------|-----|------------|-----|-----------|-----|-----|-------|--------|--------|-----|----|-------------------|
| SURFACE PUMP/BHA INFORMATION | | | | | | | | | | | | |
| Pump 1 Liner | 6.5 | Stroke Len | 9.0 | SPM | 114 | PSI | 2,100 | GPM | 400 | SPR | 65 | Slow PSI 550 |
| Pump 2 Liner | 6.5 | Stroke Len | 9.0 | SPM | | PSI | | GPM | | SPR | 65 | Slow PSI 575 |
| Pump 32 Liner | | Stroke Len | | SPM | | PSI | | GPM | | SPR | | Slow PSI |
| BHA Makeup | | STEERABLE | | | | | | Length | 920.7 | | | Hours on BHA 44 |
| Up Weight | 165 | Dn Weight | 125 | RT Weight | 142 | | | Torque | 11,600 | | | Hours on Motor 23 |

BHA MAKEUP:

| # | Component | OD | ID | Length | Weight (ft/lb) | Serial Number | Description |
|----|--------------|-------|-------|--------|----------------|---------------|----------------------------|
| 1 | BIT | 7.875 | 1.000 | 1.00 | | JJ5062 | SMITHMDSI516 |
| 2 | MUD MOTOR | 6.500 | 1.000 | 32.12 | | 650-077 | 1.5 DEG FBH 7/8 5.7 .24 |
| 3 | MONEL | 6.500 | 3.250 | 30.61 | | EN122-1 | 4.5 XH P x B |
| 4 | GAP SUB | 6.500 | 3.250 | 5.20 | | 650-0053 | 4.5 XH P x B |
| 5 | MONEL | 6.500 | 2.813 | 30.28 | | EN0815-12 | 4.5 XH P x B |
| 6 | MONEL | 6.500 | 2.813 | 30.22 | | EN0814-12 | 4.5 XH P x B |
| 7 | DC | 6.500 | 2.250 | 31.06 | | RIG | 4.5 XH P x B |
| 8 | (18) HWDP | 4.500 | 2.313 | 547.01 | | RIG | 4.5 XH P x B |
| 9 | DRILLING JAR | 6.500 | 2.813 | 31.11 | | SR-2056 | 4.5 XH P x B(SMITH)HE JARS |
| 10 | (6) HWDP | 4.500 | 2.313 | 182.09 | | RIG | 4.5 XH P x B |

| DAILY COSTS | DAILY | CUM | AFE | | DAILY | CUM | AFE |
|--------------------------------|--------|---------|---------|--------------------------------|--------|---------|---------|
| 8100..100: Permits & Fees | | | 4,500 | 8100..105: Insurance | | | 2,500 |
| 8100..110: Staking & Surveying | | | 1,500 | 8100..120: Surface Damages & R | | | |
| 8100..200: Location Roads | | | 30,000 | 8100..210: Reclamation | | | |
| 8100..220: Secondary Reclamati | | | | 8100..230: Pit Solidification | | | 5,000 |
| 8100..300: Water Well | | | | 8100..310: Water/Water Disposa | 6,716 | 10,000 | |
| 8100..320: Mud & Chemicals | | | 55,000 | 8100..325: Oil Base Mud Diesel | | 35,000 | |
| 8100..400: Drilling Rig | 19,425 | 109,060 | 135,000 | 8100..402: Drilling Rig Cleani | | 5,000 | |
| 8100..405: Rig Fuel | | | 20,000 | 8100..410: Mob/Demob | | | |
| 8100..420: Bits & Reamers | | | 17,500 | 8100..500: Roustabout Services | | 4,000 | |
| 8100..510: Testing/Inspection/ | | | 1,000 | 8100..520: Trucking & Hauling | | 23,000 | |
| 8100..530: Equipment Rental | 4,497 | 17,988 | 17,000 | 8100..531: Down Hole Motor Ren | | 1,500 | |
| 8100..532: Solids Control Equi | 390 | 1,560 | 10,000 | 8100..535: Directional Drillin | | 65,000 | |
| 8100..540: Fishing | | | | 8100..600: Surface Casing/Inte | 19,591 | 35,000 | |
| 8100..605: Cementing Work | | 13,740 | 25,000 | 8100..610: P & A | | | |
| 8100..700: Logging - Openhole | | | 14,000 | 8100..705: Logging - Mud | | | |
| 8100..800: Supervision/Consult | 2,750 | 11,000 | 35,000 | 8100..810: Engineering/Evaluat | | | |
| 8100..900: Contingencies | 2,977 | 11,907 | | 8100..950: Administrative O/H | | | |
| 8100..999: Non Operated IDC | | | | 8200..510: Testing/Inspection/ | | 2,000 | |
| 8200..520: Trucking & Hauling | | | 11,500 | 8200..530: Equipment Rental | | 20,000 | |
| 8200..605: Cementing Work | | 19,156 | 25,000 | 8210..600: Production Casing | | 79,879 | 50,000 |
| 8210..620: Wellhead/Casing Hea | | | 15,000 | Total Cost | 30,039 | 290,597 | 675,000 |

ULTRA RESOURCES, INC.
DAILY DRILLING REPORT DATE: 07/23/2014

| | | | | | | | | | | |
|----------------------|-------------------------|------------------|-----------------------|-------------------|---------------|----------------|------------|----------------------|------|---|
| WELL NAME | THREE RIVERS 16-42L-820 | | | AFE# | 140625 | | SPUD DATE | 07/20/2014 | | |
| WELL SITE CONSULTANT | JEREMY MEJORADO | | | PHONE# | 435-828-5550 | | CONTRACTOR | Ensign 122 | | |
| TD AT REPORT | 6,420' | FOOTAGE | 0' | PRATE | 0.0 | CUM. DRLG. HRS | 63.5 | DRLG DAYS SINCE SPUD | 3 | |
| ANTICIPATED TD | 6,443' | PRESENT OPS | Nipple Down at 6,420' | | | GEOLOGIC SECT. | | | | |
| DAILY MUD LOSS | SURF: | 12 | DH: | 60 | CUM. MUD LOSS | SURF: | 56 | DH: | 60 | |
| MUD COMPANY: | NEWPARK | | | MUD ENGINEER: | | JOHN LEWIS | | | | |
| LAST BOP TEST | 07/19/2014 | NEXT CASING SIZE | 5 1/2 | NEXT CASING DEPTH | | 6,400 | SSE | 0 | SSED | 0 |

| | | | | | | |
|----------------|--------------------|------|----------------------|------|----------|------|
| TIME BREAKDOWN | CASING & CEMENT | 8.00 | COND MUD & CIRCULATE | 2.00 | DRILLING | 5.00 |
| | NIPPLE DOWN B.O.P. | 3.00 | TRIPPING | 5.50 | WORK BHA | 0.50 |

| | | | | |
|---------|-------|-------|-------|---|
| DETAILS | Start | End | Hrs | |
| | 06:00 | 06:30 | 00:30 | CIRCULATE HOLE CLEAN |
| | 06:30 | 12:00 | 05:30 | T.O.O.H. FROM 6420' TO 128' |
| | 12:00 | 12:30 | 00:30 | LAY DOWN DIRECTIONAL TOOLS - PULL MWD - BREAK BIT AND DRAIN MUD MOTOR |
| | 12:30 | 17:30 | 05:00 | RIG UP LOGGERS AND LOG WELL (LOGGERS DEPTH=6418') RIG DOWN LOGGERS - NO ISSUES WHILE LOGGING |
| | 17:30 | 23:30 | 06:00 | RIG UP TO RUN 5.5" PRODUCTION CASING - RUN 145 JOINTS 5.5" 17# J-55 CASING WITH 2 MARKER JOINTS (5151', 4262') AND 43 CENTRALIZERS - CASING SET @ 6400' |
| | 23:30 | 01:00 | 01:30 | CIRCULATE AND COND MUD FOR CEMENT JOB |
| | 01:00 | 03:00 | 02:00 | SAFETY MEETING WITH HALLIBURTON - RIG UP CEMENTERS - TEST LINES TO 5000 PSI - PUMP 10 BBLS WATER SPACER, 20 BBLS 10.0 PPG SUPER FLUSH, 10 BBLS WATER SPACER, 146 BBLS 235 SACKS 11 PPG 3.5 YIELD LEAD CEMENT MIXED @ 20.92 GAL/SK, 92 BBLS 385 SKS 14 PPG 1.35 YIELD TAIL CEMENT MIXED @ 5.82 GAL/SK, SHUT DOWN WASH LINES DROP PLUG AND DISPLACE WITH 148.5 BBLS FRESH WATER - FINAL CIRCULATING PRESSURE 1510PSI BUMP PLUG AND HOLD 2100 PSI FOR TWO MINUTES - RELEASE PRESSURE FLOATS HELD - FULL RETURNS DURING JOB 15 BBLS CEMENT TO SURFACE |
| | 03:00 | 06:00 | 03:00 | NIPPLE DOWN BOP - RIG RELEASED @ 0600 7/23/14 |
| | 05:55 | 05:55 | 00:00 | SAFETY MEETING DAYS: FIRST DAY BACK/TRIPPING/LOGGING/RUNNING CASING |
| | | | | SAFETY MEETING NIGHTS:FIRSTDAY BACK/RUNNNING CASING/CEMENTING/NIPPLE DOWN |
| | | | | REGULATORY NOTICES: NONE. |
| | | | | REGULATORY VISITS:NONE. |
| | | | | INCIDENTS:NONE. |
| | | | | SAFETY DRILLS:NONE. |

| | | | |
|---------------------|--|-------------------------|--|
| AFE Days vs Depth: | | AFE Cost Vs Depth: | |
| DWOP Days vs Depth: | | # LL/BP Received Today: | |

| | | | | | |
|----------------------|-------|----------|-------------|---------|----------|
| FUEL AND WATER USAGE | Used | Received | Transferred | On Hand | Cum.Used |
| Fluid | 770.0 | 0.0 | 1,400.0 | 0.0 | 4,450.0 |
| Fuel | | | | | |
| Gas | | | | | |
| Fresh Well Water | | | | | |
| Nano Water | | | | | |
| Frac Water | | | | | |
| Reserve Pit Water | | | | | |
| Boiler Hours | | | | | |
| Air Heater Hours | | | | | |
| Urea | | | | 0.0 | |
| Urea Sys 1 Hrs | | | | | |
| Urea Sys 2 Hrs | | | | | |
| Urea Sys 3 Hrs | | | | | |

CEMENT JOB SUMMARY
SAFETY MEETING WITH HALLIBURTON - RIG UP CEMENTERS - TEST LINES TO 5000 PSI - PUMP 10 BBLS WATER SPACER, 20 BBLS 10.0 PPG SUPER FLUSH, 10 BBLS WATER SPACER, 146 BBLS 235 SACKS 11 PPG 3.5 YIELD LEAD CEMENT MIXED @ 20.92 GAL/SK, 92 BBLS 385 SKS 14 PPG 1.35 YIELD TAIL CEMENT MIXED @ 5.82 GAL/SK, SHUT DOWN WASH LINES DROP PLUG AND DISPLACE WITH 148.5 BBLS FRESH WATER - FINAL CIRCULATING PRESSURE 1510PSI BUMP PLUG AND HOLD 2100 PSI FOR TWO MINUTES - RELEASE PRESSURE FLOATS HELD - FULL RETURNS DURING JOB 15 BBLS CEMENT TO SURFACE

| | | | | | | | |
|---------------------|------------|-------|--------|--------|-------|-----------|---------|
| RECENT CASINGS RUN: | Date Set | Size | Grade | Weight | Depth | FIT Depth | FIT ppg |
| Production | 07/23/2014 | 5 1/2 | J-55 | 17 | 6,400 | | |
| Surface | 05/01/2014 | 8 5/8 | J-55 | 24 | 1,060 | | |
| Conductor | 04/21/2014 | 16 | ARJ-55 | 45 | 118 | | |

| | | | | | | | | | | |
|--------------|-----|-------|-------|-------|------------|----------------|-------|----------|-----------|-----------------------|
| RECENT BITS: | BIT | SIZE | MANUF | TYPE | SERIAL NO. | JETS | TFA | DEPTH IN | DEPTH OUT | I-O-D-L-B-G-O-R |
| | 1 | 7.875 | SEC | MM55M | 12450966 | 12/12/12/12/12 | 0.552 | 1,070 | 6,420 | 1-2-CT-A-X-1/16-WT-TD |

| | | | | | | | | | | | | |
|-----------------|-----|-----|--------|-----|-------|------|-------|-----------|----------|---------|----------|---------|
| BIT OPERATIONS: | BIT | WOB | RPM | GPM | PRESS | HHP | HRS | 24hr DIST | 24HR ROP | CUM HRS | CUM DIST | CUM ROP |
| | 1 | | 63/107 | 447 | 2,200 | 3.27 | 22.50 | 2,058 | 91.47 | 44.00 | 5,350 | 121.59 |

| | | | | | | | | | | |
|--------------------|---|-------|------------|-----------|------------|-------|----------|-----------|------------|------------|
| RECENT MUD MOTORS: | # | SIZE | MANUF | TYPE | SERIAL NO. | LOBES | DEPTH IN | DEPTH OUT | DATE IN | DATE OUT |
| | 1 | 6.750 | DYNA DRILL | 1.5 FIXED | EN650684 | 7/8 5 | 1,070 | 6,420 | 07/20/2014 | 07/22/2014 |

| | | | | | | | | | |
|-----------------------|---|-----|---------|-------|-----------|----------|---------|----------|---------|
| MUD MOTOR OPERATIONS: | # | WOB | REV/GAL | HRS | 24hr DIST | 24HR ROP | CUM HRS | CUM DIST | CUM ROP |
| | 1 | 24 | 0.24 | 22.50 | 2,058 | 91.47 | 44.00 | 5,350 | 121.59 |

| | | | | | | | | | | |
|---------|------------|-------|------|---------|-------|-------|--------|-------|-----|-----------|
| SURVEYS | Date | TMD | Incl | Azimuth | TVD | VS | NS | EW | DLS | Tool Type |
| | 07/22/2014 | 6,420 | 1.2 | 162.80 | 6,420 | -52.8 | -54.72 | 13.03 | 0.0 | |
| | 07/22/2014 | 6,370 | 1.2 | 162.80 | 6,370 | -51.8 | -53.72 | 12.72 | 0.1 | |
| | 07/22/2014 | 6,305 | 1.2 | 166.50 | 6,305 | -50.5 | -52.41 | 12.36 | 0.0 | |

| | | | | | | | | | | |
|----------------|---|------|----------------|-----|--------|-------|----------|------|----------------|-----|
| MUD PROPERTIES | Type | LSND | Mud Wt | 9.8 | Alk. | 1.0 | Sand % | 0.0 | XS Lime lb/bbl | |
| | Temp. | 96 | Gels 10sec | 6 | Cl ppm | 4,000 | Solids % | 10.7 | Salt bbls | |
| | Visc | 48 | Gels 10min | 9 | Ca ppm | 80 | LGS % | 10.7 | LCM ppb | |
| | PV | 12 | pH | 9.6 | pF | 1.0 | Oil % | | API WL cc | 8.0 |
| | YP | 11 | Filter Cake/32 | 2 | Mf | 3.0 | Water % | 89.0 | HTHP WL cc | |
| | O/W Ratio | | ES | | WPS | | | | | |
| Comments: | DYNAFIBER 8, ENGINEER 1, EXWATE 64, GSX 510 5, LIME 4, NEWGEL 15, NEWPAC R 5, NEWPHALT 13, NEWZAN D 16, PALLETS 14, SAPP 1, SAWDUST 30, SHRINKWRAP 14 | | | | | | | | | |

| | | | | | | |
|----------|--------------------|---|------------|-----|-----------------|-----|
| Flaring: | Flare Foot-Minutes | 0 | Flared MCF | 0.0 | Cum. Flared MCF | 0.0 |
|----------|--------------------|---|------------|-----|-----------------|-----|

SURFACE PUMP/BHA INFORMATION

| | | | | | | | | | | | | | | | |
|---------------|---------------|------------|---------------|-----------|---------------|--------|---------------|-----|---------------|----------------|---------------|-----------|---------------|--------------|-----------|
| Pump 1 Liner | <u>6.5</u> | Stroke Len | <u>9.0</u> | SPM | <u>114</u> | PSI | <u>2,100</u> | GPM | <u>400</u> | SPR | <u>65</u> | Slow PSI | <u>550</u> | | |
| Pump 2 Liner | <u>6.5</u> | Stroke Len | <u>9.0</u> | SPM | <u> </u> | PSI | <u> </u> | GPM | <u> </u> | SPR | <u>65</u> | Slow PSI | <u>575</u> | | |
| Pump 32 Liner | <u> </u> | Stroke Len | <u> </u> | SPM | <u> </u> | PSI | <u> </u> | GPM | <u> </u> | SPR | <u> </u> | Slow PSI | <u> </u> | | |
| BHA Makeup | STEERABLE | | | | | | | | | | Length | | <u>920.7</u> | Hours on BHA | <u>44</u> |
| Up Weight | <u>165</u> | Dn Weight | <u>125</u> | RT Weight | <u>142</u> | Torque | | | <u>11,600</u> | Hours on Motor | | <u>23</u> | | | |
| | | | | | | | | | | | | | | | |

BHA MAKEUP:

| # | Component | OD | ID | Length | Weight (ft/lb) | Serial Number | Description |
|----|--------------|-------|-------|--------|----------------|---------------|----------------------------|
| 1 | BIT | 7.875 | 1.000 | 1.00 | | JJ5062 | SMITHMDSI516 |
| 2 | MUD MOTOR | 6.500 | 1.000 | 32.12 | | 650-077 | 1.5 DEG FBH 7/8 5.7 .24 |
| 3 | MONEL | 6.500 | 3.250 | 30.61 | | EN122-1 | 4.5 XH P x B |
| 4 | GAP SUB | 6.500 | 3.250 | 5.20 | | 650-0053 | 4.5 XH P x B |
| 5 | MONEL | 6.500 | 2.813 | 30.28 | | EN0815-12 | 4.5 XH P x B |
| 6 | MONEL | 6.500 | 2.813 | 30.22 | | EN0814-12 | 4.5 XH P x B |
| 7 | DC | 6.500 | 2.250 | 31.06 | | RIG | 4.5 XH P x B |
| 8 | (18) HWDP | 4.500 | 2.313 | 547.01 | | RIG | 4.5 XH P x B |
| 9 | DRILLING JAR | 6.500 | 2.813 | 31.11 | | SR-2056 | 4.5 XH P x B(SMITH)HE JARS |
| 10 | (6) HWDP | 4.500 | 2.313 | 182.09 | | RIG | 4.5 XH P x B |

DAILY COSTS

| | DAILY | CUM | AFE | | DAILY | CUM | AFE |
|--------------------------------|--------|---------|---------|--------------------------------|---------|---------|---------|
| 8100..100: Permits & Fees | | | 4,500 | 8100..105: Insurance | | | 2,500 |
| 8100..110: Staking & Surveying | | | 1,500 | 8100..120: Surface Damages & R | | | |
| 8100..200: Location Roads | | | 30,000 | 8100..210: Reclamation | | | |
| 8100..220: Secondary Reclamati | | | | 8100..230: Pit Solidification | | | 5,000 |
| 8100..300: Water Well | | | | 8100..310: Water/Water Disposa | 992 | 7,708 | 10,000 |
| 8100..320: Mud & Chemicals | 9,917 | 9,917 | 55,000 | 8100..325: Oil Base Mud Diesel | | | 35,000 |
| 8100..400: Drilling Rig | 19,425 | 128,485 | 135,000 | 8100..402: Drilling Rig Cleani | | | 5,000 |
| 8100..405: Rig Fuel | 6,505 | 6,505 | 20,000 | 8100..410: Mob/Demob | 2,000 | 2,000 | |
| 8100..420: Bits & Reamers | 13,400 | 13,400 | 17,500 | 8100..500: Roustabout Services | 4,480 | 4,480 | 4,000 |
| 8100..510: Testing/Inspection/ | | | 1,000 | 8100..520: Trucking & Hauling | | | 23,000 |
| 8100..530: Equipment Rental | 4,497 | 22,485 | 17,000 | 8100..531: Down Hole Motor Ren | | | 1,500 |
| 8100..532: Solids Control Equi | 390 | 1,950 | 10,000 | 8100..535: Directional Drillin | 28,475 | 28,475 | 65,000 |
| 8100..540: Fishing | | | | 8100..600: Surface Casing/Inte | | 19,591 | 35,000 |
| 8100..605: Cementing Work | | 13,740 | 25,000 | 8100..610: P & A | | | |
| 8100..700: Logging - Openhole | 12,219 | 12,219 | 14,000 | 8100..705: Logging - Mud | | | |
| 8100..800: Supervision/Consult | 2,750 | 13,750 | 35,000 | 8100..810: Engineering/Evaluat | | | |
| 8100..900: Contingencies | 13,330 | 25,237 | | 8100..950: Administrative O/H | | | |
| 8100..999: Non Operated IDC | | | | 8200..510: Testing/Inspection/ | | | 2,000 |
| 8200..520: Trucking & Hauling | | | 11,500 | 8200..530: Equipment Rental | | | 20,000 |
| 8200..605: Cementing Work | 31,430 | 50,586 | 25,000 | 8210..600: Production Casing | 3,881 | 83,760 | 50,000 |
| 8210..620: Wellhead/Casing Hea | | | 15,000 | Total Cost | 153,690 | 444,287 | 675,000 |

43 047 54269

Accumulator Function Test

Lease # 16-424-820 Operator Ultra Res
 Rig Name & # Ensign 122 Location 1/4 1/4 16 T8S R 20E
 Inspector Brian Brown Date 7-20-14

TO CHECK THE USABLE FLUID STORED IN THE NITROGEN BOTTLES ON THE ACCUMULATOR (O.S.O. #2 section, III.A.2.c.i. or ii or iii)

1. Make sure all rams and annular are open and if applicable HCR is closed.
2. Ensure accumulator is pumped up to working pressure! (Shut off all pumps)
3. Open HCR Valve. (If applicable)
4. Close annular.
5. Close all pipe rams.
6. Open one set of the pipe rams to simulate closing the blind ram.
7. If you have a 3 ram stack, open the annular to achieve the 50±% safety factor for 5M and greater systems).
8. Accumulator pressure should be 200 psi above the desired pre-charge pressure, (Accumulator working pressure {1500 psi = 750 desired psi} {2000 and 3000 psi = 1000 desired psi}).

9. Record the remaining pressure 1,500 psi.
 If annular is closed, open it at this time and close HCR.

TO CHECK THE PRECHARGE ON BOTTLES OR SPHERICAL (O.S.O. #2 section III.A.2.d.)

1. The manifold pre-charge pressure should be above the desired pre-charge pressure, {1500 psi = 750 desired psi} {2000 and 3000 psi = 1000 desired psi}) may need to use pumps to pressure back up.
2. With power to pumps shut off open bleed line to the tank.
3. Watch and record where the pressure drops, (accumulator psi).

Record the pressure drop 1000 psi.

If the pressure drops below the MINIMUM pre-charge, (Accumulator working pressure {1500 psi = 700 min.} {2000 and 3000 psi = 900 psi min.}), each bottle shall be independently checked with a gauge and recharged with nitrogen to the desired pre-charge pressure. (Accumulator working pressure {1500 psi = 750 desired psi} {2000 and 3000 psi = 1000 desired psi}).


TO CHECK THE CAPACITY OF THE ACCUMULATOR PUMPS (O.S.O. #2 section III.A.2.f.)

Shut the accumulator bottles or spherical, (isolate them from the pumps & manifold) open the bleed off valve to the tank, (manifold psi should go to 0 psi) close bleed valve.

1. Open the HCR valve, (if applicable).
2. Close annular.
3. With pumps only, time how long it takes to regain manifold pressure to 200 psi over desired pre-charge pressure! (Accumulator working pressure {1500 psi = 750 desired psi} {2000 and 3000 psi = 1000 desired psi}).

4. Record elapsed time 12 sec. (2 minutes or less)
 Open bottles or spherical back up and turn pumps on.

X:



Witness


10 min low 250 psi
10 min High 3000 psi

RECEIVED

JUL 23 2014

DIV. OF OIL, GAS & MINING

| | |
|------------------|-------------------|
| DATE | 7-19-14 / 7-20-14 |
| COMPANY | ultra |
| CONTRACTOR | Ensign 122 |
| WELL NAME AND TR | 16-42L-820 |



DATE: 7-20-14 COMPANY: Ultra

RIG: Ensign 122


WELL NAME: TR 16-424-820


| Time | Test No. | | Result: |
|--|----------|---|--|
| 1:50 AM <input checked="" type="checkbox"/> PM <input type="checkbox"/> | 1 | Hydraulic IBOP | Pass <input checked="" type="checkbox"/> Fail <input type="checkbox"/> |
| 3:05 AM <input checked="" type="checkbox"/> PM <input type="checkbox"/> | 2 | Annular | Pass <input checked="" type="checkbox"/> Fail <input type="checkbox"/> |
| 3:33 AM <input checked="" type="checkbox"/> PM <input type="checkbox"/> | 3 | Pipe rams Inside choke Inside Kill TIW | Pass <input type="checkbox"/> Fail <input checked="" type="checkbox"/> |
| 4:52 AM <input checked="" type="checkbox"/> PM <input type="checkbox"/> | 4 | Isolation valve | Pass <input checked="" type="checkbox"/> Fail <input type="checkbox"/> |
| 6:30 AM <input checked="" type="checkbox"/> PM <input type="checkbox"/> | 5 | Pipe rams Inside choke Inside Kill TIW | Pass <input type="checkbox"/> Fail <input checked="" type="checkbox"/> |
| 9:15 AM <input checked="" type="checkbox"/> PM <input type="checkbox"/> | 6 | Pipe rams HCR Inside Kill TIW | Pass <input checked="" type="checkbox"/> Fail <input type="checkbox"/> |
| 10:17 AM <input checked="" type="checkbox"/> PM <input type="checkbox"/> | 7 | Inside manifold valves blind rams check valve | Pass <input checked="" type="checkbox"/> Fail <input type="checkbox"/> |
| 10:59 AM <input checked="" type="checkbox"/> PM <input type="checkbox"/> | 8 | outside manifold valves | Pass <input checked="" type="checkbox"/> Fail <input type="checkbox"/> |
| 11:50 AM <input checked="" type="checkbox"/> PM <input type="checkbox"/> | 9 | Inside choke valve | Pass <input checked="" type="checkbox"/> Fail <input type="checkbox"/> |
| 12:20 AM <input checked="" type="checkbox"/> PM <input type="checkbox"/> | 10 | down stream manifold valves Riser Valve | Pass <input checked="" type="checkbox"/> Fail <input type="checkbox"/> |
| 12:52 AM <input checked="" type="checkbox"/> PM <input type="checkbox"/> | 11 | Super choke | Pass <input checked="" type="checkbox"/> Fail <input type="checkbox"/> |
| 2:00 AM <input checked="" type="checkbox"/> PM <input type="checkbox"/> | 12 | Casing | Pass <input type="checkbox"/> Fail <input type="checkbox"/> |
| AM <input type="checkbox"/> PM <input type="checkbox"/> | 13 | | Pass <input type="checkbox"/> Fail <input type="checkbox"/> |
| AM <input type="checkbox"/> PM <input type="checkbox"/> | 14 | | Pass <input type="checkbox"/> Fail <input type="checkbox"/> |
| AM <input type="checkbox"/> PM <input type="checkbox"/> | Retest | | Pass <input type="checkbox"/> Fail <input checked="" type="checkbox"/> |
| AM <input type="checkbox"/> PM <input type="checkbox"/> | Retest | | Pass <input type="checkbox"/> Fail <input type="checkbox"/> |
| AM <input type="checkbox"/> PM <input type="checkbox"/> | Retest | | Pass <input type="checkbox"/> Fail <input type="checkbox"/> |
| AM <input type="checkbox"/> PM <input type="checkbox"/> | Retest | | Pass <input type="checkbox"/> Fail <input type="checkbox"/> |
| AM <input type="checkbox"/> PM <input type="checkbox"/> | Retest | | Pass <input type="checkbox"/> Fail <input type="checkbox"/> |
| AM <input type="checkbox"/> PM <input type="checkbox"/> | Retest | | Pass <input type="checkbox"/> Fail <input type="checkbox"/> |
| AM <input type="checkbox"/> PM <input type="checkbox"/> | Retest | | Pass <input type="checkbox"/> Fail <input type="checkbox"/> |

Acc. Tank Size (Inches) (W D L) ÷ 231 = gal.

Rock Springs, WY (307) 382-3350

BOP TESTING, CASING TESTING, LEAK OFF TESTING, &
 INTEGRITY TESTING
 NIPPLE UP CREWS, NITROGEN CHARGING SERVICE





6 AM

NOON

MIDNIGHT

96
Graphic Controls LLC

7-20-14

CHART NO. MC MP-15000

ENSIGN
122

METER
ultra 905

TAKEN OFF

CHART PUT ON

M

LOCATION T2 6-426-822

REMARKS API # 43-047-52640

3043

844

WALKER INSPECTION, LLC.
REBEL TESTING • EAGER BEAVER TESTERS
WYOMING • COLORADO • NORTH DAKOTA

Daily JSA/Observation Report

OPERATOR: Ultra ResDATE: 7-19-14 / 7-20-14LOCATION: TR 16-42L #20CONTRACTOR: Ensign 122EMPLOYEE NAME: Brandon RarrCOMMENTS: 3K BOP TESToff floor out of Chokehouse out of subDATE: 7-20-14☒ High Pressure Testing☒ Working Below Platform☒ Requires PPE☐ Overhead Work is Occurring☐ Confined Spaces are Involved☐ Set up of Containment☐ Using Rig Hoist to Lift Tools☐ Other: _____SIGNATURE: B. Rarr

WALKER INSPECTION, LLC. AND AFFILIATES

ATTENDANCE:

| | | |
|---------------------|---------------------|--|
| <u>B. Rarr</u> | <u>Brandon Rarr</u> | |
| <u>Brandon Rarr</u> | | |
| <u>Brandon Rarr</u> | | |
| <u>Brandon Rarr</u> | | |
| <u>Brandon Rarr</u> | | |
| <u>Brandon Rarr</u> | | |
| <u>Brandon Rarr</u> | | |
| <u>Brandon Rarr</u> | | |
| <u>Brandon Rarr</u> | | |
| <u>Brandon Rarr</u> | | |

Observation Report

EMPLOYEE REPORTING: B. Rarr SIGNATURE: B. RarrWas job set up and performed correctly and to best of companies ability? Y/NWas all safety equipment used correctly by all involved? Y/NAny incidents or near misses to report about WI? Y/NAny incidents or near misses to report in general? Y/NAny spills or environmental issues to report? Y/N

Basic Comments: _____

| | | |
|--|--|--|
| STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING | | FORM 9 |
| SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals. | | 5. LEASE DESIGNATION AND SERIAL NUMBER: ML-49319 |
| 1. TYPE OF WELL Oil Well | | 6. IF INDIAN, ALLOTTEE OR TRIBE NAME: |
| 2. NAME OF OPERATOR: ULTRA RESOURCES INC | | 7. UNIT or CA AGREEMENT NAME: |
| 3. ADDRESS OF OPERATOR: 304 Inverness Way South #295, Englewood, CO, 80112 | | 8. WELL NAME and NUMBER: Three Rivers 16-42L-820 |
| 4. LOCATION OF WELL FOOTAGES AT SURFACE: 2006 FNL 0607 FEL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: SENE Section: 16 Township: 08.0S Range: 20.0E Meridian: S | | 9. API NUMBER: 43047542690000 |
| PHONE NUMBER: 303 645-9810 Ext | | 9. FIELD and POOL or WILDCAT: THREE RIVERS |
| COUNTY: UTAH | | STATE: UTAH |

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

| TYPE OF SUBMISSION | TYPE OF ACTION | | | |
|--|---|---|--|---|
| <input type="checkbox"/> NOTICE OF INTENT Approximate date work will start: | <input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE | <input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER | <input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION | OTHER: <input style="width: 100px;" type="text"/> |
| <input checked="" type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: 8/7/2014 | <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION | <input checked="" type="checkbox"/> PRODUCTION START OR RESUME | | |
| <input type="checkbox"/> SPUD REPORT Date of Spud: | | | | |
| <input type="checkbox"/> DRILLING REPORT Report Date: | | | | |

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.
 First Production occurred on the TR16-42L-820 on 08/07/2014.

Accepted by the
 Utah Division of
 Oil, Gas and Mining
FOR RECORD ONLY
 August 18, 2014

| | | |
|--|-------------------------------------|--------------------------------------|
| NAME (PLEASE PRINT) Jenna Anderson | PHONE NUMBER 303 645-9804 | TITLE Permitting Assistant |
| SIGNATURE N/A | DATE 8/8/2014 | |

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MININGAMENDED REPORT ☐ FORM 8
(highlight changes)5. LEASE DESIGNATION AND SERIAL NUMBER:
ML49319

6. IF INDIAN, ALLOTTEE OR TRIBE NAME

7. UNIT or CA AGREEMENT NAME

8. WELL NAME and NUMBER:
THREE RIVERS 16-42L-8209. API NUMBER:
430475426910. FIELD AND POOL, OR WILDCAT
THREE RIVERS11. QTR/QTR, SECTION, TOWNSHIP, RANGE,
MERIDIAN:
SENE 16 8S 20E S12. COUNTY
Uintah13. STATE
UTAH

WELL COMPLETION OR RECOMPLETION REPORT AND LOG

1a. TYPE OF WELL: OIL WELL ☒ GAS WELL ☐ DRY ☐ OTHERb. TYPE OF WORK: NEW WELL ☒ HORIZ. LATS. ☐ DEEP-EN ☐ RE-ENTRY ☐ DIFF. RESVR. ☐ OTHER2. NAME OF OPERATOR:
Ultra Resources, Inc.3. ADDRESS OF OPERATOR:
304 Inverness Way So. CITY Englewood STATE CO ZIP 80112 PHONE NUMBER:
(303) 645-98044. LOCATION OF WELL (FOOTAGES)
AT SURFACE: 2006 FNL 607 FEL 40.1244 109.665986
AT TOP PRODUCING INTERVAL REPORTED BELOW: 1944 FNL 665 FEL 40.124569 109.666191
AT TOTAL DEPTH: 1987 FNL 671 FEL 40.12445 109.66621514. DATE SPUDDED:
4/21/201415. DATE T.D. REACHED:
7/22/201416. DATE COMPLETED:
8/13/2014ABANDONED ☐ READY TO PRODUCE ☒17. ELEVATIONS (DF, RKB, RT, GL):
GL 4702.918. TOTAL DEPTH: MD 6,420
TVD 6,41519. PLUG BACK T.D.: MD 6,399
TVD 6,394

20. IF MULTIPLE COMPLETIONS, HOW MANY? *

21. DEPTH BRIDGE MD
PLUG SET: TVD

22. TYPE ELECTRIC AND OTHER MECHANICAL LOGS RUN (Submit copy of each)

Triple Combo, CBL

23. WAS WELL CORED? NO ☒ YES ☐ (Submit analysis)
WAS DST RUN? NO ☒ YES ☐ (Submit report)
DIRECTIONAL SURVEY? NO ☐ YES ☒ (Submit copy)

24. CASING AND LINER RECORD (Report all strings set in well)

| HOLE SIZE | SIZE/GRADE | WEIGHT (#/ft.) | TOP (MD) | BOTTOM (MD) | STAGE CEMENTER DEPTH | CEMENT TYPE & NO. OF SACKS | SLURRY VOLUME (BBL) | CEMENT TOP ** | AMOUNT PULLED |
|-----------|------------|----------------|----------|-------------|----------------------|----------------------------|---------------------|---------------|---------------|
| 24 | 16 arj55 | 45 | 0 | 118 | | | | 0 | |
| 12 1/4 | 8 5/8 J-55 | 24 | 0 | 1,060 | | 675 | | 0 | |
| 7 7/8 | 5 1/2 J-55 | 17 | 0 | 6,400 | | 620 | | 0 | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |

25. TUBING RECORD

| SIZE | DEPTH SET (MD) | PACKER SET (MD) | SIZE | DEPTH SET (MD) | PACKER SET (MD) | SIZE | DEPTH SET (MD) | PACKER SET (MD) |
|-------|----------------|-----------------|------|----------------|-----------------|------|----------------|-----------------|
| 2 7/8 | 4,579 | | | | | | | |

26. PRODUCING INTERVALS

| FORMATION NAME | TOP (MD) | BOTTOM (MD) | TOP (TVD) | BOTTOM (TVD) | INTERVAL (Top/Bot - MD) | SIZE | NO. HOLES | PERFORATION STATUS |
|----------------|----------|-------------|-----------|--------------|-------------------------|------|-----------|--|
| (A) Lower GR | 4,535 | 6,299 | | | 4,535 6,299 | | 270 | Open <input checked="" type="checkbox"/> Squeezed <input type="checkbox"/> |
| (B) | | | | | | | | Open <input type="checkbox"/> Squeezed <input type="checkbox"/> |
| (C) | | | | | | | | Open <input type="checkbox"/> Squeezed <input type="checkbox"/> |
| (D) | | | | | | | | Open <input type="checkbox"/> Squeezed <input type="checkbox"/> |

27. PERFORATION RECORD

28. ACID, FRACTURE, TREATMENT, CEMENT SQUEEZE, ETC.

WAS WELL HYDRAULICALLY FRACTURED? YES ☒ NO ☐ IF YES - DATE FRACTURED: 8/2/2014

| DEPTH INTERVAL | AMOUNT AND TYPE OF MATERIAL |
|----------------|------------------------------|
| 4535 to 6299 | Fracture/ Stimulate 7 Stages |
| | |
| | |

29. ENCLOSED ATTACHMENTS:

☒ ELECTRICAL/MECHANICAL LOGS ☐ GEOLOGIC REPORT ☐ DST REPORT ☒ DIRECTIONAL SURVEY
☐ SUNDRY NOTICE FOR PLUGGING AND CEMENT VERIFICATION ☐ CORE ANALYSIS ☒ OTHER:

30. WELL STATUS:

POW

31. INITIAL PRODUCTION**INTERVAL A (As shown in item #26)**

| | | | | | | | |
|---|--------------------------------|----------------------------|-----------------------------|--------------------------|-------------------------|------------------------------|-------------------------------------|
| DATE FIRST PRODUCED: 8/7/2014 | TEST DATE: 8/15/2014 | HOURS TESTED: 24 | TEST PRODUCTION RATES: → | OIL – BBL: 200 | GAS – MCF: 63 | WATER – BBL: 408 | PROD. METHOD: Gas Pumping |
| CHOKE SIZE: | TBG. PRESS. | CSG. PRESS. | API GRAVITY | BTU – GAS | GAS/OIL RATIO | 24 HR PRODUCTION RATES: → | INTERVAL STATUS: |

INTERVAL B (As shown in item #26)

| | | | | | | | |
|----------------------|-------------|---------------|-----------------------------|------------|---------------|------------------------------|------------------|
| DATE FIRST PRODUCED: | TEST DATE: | HOURS TESTED: | TEST PRODUCTION RATES: → | OIL – BBL: | GAS – MCF: | WATER – BBL: | PROD. METHOD: |
| CHOKE SIZE: | TBG. PRESS. | CSG. PRESS. | API GRAVITY | BTU – GAS | GAS/OIL RATIO | 24 HR PRODUCTION RATES: → | INTERVAL STATUS: |

INTERVAL C (As shown in item #26)

| | | | | | | | |
|----------------------|-------------|---------------|-----------------------------|------------|---------------|------------------------------|------------------|
| DATE FIRST PRODUCED: | TEST DATE: | HOURS TESTED: | TEST PRODUCTION RATES: → | OIL – BBL: | GAS – MCF: | WATER – BBL: | PROD. METHOD: |
| CHOKE SIZE: | TBG. PRESS. | CSG. PRESS. | API GRAVITY | BTU – GAS | GAS/OIL RATIO | 24 HR PRODUCTION RATES: → | INTERVAL STATUS: |

INTERVAL D (As shown in item #26)

| | | | | | | | |
|----------------------|-------------|---------------|-----------------------------|------------|---------------|------------------------------|------------------|
| DATE FIRST PRODUCED: | TEST DATE: | HOURS TESTED: | TEST PRODUCTION RATES: → | OIL – BBL: | GAS – MCF: | WATER – BBL: | PROD. METHOD: |
| CHOKE SIZE: | TBG. PRESS. | CSG. PRESS. | API GRAVITY | BTU – GAS | GAS/OIL RATIO | 24 HR PRODUCTION RATES: → | INTERVAL STATUS: |

32. DISPOSITION OF GAS (Sold, Used for Fuel, Vented, Etc.)

Used on lease

33. SUMMARY OF POROUS ZONES (Include Aquifers):

Show all important zones of porosity and contents thereof: Cored intervals and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures and recoveries.

34. FORMATION (Log) MARKERS:

| Formation | Top (MD) | Bottom (MD) | Descriptions, Contents, etc. | Name | Top (Measured Depth) |
|-----------|-------------|----------------|------------------------------|-------------------|-------------------------|
| | | | | Upper Green River | 2,458 |
| | | | | Mahogany | 3,768 |
| | | | | Lower Green River | 4,498 |
| | | | | Wasatch | 6,310 |

35. ADDITIONAL REMARKS (Include plugging procedure)

Frac material used: 8049 HCl Acid, 970088 gal FR-66 Water, 236011 gal DeltaFrac Fluid, 989129 lbs White Sand

36. I hereby certify that the foregoing and attached information is complete and correct as determined from all available records.

NAME (PLEASE PRINT) Jenna AndersonTITLE Permitting SpecialistSIGNATURE DATE 9/3/2014

This report must be submitted within 30 days of

- completing or plugging a new well
- drilling horizontal laterals from an existing well bore
- recompleting to a different producing formation
- reentering a previously plugged and abandoned well
- significantly deepening an existing well bore below the previous bottom-hole depth
- drilling hydrocarbon exploratory holes, such as core samples and stratigraphic tests

* ITEM 20: Show the number of completions if production is measured separately from two or more formations.

** ITEM 24: Cement Top – Show how reported top(s) of cement were determined (circulated (CIR), calculated (CAL), cement bond log (CBL), temperature survey (TS)).

Send to: Utah Division of Oil, Gas and Mining
1594 West North Temple, Suite 1210
Box 145801
Salt Lake City, Utah 84114-5801

Phone: 801-538-5340

Fax: 801-359-3940

☐ Proposed
☒ As Is

THREE RIVERS 16-42L-820 GL: 4,702.9, KB: 4,716.0
 Sec 16, 8S, 20E Uintah County, Utah

| | Size | Weight | Grade | Depth | Sks/Cmt |
|-------------------|-------|--------|--------|-------|---------|
| Conductor | 16 | 45 | ARJ-55 | 118 | |
| Surface | 8 5/8 | 24 | J-55 | 1060 | 675 |
| Production | 5 1/2 | 17 | J-55 | 6400 | 620 |
| Tubing | | | | 4554 | |
| Tubing | 2.875 | | | 4491 | |
| Tubing | 2.875 | 6.5 | J-55 | 17 | |
| Cement Top | | | | 0 | |


| STAGE | ZONE 1 | ZONE 2 | ZONE 3 | ZONE 4 | ZONE 5 | ZONE 6 | ZONE 7 |
|-------|-----------|-----------|-----------|-----------|-----------|-----------|-----------|
| 1 | 6297-6299 | 6290-6291 | 6267-6268 | 6242-6243 | 6236-6237 | 6229-6230 | 6207-6208 |
| 2 | 6143-6144 | 6129-6130 | 6120-6121 | 6110-6111 | 6103-6104 | 6091-6092 | 6073-6074 |
| 3 | 5959-5961 | 5932-5933 | 5905-5906 | 5894-5895 | 5880-5881 | 5855-5856 | 5844-5845 |
| 4 | 5705-5706 | 5699-5700 | 5679-5680 | 5667-5668 | 5650-5651 | 5639-5640 | 5624-5625 |
| 5 | 5421-5423 | 5401-5402 | 5391-5392 | 5382-5383 | 5374-5375 | 5365-5366 | 5356-5357 |
| 6 | 5040-5041 | 5021-5022 | 4992-4993 | 4980-4981 | 4936-4937 | 4883-4884 | 4875-4876 |
| 7 | 4704-4706 | 4684-4685 | 4669-4670 | 4657-4658 | 4633-4634 | 4619-4620 | 4608-4609 |


| Stage | Date | Av. Rate | Av. Press | Proppant | Clean Fluid | Tracer | Screenout |
|-------|------------|----------------|-----------|----------|-------------|--------|-----------|
| 1 | 08/02/2014 | 60.9 | 2,513 | 94,200 | 3,139 | | N |
| 2 | 08/02/2014 | 60.8 | 2,372 | 146,900 | 4,601 | | N |
| 3 | 08/02/2014 | 57.7 | 2,619 | 124,100 | 4,012 | | N |
| 4 | 08/03/2014 | 60.9 | 3,318 | 180,500 | 4,927 | | N |
| 5 | 08/03/2014 | 60.7 | 3,013 | 180,813 | 5,127 | | N |
| 6 | 08/03/2014 | 57.3 | 2,485 | 129,542 | 3,941 | | N |
| 7 | 08/03/2014 | 60.3 | 1,982 | 133,074 | 3,804 | | N |
| | | Totals: | | 989,129 | 29,551 | | |

| Actual Formation or Depth | Top | Sand Type | Amount |
|---------------------------|-----|--------------------|--------|
| | | Gross Sand Drilled | |
| | | Gross Sand Logged | |
| | | Net Sand | |
| | | Net Pay | |

| Move In | Spud Date | TD Date | Rig Release | 1st Prod | Full Sales |
|------------|------------|------------|-------------|------------|------------|
| 04/30/2014 | 07/20/2014 | 07/22/2014 | 07/23/2014 | 08/07/2014 | |

| Tbg Date | Depth | OD | ID | Weight | Grade | Thread | Csg Size | 1st Jt | # Joints | Coil |
|------------|-----------|----|----|--------|-------|--------|----------|--------|----------|------|
| 08/13/2014 | 4,554.000 | | | | | | 5.5 | | 144 | N |
| 08/13/2014 | 4,491.000 | | | | | | 5.5 | | 144 | N |





ULTRA RESOURCES, INC

Location: Three Rivers Slot: Three Rivers 16-42L-820 (2006' FNL & 607' FEL)
 Field: UTAH COUNTY Well: Three Rivers 16-42L-820
 Facility: Sec 16-T8S-R20E Wellbore: Three Rivers 16-42L-820 PWB

Plot reference depths to Three Rivers 16-42L-820 PWB

True vertical depths are referenced to Capota 321 (RT)

Measured depths are referenced to Capota 321 (RT)

Capota 321 (RT) to Mean Sea Level: 4710 feet

Mean Sea Level to Mordine (AI) Slot: Three Rivers 16-42L-820 (2006' FNL & 607' FEL): 0 feet

Coordinates are in feet referenced to 561



Grid System: NAD83 (1 Lambert Utah SP, Central Zone 14S02, UTM)

North Reference: True north

Scale: True distance

Depth: in feet

Created by: anderson30/1/2014





Actual Wellpath Report

Three Rivers 16-42L-820 AWP

Page 1 of 5



REFERENCE WELLPATH IDENTIFICATION

| | | | |
|----------|----------------------|----------|--|
| Operator | ULTRA RESOURCES, INC | Slot | Three Rivers 16-42L-820 (2006' FNL & 607' FEL) |
| Area | Three Rivers | Well | Three Rivers 16-42L-820 |
| Field | UINTAH COUNTY | Wellbore | Three Rivers 16-42L-820 AWB |
| Facility | Sec.16-T8S-R20E | | |

REPORT SETUP INFORMATION

| | | | |
|---------------------|---|----------------------|---|
| Projection System | NAD83 / Lambert Utah SP, Central Zone (4302), US feet | Software System | WellArchitect® 3.0.0 |
| North Reference | True | User | Ewilliams |
| Scale | 0.999912 | Report Generated | 8/27/2014 at 2:51:04 PM |
| Convergence at slot | 1.17° East | Database/Source file | WellArchitectDB/Three_Rivers_16-42L-820_AWB.xml |

WELLPATH LOCATION

| | Local coordinates | | Grid coordinates | | Geographic coordinates | |
|-----------------------|-------------------|----------|------------------|-----------------|------------------------|-----------------|
| | North[ft] | East[ft] | Easting[US ft] | Northing[US ft] | Latitude | Longitude |
| Slot Location | 2037.25 | 2627.90 | 2153224.59 | 7219294.78 | 40°07'27.840"N | 109°39'57.550"W |
| Facility Reference Pt | | | 2150639.03 | 7217204.54 | 40°07'07.709"N | 109°40'31.379"W |
| Field Reference Pt | | | 2156630.96 | 7236613.42 | 40°10'18.270"N | 109°39'09.100"W |

WELLPATH DATUM

| | | | |
|--------------------------|-------------------|---|-------------------|
| Calculation method | Minimum curvature | Capstar 321 (RT) to Facility Vertical Datum | 4716.00ft |
| Horizontal Reference Pt | Slot | Capstar 321 (RT) to Mean Sea Level | 4716.00ft |
| Vertical Reference Pt | Capstar 321 (RT) | Capstar 321 (RT) to Mud Line at Slot (Three Rivers 16-42L-820 (2006' FNL & 607' FEL)) | 4716.00ft |
| MD Reference Pt | Capstar 321 (RT) | Section Origin | N 0.00, E 0.00 ft |
| Field Vertical Reference | Mean Sea Level | Section Azimuth | 326.34° |



Actual Wellpath Report

Three Rivers 16-42L-820 AWP

Page 2 of 5



REFERENCE WELLPATH IDENTIFICATION

| | | | |
|----------|----------------------|----------|--|
| Operator | ULTRA RESOURCES, INC | Slot | Three Rivers 16-42L-820 (2006' FNL & 607' FEL) |
| Area | Three Rivers | Well | Three Rivers 16-42L-820 |
| Field | UINTAH COUNTY | Wellbore | Three Rivers 16-42L-820 AWB |
| Facility | Sec.16-T8S-R20E | | |

WELLPATH DATA (69 stations) † = interpolated/extrapolated station

| MD [ft] | Inclination [°] | Azimuth [°] | TVD [ft] | Vert Sect [ft] | North [ft] | East [ft] | Latitude | Longitude | DLS [°/100ft] | Comments |
|----------|-----------------|-------------|----------|----------------|------------|-----------|----------------|-----------------|---------------|-------------------|
| 0.00† | 0.000 | 260.500 | 0.00 | 0.00 | 0.00 | 0.00 | 40°07'27.840"N | 109°39'57.550"W | 0.00 | |
| 13.00 | 0.000 | 260.500 | 13.00 | 0.00 | 0.00 | 0.00 | 40°07'27.840"N | 109°39'57.550"W | 0.00 | |
| 118.00 | 0.000 | 0.000 | 118.00 | 0.00 | 0.00 | 0.00 | 40°07'27.840"N | 109°39'57.550"W | 0.00 | |
| 1060.00 | 0.000 | 0.000 | 1060.00 | 0.00 | 0.00 | 0.00 | 40°07'27.840"N | 109°39'57.550"W | 0.00 | |
| 1142.00 | 1.900 | 260.500 | 1141.98 | 0.56 | -0.22 | -1.34 | 40°07'27.838"N | 109°39'57.567"W | 2.32 | |
| 1232.00 | 1.700 | 264.500 | 1231.94 | 1.80 | -0.60 | -4.14 | 40°07'27.834"N | 109°39'57.603"W | 0.26 | |
| 1323.00 | 2.700 | 304.900 | 1322.88 | 4.43 | 0.50 | -7.24 | 40°07'27.845"N | 109°39'57.643"W | 1.96 | |
| 1414.00 | 2.500 | 359.500 | 1413.80 | 8.09 | 3.71 | -9.02 | 40°07'27.877"N | 109°39'57.666"W | 2.63 | |
| 1504.00 | 2.800 | 0.100 | 1503.70 | 11.56 | 7.87 | -9.03 | 40°07'27.918"N | 109°39'57.666"W | 0.33 | |
| 1595.00 | 3.200 | 359.700 | 1594.58 | 15.53 | 12.63 | -9.04 | 40°07'27.965"N | 109°39'57.666"W | 0.44 | |
| 1685.00 | 5.800 | 355.100 | 1684.29 | 21.61 | 19.68 | -9.44 | 40°07'28.034"N | 109°39'57.672"W | 2.91 | |
| 1776.00 | 7.100 | 336.200 | 1774.72 | 31.18 | 29.41 | -12.11 | 40°07'28.131"N | 109°39'57.706"W | 2.72 | |
| 1867.00 | 7.400 | 325.300 | 1865.00 | 42.59 | 39.37 | -17.71 | 40°07'28.229"N | 109°39'57.778"W | 1.54 | |
| 1957.00 | 6.900 | 313.300 | 1954.30 | 53.65 | 47.84 | -24.95 | 40°07'28.313"N | 109°39'57.871"W | 1.75 | |
| 2048.00 | 6.300 | 312.000 | 2044.70 | 63.81 | 54.93 | -32.63 | 40°07'28.383"N | 109°39'57.970"W | 0.68 | |
| 2138.00 | 5.600 | 315.100 | 2134.22 | 72.90 | 61.35 | -39.40 | 40°07'28.446"N | 109°39'58.057"W | 0.86 | |
| 2229.00 | 4.200 | 320.000 | 2224.88 | 80.57 | 67.05 | -44.68 | 40°07'28.503"N | 109°39'58.125"W | 1.60 | |
| 2319.00 | 3.200 | 323.700 | 2314.69 | 86.35 | 71.59 | -48.29 | 40°07'28.548"N | 109°39'58.172"W | 1.14 | |
| 2410.00 | 1.200 | 15.900 | 2405.63 | 89.51 | 74.56 | -49.53 | 40°07'28.577"N | 109°39'58.188"W | 2.90 | |
| 2458.00† | 1.253 | 14.805 | 2453.62 | 90.18 | 75.55 | -49.26 | 40°07'28.587"N | 109°39'58.184"W | 0.12 | Top Green River |
| 2501.00 | 1.300 | 13.900 | 2496.61 | 90.82 | 76.48 | -49.02 | 40°07'28.596"N | 109°39'58.181"W | 0.12 | |
| 2591.00 | 1.300 | 16.200 | 2586.58 | 92.17 | 78.45 | -48.49 | 40°07'28.615"N | 109°39'58.174"W | 0.06 | |
| 2682.00 | 0.200 | 253.800 | 2677.58 | 92.88 | 79.40 | -48.35 | 40°07'28.625"N | 109°39'58.172"W | 1.56 | |
| 2772.00 | 0.500 | 290.100 | 2767.57 | 93.25 | 79.49 | -48.87 | 40°07'28.625"N | 109°39'58.179"W | 0.40 | |
| 2863.00 | 0.600 | 298.300 | 2858.57 | 93.99 | 79.85 | -49.67 | 40°07'28.629"N | 109°39'58.189"W | 0.14 | |
| 2954.00 | 0.900 | 280.800 | 2949.56 | 94.91 | 80.21 | -50.79 | 40°07'28.633"N | 109°39'58.204"W | 0.41 | |
| 3044.00 | 0.500 | 255.500 | 3039.56 | 95.53 | 80.24 | -51.86 | 40°07'28.633"N | 109°39'58.218"W | 0.55 | |
| 3135.00 | 0.700 | 233.500 | 3130.55 | 95.64 | 79.81 | -52.69 | 40°07'28.629"N | 109°39'58.228"W | 0.33 | |
| 3225.00 | 0.800 | 239.100 | 3220.54 | 95.64 | 79.16 | -53.67 | 40°07'28.622"N | 109°39'58.241"W | 0.14 | |
| 3316.00 | 0.700 | 226.700 | 3311.53 | 95.58 | 78.46 | -54.62 | 40°07'28.615"N | 109°39'58.253"W | 0.21 | |
| 3407.00 | 1.000 | 218.200 | 3402.52 | 95.24 | 77.45 | -55.52 | 40°07'28.605"N | 109°39'58.265"W | 0.36 | |
| 3497.00 | 1.200 | 218.900 | 3492.51 | 94.71 | 76.10 | -56.60 | 40°07'28.592"N | 109°39'58.279"W | 0.22 | |
| 3588.00 | 1.000 | 214.900 | 3583.49 | 94.14 | 74.71 | -57.65 | 40°07'28.578"N | 109°39'58.292"W | 0.24 | |
| 3678.00 | 1.100 | 213.500 | 3673.48 | 93.51 | 73.34 | -58.58 | 40°07'28.565"N | 109°39'58.304"W | 0.11 | |
| 3768.00† | 0.901 | 192.775 | 3763.46 | 92.69 | 71.93 | -59.21 | 40°07'28.551"N | 109°39'58.312"W | 0.46 | Mahogany |
| 3769.00 | 0.900 | 192.500 | 3764.46 | 92.68 | 71.92 | -59.21 | 40°07'28.551"N | 109°39'58.312"W | 0.46 | |
| 3859.00 | 1.000 | 202.600 | 3854.45 | 91.75 | 70.50 | -59.67 | 40°07'28.537"N | 109°39'58.318"W | 0.22 | |
| 3950.00 | 0.500 | 149.900 | 3945.44 | 90.92 | 69.42 | -59.77 | 40°07'28.526"N | 109°39'58.319"W | 0.88 | |
| 4041.00 | 0.400 | 178.800 | 4036.44 | 90.25 | 68.76 | -59.57 | 40°07'28.520"N | 109°39'58.317"W | 0.27 | |
| 4131.00 | 0.700 | 163.100 | 4126.44 | 89.46 | 67.92 | -59.40 | 40°07'28.511"N | 109°39'58.315"W | 0.37 | |
| 4222.00 | 0.900 | 157.100 | 4217.43 | 88.23 | 66.73 | -58.96 | 40°07'28.499"N | 109°39'58.309"W | 0.24 | |
| 4312.00 | 0.800 | 151.400 | 4307.42 | 86.91 | 65.53 | -58.39 | 40°07'28.488"N | 109°39'58.302"W | 0.15 | |
| 4403.00 | 1.100 | 162.300 | 4398.41 | 85.43 | 64.14 | -57.82 | 40°07'28.474"N | 109°39'58.294"W | 0.38 | |
| 4493.00 | 1.000 | 175.600 | 4488.39 | 83.92 | 62.53 | -57.49 | 40°07'28.458"N | 109°39'58.290"W | 0.29 | |
| 4498.00† | 1.011 | 175.802 | 4493.39 | 83.84 | 62.45 | -57.49 | 40°07'28.457"N | 109°39'58.290"W | 0.23 | Lower Green River |



Actual Wellpath Report

Three Rivers 16-42L-820 AWP

Page 3 of 5



REFERENCE WELLPATH IDENTIFICATION

| | | | |
|----------|----------------------|----------|--|
| Operator | ULTRA RESOURCES, INC | Slot | Three Rivers 16-42L-820 (2006' FNL & 607' FEL) |
| Area | Three Rivers | Well | Three Rivers 16-42L-820 |
| Field | UINTAH COUNTY | Wellbore | Three Rivers 16-42L-820 AWB |
| Facility | Sec.16-T8S-R20E | | |

WELLPATH DATA (69 stations) † = interpolated/extrapolated station

| MD [ft] | Inclination [°] | Azimuth [°] | TVD [ft] | Vert Sect [ft] | North [ft] | East [ft] | Latitude | Longitude | DLS [%/100ft] | Comments |
|------------|--------------------|----------------|-------------|-------------------|---------------|--------------|----------------|-----------------|------------------|-------------------|
| 4535.00† | 1.092 | 177.172 | 4530.38 | 83.25 | 61.77 | -57.45 | 40°07'28.450"N | 109°39'58.289"W | 0.23 | Top of Production |
| 4584.00 | 1.200 | 178.700 | 4579.37 | 82.42 | 60.79 | -57.41 | 40°07'28.441"N | 109°39'58.289"W | 0.23 | |
| 4675.00 | 1.300 | 192.600 | 4670.35 | 80.90 | 58.83 | -57.61 | 40°07'28.421"N | 109°39'58.292"W | 0.35 | |
| 4765.00 | 1.300 | 178.000 | 4760.33 | 79.33 | 56.81 | -57.80 | 40°07'28.401"N | 109°39'58.294"W | 0.37 | |
| 4856.00 | 1.200 | 184.300 | 4851.31 | 77.70 | 54.83 | -57.84 | 40°07'28.382"N | 109°39'58.295"W | 0.19 | |
| 4946.00 | 1.600 | 202.200 | 4941.28 | 76.25 | 52.73 | -58.38 | 40°07'28.361"N | 109°39'58.302"W | 0.65 | |
| 5037.00 | 1.400 | 202.100 | 5032.25 | 74.91 | 50.52 | -59.28 | 40°07'28.339"N | 109°39'58.313"W | 0.22 | |
| 5128.00 | 1.600 | 211.600 | 5123.22 | 73.75 | 48.41 | -60.36 | 40°07'28.318"N | 109°39'58.327"W | 0.35 | |
| 5218.00 | 1.500 | 209.300 | 5213.19 | 72.69 | 46.31 | -61.60 | 40°07'28.298"N | 109°39'58.343"W | 0.13 | |
| 5309.00 | 1.500 | 204.300 | 5304.15 | 71.52 | 44.19 | -62.67 | 40°07'28.277"N | 109°39'58.357"W | 0.14 | |
| 5399.00 | 1.300 | 200.500 | 5394.13 | 70.30 | 42.16 | -63.51 | 40°07'28.257"N | 109°39'58.368"W | 0.24 | |
| 5490.00 | 1.600 | 195.600 | 5485.10 | 68.86 | 39.97 | -64.22 | 40°07'28.235"N | 109°39'58.377"W | 0.36 | |
| 5580.00 | 1.300 | 191.200 | 5575.07 | 67.32 | 37.76 | -64.75 | 40°07'28.213"N | 109°39'58.384"W | 0.36 | |
| 5671.00 | 1.500 | 190.800 | 5666.04 | 65.74 | 35.57 | -65.18 | 40°07'28.192"N | 109°39'58.389"W | 0.22 | |
| 5762.00 | 1.600 | 191.800 | 5757.01 | 64.00 | 33.16 | -65.66 | 40°07'28.168"N | 109°39'58.395"W | 0.11 | |
| 5852.00 | 1.300 | 180.000 | 5846.98 | 62.27 | 30.91 | -65.92 | 40°07'28.145"N | 109°39'58.399"W | 0.47 | |
| 5943.00 | 1.300 | 167.600 | 5937.96 | 60.45 | 28.87 | -65.70 | 40°07'28.125"N | 109°39'58.396"W | 0.31 | |
| 6033.00 | 1.100 | 169.400 | 6027.94 | 58.70 | 27.02 | -65.32 | 40°07'28.107"N | 109°39'58.391"W | 0.23 | |
| 6124.00 | 1.400 | 183.900 | 6118.92 | 57.01 | 25.06 | -65.23 | 40°07'28.088"N | 109°39'58.390"W | 0.48 | |
| 6214.00 | 1.600 | 168.600 | 6208.88 | 54.98 | 22.73 | -65.06 | 40°07'28.065"N | 109°39'58.388"W | 0.50 | |
| 6305.00 | 1.200 | 166.500 | 6299.86 | 52.91 | 20.55 | -64.59 | 40°07'28.043"N | 109°39'58.381"W | 0.44 | |
| 6310.00† | 1.200 | 166.216 | 6304.86 | 52.81 | 20.45 | -64.56 | 40°07'28.042"N | 109°39'58.381"W | 0.12 | Wasatch |
| 6370.00 | 1.200 | 162.800 | 6364.84 | 51.62 | 19.24 | -64.23 | 40°07'28.030"N | 109°39'58.377"W | 0.12 | End of Surveys |
| 6420.00 | 1.200 | 162.800 | 6414.83 | 50.61 | 18.24 | -63.92 | 40°07'28.020"N | 109°39'58.373"W | 0.00 | Projection To Bit |



Actual Wellpath Report

Three Rivers 16-42L-820 AWP

Page 4 of 5



REFERENCE WELLPATH IDENTIFICATION

| | | | |
|----------|----------------------|----------|--|
| Operator | ULTRA RESOURCES, INC | Slot | Three Rivers 16-42L-820 (2006' FNL & 607' FEL) |
| Area | Three Rivers | Well | Three Rivers 16-42L-820 |
| Field | UINTAH COUNTY | Wellbore | Three Rivers 16-42L-820 AWB |
| Facility | Sec.16-T8S-R20E | | |

TARGETS

| Name | MD [ft] | TVD [ft] | North [ft] | East [ft] | Grid East [US ft] | Grid North [US ft] | Latitude | Longitude | Shape |
|--|------------|-------------|---------------|--------------|----------------------|-----------------------|----------------|-----------------|--------|
| Target Box 400' X 400' Center @ 1980' FNL & 660' FEL | | 4200.00 | 25.30 | -52.82 | 2153171.26 | 7219318.99 | 40°07'28.090"N | 109°39'58.230"W | point |
| Three Rivers 16-42L-820 Driller's Target Radius: 5' 1932' FNL & 656' FEL | | 4200.00 | 73.30 | -48.82 | 2153174.28 | 7219367.06 | 40°07'28.564"N | 109°39'58.178"W | circle |
| Three Rivers 16-42L-820 Target On Plat Radius: 50' 1980' FNL & 660' FEL | | 4200.00 | 25.30 | -52.82 | 2153171.26 | 7219318.99 | 40°07'28.090"N | 109°39'58.230"W | circle |

WELLPATH COMPOSITION - Ref Wellbore: Three Rivers 16-42L-820 AWB Ref Wellpath: Three Rivers 16-42L-820 AWP

| Start MD [ft] | End MD [ft] | Positional Uncertainty Model | Log Name/Comment | Wellbore |
|------------------|----------------|------------------------------------|-------------------|-----------------------------|
| 13.00 | 118.00 | Unknown Tool (Standard) | Conductor | Three Rivers 16-42L-820 AWB |
| 118.00 | 1060.00 | Unknown Tool (Standard) | Surface | Three Rivers 16-42L-820 AWB |
| 1060.00 | 6370.00 | MTC (Collar, post-2000) (Standard) | MWD | Three Rivers 16-42L-820 AWB |
| 6370.00 | 6420.00 | Blind Drilling (std) | Projection to bit | Three Rivers 16-42L-820 AWB |



Actual Wellpath Report

Three Rivers 16-42L-820 AWP

Page 5 of 5



REFERENCE WELLPATH IDENTIFICATION

| | | | |
|----------|----------------------|----------|--|
| Operator | ULTRA RESOURCES, INC | Slot | Three Rivers 16-42L-820 (2006' FNL & 607' FEL) |
| Area | Three Rivers | Well | Three Rivers 16-42L-820 |
| Field | UINTAH COUNTY | Wellbore | Three Rivers 16-42L-820 AWB |
| Facility | Sec.16-T8S-R20E | | |

WELLPATH COMMENTS

| MD [ft] | Inclination [°] | Azimuth [°] | TVD [ft] | Comment |
|------------|--------------------|----------------|-------------|-------------------|
| 2458.00 | 1.253 | 14.805 | 2453.62 | Top Green River |
| 3768.00 | 0.901 | 192.775 | 3763.46 | Mahogany |
| 4498.00 | 1.011 | 175.802 | 4493.39 | Lower Green River |
| 4535.00 | 1.092 | 177.172 | 4530.38 | Top of Production |
| 6310.00 | 1.200 | 166.216 | 6304.86 | Wasatch |
| 6370.00 | 1.200 | 162.800 | 6364.84 | End of Surveys |
| 6420.00 | 1.200 | 162.800 | 6414.83 | Projection To Bit |

ULTRA RESOURCES, INC.
DAILY COMPLETION REPORT FOR 07/26/2014 TO 08/13/2014

| | | | |
|--------------------|--|--------------|-----------|
| Well Name | THREE RIVERS 16-42L-820 | Frac Planned | 7 |
| Location: | UINTAH County, UTAH(SENE 16 8S 20E) | AFE# | 140625 |
| Total Depth Date: | 07/22/2014 TD 6,420 | Formation: | (Missing) |
| Production Casing: | Size 5 1/2 Wt 17 Grade J-55 Set At 6,400 | GL: | KB: 4,716 |

| | | | |
|--------------------|---|-------------------|--------------|
| Date: 07/26/2014 | | | |
| Tubing: | OD: 2.875" ID: Joints: 144" Depth Set: 4,580" | PBTD: | 6,399 |
| Supervisor: | Duncan | | |
| Work Objective: | Logging | | |
| Contractors: | J-W | | |
| Completion Rig: | J-W | Supervisor Phone: | 435-828-1472 |
| Upcoming Activity: | Completion | | |
| Activities | | | |
| 0700-1100 | MIRU JW WLU, run 4.65" gauge ring fr/surface to 6380'. POH w/gauge ring. Run CBL/GR/CCL fr/6366' to surface. TOC @ 1518'. RDMO WLU. | | |
| Costs (\$): | Daily: 4,400 | Cum: 4,400 | AFE: 948,500 |

| | | | |
|--------------------|---|-------------------|--------------|
| Date: 07/27/2014 | | | |
| Tubing: | OD: 2.875" ID: Joints: 144" Depth Set: 4,580" | PBTD: | 6,399 |
| Supervisor: | (Missing) | | |
| Work Objective: | (Nothing Recorded) | | |
| Contractors: | (Missing) | | |
| Completion Rig: | (Missing) | Supervisor Phone: | (Missing) |
| Upcoming Activity: | | | |
| Activities | | | |
| 0800-1700 | MIRU HES. | | |
| Costs (\$): | Daily: 0 | Cum: 4,400 | AFE: 948,500 |

| | | | |
|--------------------|---|-------------------|--------------|
| Date: 07/28/2014 | | | |
| Tubing: | OD: 2.875" ID: Joints: 144" Depth Set: 4,580" | PBTD: | 6,399 |
| Supervisor: | Fletcher | | |
| Work Objective: | Prep for frac work | | |
| Contractors: | (Missing) | | |
| Completion Rig: | (Missing) | Supervisor Phone: | 3036459812 |
| Upcoming Activity: | Completion | | |
| Costs (\$): | Daily: 0 | Cum: 4,400 | AFE: 948,500 |

| | | | |
|--------------------|---|-------------------|--------------|
| Date: 07/30/2014 | | | |
| Tubing: | OD: 2.875" ID: Joints: 144" Depth Set: 4,580" | PBTD: | 6,399 |
| Supervisor: | Duncan | | |
| Work Objective: | Prep for frac work | | |
| Contractors: | Knight, BC, T&S | | |
| Completion Rig: | (Missing) | Supervisor Phone: | 435-828-1472 |
| Upcoming Activity: | Completion | | |
| Activities | | | |
| 0700-1030 | MINU Knight 5K BOP. Install live load manifold. | | |
| 1030-1031 | Fill frac tanks with water. | | |
| Costs (\$): | Daily: 1,830 | Cum: 6,230 | AFE: 948,500 |

| | | | |
|--------------------|---|-------------------|--------------|
| Date: 07/31/2014 | | | |
| Tubing: | OD: 2.875" ID: Joints: 144" Depth Set: 4,580" | PBTD: | 6,399 |
| Supervisor: | Duncan | | |
| Work Objective: | Pressure test | | |
| Contractors: | RBS, R&R, J-W | | |
| Completion Rig: | (Missing) | Supervisor Phone: | 435-828-1472 |
| Upcoming Activity: | Completion | | |
| Activities | | | |
| 0800-0830 | MIRU RBS Test Unit, and test csg, WH, Flow back lines, and BOP to 4,250 psig, good test. RDMO Testers | | |
| 0830-0930 | Perforate stage 1 (6168' - 6299'). | | |
| Costs (\$): | Daily: 19,341 | Cum: 25,571 | AFE: 948,500 |

| | | | |
|--------------------|--|-------------------|--------------------------|
| Date: 08/02/2014 | | | |
| Tubing: | OD: 2.875" ID: Joints: 144" Depth Set: 4,580" | PBTD: | 6,399 |
| Supervisor: | Duncan,Stringham | | |
| Work Objective: | Perf, Frac, and Flowback | SSE: | 2 |
| Contractors: | HES,Cutters,R&R | | |
| Completion Rig: | HAL - Blue UT | Supervisor Phone: | 435.28.1472/435.790.2326 |
| Upcoming Activity: | Drill out plug | | |
| Activities | | | |
| 0330-1300 | MIRU Hall.-Blue. | | |
| 1300-1310 | Review location hazards including production equipment & producing wells. Discuss the heat, humidity, & need for hydration. Discuss slips, trips, & falls. Review WHD operations, High Pressure pumping, FB, crane operations, chemical handling, MSDS sheets & PPE requirements. Discuss traffic control & the use of land guides while backing. Review the reporting of property damage, & personnel injuries. Establish smoking area & Muster area. | | |
| 1310-1330 | Pressure test frac lines to 5500 psi. | | |
| 1330-1450 | Frac stage 1. | | |
| 1450-1550 | Perforate stage 2 (5984'-6144'). Set 5.5" FTFP at 6160'. | | |
| 1550-1605 | Wait on TR 16-44T-820. | | |
| 1605-1730 | Frac stage 2. | | |
| 1730-1830 | Perforate Stage 3 (5737'-5961'). Set 5.5" FTFP at 5981'. | | |
| 1830-2000 | Wait On Tr 16-44T-820 | | |
| 2000-2135 | Frac Stage 3 | | |
| 2135-2240 | Perforate Stage 4 (5451'-5706'). Set 5.5" FTFP at 5726'. | | |
| 2240-2345 | Wait On TR 16-44T-820 | | |
| 2345-0000 | Fluid Issue With Crosslinker | | |
| 0000-0040 | Fluid Issue's With Crosslinker | | |
| Costs (\$): | Daily: 7,440 | Cum: 33,011 | AFE: 948,500 |

| | | | |
|--------------------|---|-------------------|-----------------------|
| Date: 08/03/2014 | | | |
| Tubing: | OD: 2.875" ID: Joints: 144" Depth Set: 4,580" | PBTD: | 6,399 |
| Supervisor: | Stringham/Duncan | | |
| Work Objective: | Perf, Frac, and Flowback | SSE: | 3 |
| Contractors: | HES,Cutters,R&R,IPS,ETS,RNI | | |
| Completion Rig: | Cutters, HAL - Blue UT, IPS CT 2" | Supervisor Phone: | 4357902326/4358281472 |
| Upcoming Activity: | Drill out plug | | |
| Activities | | | |
| 0000-0040 | Fluid Issue's With Crosslinker | | |
| 0040-0210 | Frac Stage 4 | | |
| 0210-0405 | Rope Socket Stuck At Grease Head Drop Plug On Top Of Top Rams Broke Off Pieces Of Plug. Retrieved Out. | | |
| 0405-0445 | Perforate Stage 5 (5277'-5423'). Set 5.5" FTFP at 5443'. | | |
| 0445-0650 | Frac Stage 5 | | |
| 0650-0755 | RIH Unable to set FTFP, plug chamber flooded, resulting in the second gun firing @ 5048' - 5049', 3 holes. | | |
| 0755-0910 | RIH Attempt to perforate stage 6, set plug, and shot the first gun, unable to finish. POH, found no detonators the gun. Note: Unable to put the following miscue in because Cutter WL is not in the library. Cutter WL, RIH attempt to set FTFP, plug chamber flooded resulting in the second gun firing shooting 3 holes off depth at 5048'-5049'. RIH Attempt to perforate stage 6, set plug, and shot the first gun, unable to finish. POH, found n detonators in the gun. | | |
| 0910-1035 | RIH Perforate Stage 6 (4740'-5041'). Set 5.5" FTFP at 5067'. | | |
| 1035-1205 | Frac Stage 6. | | |
| 1205-1320 | Perforate Stage 7 (4535'-4706'). Set 5.5" FTFP at 4726'. | | |
| 1320-1445 | Frac Stage 7. | | |
| 1445-1446 | SICP 1297 psi. Wait on CTU. | | |
| 2130-2145 | Safety Meeting-Review location hazards including ,WHD, WL crane operations,overhead objects,the use of land guides while backing. Review incident reporting of property damage, & personnel injuries. Slips trips and falls, Establish smoking area & Muster area. | | |
| 2145-0000 | MIRU IPS CTU NU. lub. Fill coil with water. Install coil connect. Pull test to 25,000# & pressure test to 3000 psi. | | |
| 0000-0025 | Pull test to 25,000# & pressure test to 3000 psi. Break lubricator off 7-1/16" BOP. Used On TR 16-26T-820 ETS BHA as follows: Coil Connector, Bi-Directional jar, MHA Dual Check Valves, 3/4" Ball Seat (back pressure valve) Hydraulic Disconnect, motor and 5 blade 4.625" mill. Reconnect lubricator. Function test motor,(1200 psi @ 1.5 bbl/min). | | |
| Costs (\$): | Daily: 415,659 | Cum: 448,670 | AFE: 948,500 |

| | | | |
|--------------------|--|---|--------------|
| Date: 08/04/2014 | | | |
| Tubing: | OD: 2.875" ID: Joints: 144" Depth Set: 4,580" | PBTD: | 6,399 |
| Supervisor: | Stringham/Duncan | | |
| Work Objective: | Drill out plug | SSE: | 1 |
| Contractors: | IPS,R&R,ETS,RNI | | |
| Completion Rig: | IPS CT 2" | Supervisor Phone: 4357902326/4358281472 | |
| Upcoming Activity: | Flow test well | | |
| Activities | | | |
| 0000-0025 | Pull test to 25,000# & pressure test to 3000 psi. Break lubricator off 7-1/16" BOP. Used On TR 16-26T-820 ETS BHA as follows: Coil Connector, Bi-Directional jar, MHA Dual Check Valves, 3/4" Ball Seat (back pressure valve) Hydraulic Disconnect, motor and 5 blade 4.625" mill. Reconnect lubricator. Function test motor,(1200 psi @ 1.5 bbl/min). | | |
| 0025-0030 | Pressure test to 3500 psi. Open rams, 900 psi well pressure. | | |
| 0030-0110 | RIH with mill and motor to plug @ 4726'. (Coil depth 4720'). | | |
| 0110-0120 | Drill Plug @ 4720' (750 PSI). | | |
| 0120-0135 | Pump a 10 bbl gel sweep. RIH to plug @ 5067'. Tag sand at 5027', wash sand to plug. (Coil depth 5061'). | | |
| 0135-0150 | Drill Plug @ 5061' (750 PSI). | | |
| 0150-0210 | Pump a 10 bbl gel sweep. RIH to plug @ 5439'. Tag sand at 5363', wash sand to plug. (Coil depth 5433'). | | |
| 0210-0220 | Drill Plug @ 5433' (750 PSI). | | |
| 0220-0255 | Pump a 10 bbl gel sweep. RIH to plug @ 5726'. Tag sand at 5570', wash sand to plug. (Coil depth 5718'). | | |
| 0255-0325 | Drill Plug @ 5718' (800 PSI). | | |
| 0325-0345 | Pump a 10 bbl gel sweep. RIH to plug @ 5979'. Tag sand at 5771', wash sand to plug. (Coil depth 5971'). | | |
| 0345-0405 | Drill Plug @ 5971' (800 PSI). | | |
| 0405-0415 | Pump a 10 bbl gel sweep. RIH to plug @ 6160'. (Coil depth 6150'). | | |
| 0415-0445 | Drill Plug @ 6150' (800 PSI). | | |
| 0445-0630 | RIH to PBTD @ 6399'. Pump 20 bbl gel sweep, 10 bbl water spacer & 20 bbl gel sweep. Coil PBTD @ 6389' Make 500' short trip and retag PBTD. POOH @ 50 ft/min for 30 min and then continue POOH. Close Bottom ram, SICP 800#. | | |
| 0630-0700 | SICP @ 800 PSI. RD CTU, swing over to the TR 16-44T-820. | | |
| 0700-0701 | Open to tank on 16/64 choke, IP @ 800 PSI. | | |
| Costs (\$): | Daily: 26,559 | Cum: 475,229 | AFE: 948,500 |

| | | | |
|--------------------|---|-------------------|--------------|
| Date: 08/05/2014 | | | |
| Tubing: | OD: 2.875" ID: Joints: 144" Depth Set: 4,580" | PBTD: | 6,399 |
| Supervisor: | Duncan | | |
| Work Objective: | Flow test well | | |
| Contractors: | R&R, RNI | | |
| Completion Rig: | (Missing) | Supervisor Phone: | 435-828-1472 |
| Upcoming Activity: | Flow test well | | |
| Costs (\$): | Daily: 12,099 | Cum: 487,328 | AFE: 948,500 |

| | | | |
|--------------------|---|-------------------|--------------|
| Date: 08/06/2014 | | | |
| Tubing: | OD: 2.875" ID: Joints: 144" Depth Set: 4,580" | PBTD: | 6,399 |
| Supervisor: | Duncan | | |
| Work Objective: | Flow test well | | |
| Contractors: | R&R, RNI | | |
| Completion Rig: | (Missing) | Supervisor Phone: | 435-828-1472 |
| Upcoming Activity: | Flow test well | | |
| Costs (\$): | Daily: 3,897 | Cum: 491,225 | AFE: 948,500 |

| | | | |
|--------------------|---|-------------------|--------------|
| Date: 08/07/2014 | | | |
| Tubing: | OD: 2.875" ID: Joints: 144" Depth Set: 4,580" | PBTD: | 6,399 |
| Supervisor: | Duncan | | |
| Work Objective: | Flow test well | | |
| Contractors: | R&R, RNI | | |
| Completion Rig: | (Missing) | Supervisor Phone: | 435-828-1472 |
| Upcoming Activity: | Turned over to Production Dept | | |
| Costs (\$): | Daily: 27,018 | Cum: 518,243 | AFE: 948,500 |

| | | | |
|--------------------|---|-------------------|--------------|
| Date: 08/08/2014 | | | |
| Tubing: | OD: 2.875" ID: Joints: 144" Depth Set: 4,580" | PBTD: | 6,399 |
| Supervisor: | Fletcher | | |
| Work Objective: | Turned over to Production Dept | | |
| Contractors: | (Missing) | | |
| Completion Rig: | (Missing) | Supervisor Phone: | 3036459812 |
| Upcoming Activity: | Completion | | |
| Costs (\$): | Daily: 0 | Cum: 518,243 | AFE: 948,500 |

| | | | |
|--------------------|---|-------------------|--------------|
| Date: 08/09/2014 | | | |
| Tubing: | OD: 2.875" ID: Joints: 144" Depth Set: 4,580" | PBTD: | 6,399 |
| Supervisor: | (Missing) | | |
| Work Objective: | (Nothing Recorded) | | |
| Contractors: | (Missing) | | |
| Completion Rig: | (Missing) | Supervisor Phone: | (Missing) |
| Upcoming Activity: | | | |
| Costs (\$): | Daily: 817 | Cum: 519,060 | AFE: 948,500 |

| | | | |
|--------------------|--|--------------|-----------------------------|
| Date: 08/12/2014 | | | |
| Tubing: | OD: 2.875" ID: Joints: 144" Depth Set: 4,580" | | PBTD: 6,399 |
| Supervisor: | Jim Burns | | |
| Work Objective: | MI/RU workover rig | | |
| Contractors: | (Missing) | | |
| Completion Rig: | Stone #7 | | Supervisor Phone: (Missing) |
| Upcoming Activity: | Well sent to sales | | |
| Activities | | | |
| 1200-1800 | slide rig over S.I.R.U. R/D floor r/u TBG equip. spot pipe trailer prep and tally TBG and BHA m/u BHA, RIH w | | |
| | 115= jnts TBG W.I. F.N. | | |
| 1800-1900 | Crew Travel | | |
| Costs (\$): | Daily: 27,763 | Cum: 546,823 | AFE: 948,500 |

| | | | |
|--------------------|--|-----------------------------|--------------|
| Date: 08/13/2014 | | | |
| Tubing: | OD: 2.875" ID: Joints: 144" Depth Set: 4,580" | PBTD: | 6,399 |
| Supervisor: | Jim Burns | | |
| Work Objective: | MI/RU workover rig | | |
| Contractors: | (Missing) | | |
| Completion Rig: | Stone #7 | Supervisor Phone: (Missing) | |
| Upcoming Activity: | Well sent to sales | | |
| Activities | | | |
| 0600-0700 | crew travel | | |
| 0700-1030 | S.M. csg psi 50, tbg psi 0 bleed off well finish RIH with tbg to depth land tbg on hanger r/d tbg equip r/u floor n/d BOP | | |
| 1030-1130 | po hanger set 5.5" slim hole TAC @ 4570.77' land back in 10 k tention n/u well head etc EOT@ 4579.07' | | |
| 1130-1330 | prep rod's p/u plunger and pull rod rih with rods to depth space out p/u Polish rod fill tbg w 2 bbls stk test @ 1000 psi goo no leaks r/u unit r/d rig. | | |
| Costs (\$): | Daily: 0 | Cum: 546,823 | AFE: 948,500 |

ULTRA RESOURCES, INC.
PERFORATION AND FRAC SUMMARY FOR THREE RIVERS 16-42L-820

| | | | | | |
|---|------------|-------------------------------------|-----------------------------------|-------------------------|-------|
| Well Name: THREE RIVERS 16-42L-820 | | | Fracs Planned: 7 | | |
| Location: UINTAH County, UTAH (SENE 016 8S 20E) | | | | | |
| Stage 1 | | Frac Date: 08/02/2014 | Avg Rate: 60.9 BPM | Avg Pressure: 2,513 PSI | |
| Initial Completion | | Proppant: 94,200 lbs total | Max Rate: 61.5 BPM | Max Pressure: 3,476 PSI | |
| 94200 lbs Ottawa | | | | | |
| Initial Annulus Pressure: 10 | | Final Annulus Pressure: 10 | Pump Down Volume: | | |
| PreFrac SICP: | | ISIP: 1,834 PSI | Base BBLS to Recover: 3,139 BBLs | | |
| Pseudo Frac Gradient: 0.724 PSI/FT | | Pseudo Frac Gradient: 13.922 LB/GAL | | | |
| | | Net Pressure: 133 psi | Total BBLS to Recover: 3,139 BBLs | | |
| Breakdown Pressure: 2442 | | Breakdown Rate: 9.1 | Perfs Open: | | |
| ScreenOut: No | | Tracer: (None) | | | |
| Zones: | Perf Date | SPF | Perf Interval: | From | To |
| 11 | 07/31/2014 | 3 | | 6,168 | 6,169 |
| 10 | 07/31/2014 | 3 | | 6,178 | 6,179 |
| 9 | 07/31/2014 | 3 | | 6,189 | 6,190 |
| 8 | 07/31/2014 | 3 | | 6,202 | 6,203 |
| 7 | 07/31/2014 | 3 | | 6,207 | 6,208 |
| 6 | 07/31/2014 | 3 | | 6,229 | 6,230 |
| 5 | 07/31/2014 | 3 | | 6,236 | 6,237 |
| 4 | 07/31/2014 | 3 | | 6,242 | 6,243 |
| 3 | 07/31/2014 | 3 | | 6,267 | 6,268 |
| 2 | 07/31/2014 | 3 | | 6,290 | 6,291 |
| 1 | 07/31/2014 | 3 | | 6,297 | 6,299 |
| Stage 2 | | Frac Date: 08/02/2014 | Avg Rate: 60.8 BPM | Avg Pressure: 2,372 PSI | |
| Initial Completion | | Proppant: 146,900 lbs total | Max Rate: 62.3 BPM | Max Pressure: 3,315 PSI | |
| 146900 lbs Ottawa | | | | | |
| Initial Annulus Pressure: 13 | | Final Annulus Pressure: 13 | Pump Down Volume: | | |
| PreFrac SICP: | | ISIP: 1,550 PSI | Base BBLS to Recover: 4,601 BBLs | | |
| Pseudo Frac Gradient: 0.685 PSI/FT | | Pseudo Frac Gradient: 13.174 LB/GAL | | | |
| | | Net Pressure: 112 psi | Total BBLS to Recover: 4,601 BBLs | | |
| Breakdown Pressure: 1765 | | Breakdown Rate: 8.2 | Perfs Open: | | |
| ScreenOut: No | | Tracer: (None) | | | |
| Zones: | Perf Date | SPF | Perf Interval: | From | To |
| 13 | 08/02/2014 | 3 | | 5,984 | 5,985 |
| 12 | 08/02/2014 | 3 | | 6,005 | 6,006 |
| 11 | 08/02/2014 | 3 | | 6,010 | 6,011 |
| 10 | 08/02/2014 | 3 | | 6,024 | 6,025 |
| 9 | 08/02/2014 | 3 | | 6,052 | 6,053 |
| 8 | 08/02/2014 | 3 | | 6,064 | 6,065 |
| 7 | 08/02/2014 | 3 | | 6,073 | 6,074 |
| 6 | 08/02/2014 | 3 | | 6,091 | 6,092 |
| 5 | 08/02/2014 | 3 | | 6,103 | 6,104 |
| 4 | 08/02/2014 | 3 | | 6,110 | 6,111 |
| 3 | 08/02/2014 | 3 | | 6,120 | 6,121 |
| 2 | 08/02/2014 | 3 | | 6,129 | 6,130 |
| 1 | 08/02/2014 | 3 | | 6,143 | 6,144 |
| Stage 3 | | Frac Date: 08/02/2014 | Avg Rate: 57.7 BPM | Avg Pressure: 2,619 PSI | |
| Initial Completion | | Proppant: 124,100 lbs total | Max Rate: 61.3 BPM | Max Pressure: 4,175 PSI | |
| 124100 lbs Ottawa | | | | | |
| Initial Annulus Pressure: 0 | | Final Annulus Pressure: 0 | Pump Down Volume: | | |
| PreFrac SICP: | | ISIP: 2,371 PSI | Base BBLS to Recover: 4,012 BBLs | | |
| Pseudo Frac Gradient: 0.831 PSI/FT | | Pseudo Frac Gradient: 15.971 LB/GAL | | | |
| | | Net Pressure: | Total BBLS to Recover: 4,012 BBLs | | |
| Breakdown Pressure: 2212 | | Breakdown Rate: 9.8 | Perfs Open: | | |
| ScreenOut: No | | Tracer: (None) | | | |
| Zones: | Perf Date | SPF | Perf Interval: | From | To |
| 12 | 08/02/2014 | 3 | | 5,737 | 5,738 |
| 11 | 08/02/2014 | 3 | | 5,744 | 5,745 |
| 10 | 08/02/2014 | 3 | | 5,774 | 5,775 |
| 9 | 08/02/2014 | 3 | | 5,816 | 5,817 |
| 8 | 08/02/2014 | 3 | | 5,834 | 5,835 |
| 7 | 08/02/2014 | 3 | | 5,844 | 5,845 |
| 6 | 08/02/2014 | 3 | | 5,855 | 5,856 |
| 5 | 08/02/2014 | 3 | | 5,880 | 5,881 |
| 4 | 08/02/2014 | 3 | | 5,894 | 5,895 |
| 3 | 08/02/2014 | 3 | | 5,905 | 5,906 |
| 2 | 08/02/2014 | 3 | | 5,932 | 5,933 |
| 1 | 08/02/2014 | 3 | | 5,959 | 5,961 |

| | | | |
|--------------------|--|-------------------------------------|-----------------------------------|
| Stage 4 | Frac Date: 08/03/2014 | Avg Rate: 60.9 BPM | Avg Pressure: 3,318 PSI |
| Initial Completion | Proppant: 180,500 lbs total 180500 lbs Ottawa | Max Rate: 61.2 BPM | Max Pressure: 3,533 PSI |
| | Initial Annulus Pressure: 20 | Final Annulus Pressure: 22 | Pump Down Volume: |
| | PreFrac SICP: | ISIP: 1,740 PSI | Base BBLS to Recover: 4,927 BBLS |
| | Pseudo Frac Gradient: 0.738 PSI/FT | Pseudo Frac Gradient: 14.187 LB/GAL | |
| | | Net Pressure: -841 psi | Total BBLS to Recover: 4,927 BBLS |
| | Breakdown Pressure: 2503 | Breakdown Rate: 9.1 | Perfs Open: |
| | ScreenOut: No | Tracer: (None) | |
| Zones: | Perf Date | SPF | Perf Interval: From To |
| 13 | 08/02/2014 | 3 | 5,451 5,452 |
| 12 | 08/02/2014 | 3 | 5,468 5,469 |
| 11 | 08/02/2014 | 3 | 5,501 5,502 |
| 10 | 08/02/2014 | 3 | 5,545 5,546 |
| 9 | 08/02/2014 | 3 | 5,562 5,563 |
| 8 | 08/02/2014 | 3 | 5,586 5,587 |
| 7 | 08/02/2014 | 3 | 5,624 5,625 |
| 6 | 08/02/2014 | 3 | 5,639 5,640 |
| 5 | 08/02/2014 | 3 | 5,650 5,651 |
| 4 | 08/02/2014 | 3 | 5,667 5,668 |
| 3 | 08/02/2014 | 3 | 5,679 5,680 |
| 2 | 08/02/2014 | 3 | 5,699 5,700 |
| 1 | 08/02/2014 | 3 | 5,705 5,706 |
| Stage 5 | Frac Date: 08/03/2014 | Avg Rate: 60.7 BPM | Avg Pressure: 3,013 PSI |
| Initial Completion | Proppant: 180,813 lbs total 180813 lbs Ottawa | Max Rate: 63.2 BPM | Max Pressure: 4,142 PSI |
| | Initial Annulus Pressure: 22 | Final Annulus Pressure: 23 | Pump Down Volume: |
| | PreFrac SICP: | ISIP: 2,051 PSI | Base BBLS to Recover: 5,127 BBLS |
| | Pseudo Frac Gradient: 0.811 PSI/FT | Pseudo Frac Gradient: 15.595 LB/GAL | |
| | | Net Pressure: -324 psi | Total BBLS to Recover: 5,127 BBLS |
| | Breakdown Pressure: 2114 | Breakdown Rate: 9.5 | Perfs Open: |
| | ScreenOut: No | Tracer: (None) | |
| Zones: | Perf Date | SPF | Perf Interval: From To |
| 12 | 08/03/2014 | 3 | 5,277 5,278 |
| 11 | 08/03/2014 | 3 | 5,288 5,289 |
| 10 | 08/03/2014 | 3 | 5,305 5,306 |
| 9 | 08/03/2014 | 3 | 5,328 5,329 |
| 8 | 08/03/2014 | 3 | 5,339 5,340 |
| 7 | 08/03/2014 | 3 | 5,356 5,357 |
| 6 | 08/03/2014 | 3 | 5,365 5,366 |
| 5 | 08/03/2014 | 3 | 5,374 5,375 |
| 4 | 08/03/2014 | 3 | 5,382 5,383 |
| 3 | 08/03/2014 | 3 | 5,391 5,392 |
| 2 | 08/03/2014 | 3 | 5,401 5,402 |
| 1 | 08/03/2014 | 3 | 5,421 5,423 |
| Stage 6 | Frac Date: 08/03/2014 | Avg Rate: 57.3 BPM | Avg Pressure: 2,485 PSI |
| Initial Completion | Proppant: 129,542 lbs total 129542 lbs Ottawa | Max Rate: 63.5 BPM | Max Pressure: 3,672 PSI |
| | Initial Annulus Pressure: 0 | Final Annulus Pressure: 0 | Pump Down Volume: |
| | PreFrac SICP: | ISIP: 1,301 PSI | Base BBLS to Recover: 3,941 BBLS |
| | Pseudo Frac Gradient: 0.691 PSI/FT | Pseudo Frac Gradient: 13.286 LB/GAL | |
| | | Net Pressure: -903 psi | Total BBLS to Recover: 3,941 BBLS |
| | Breakdown Pressure: 2760 | Breakdown Rate: 9.5 | Perfs Open: |
| | ScreenOut: No | Tracer: (None) | |
| Zones: | Perf Date | SPF | Perf Interval: From To |
| 13 | 08/03/2014 | 3 | 4,740 4,741 |
| 12 | 08/03/2014 | 3 | 4,762 4,763 |
| 11 | 08/03/2014 | 3 | 4,776 4,777 |
| 10 | 08/03/2014 | 3 | 4,801 4,802 |
| 9 | 08/03/2014 | 3 | 4,822 4,823 |
| 8 | 08/03/2014 | 3 | 4,860 4,861 |
| 7 | 08/03/2014 | 3 | 4,875 4,876 |
| 6 | 08/03/2014 | 3 | 4,883 4,884 |
| 5 | 08/03/2014 | 3 | 4,936 4,937 |
| 4 | 08/03/2014 | 3 | 4,980 4,981 |
| 3 | 08/03/2014 | 3 | 4,992 4,993 |
| 2 | 08/03/2014 | 3 | 5,021 5,022 |
| 1 | 08/03/2014 | 3 | 5,040 5,041 |

| | | | |
|--------------------|------------------------------------|-------------------------------------|-----------------------------------|
| Stage 7 | Frac Date: 08/03/2014 | Avg Rate: 60.3 BPM | Avg Pressure: 1,982 PSI |
| Initial Completion | Proppant: 133,074 lbs total | Max Rate: 61.3 BPM | Max Pressure: 2,508 PSI |
| | 133074 lbs Ottawa | | |
| | Initial Annulus Pressure: 30 | Final Annulus Pressure: 30 | Pump Down Volume: |
| | PreFrac SICP: | ISIP: 1,297 PSI | Base BBLs to Recover: 3,804 BBLs |
| | Pseudo Frac Gradient: 0.709 PSI/FT | Pseudo Frac Gradient: 13.623 LB/GAL | |
| | | Net Pressure: | Total BBLs to Recover: 3,804 BBLs |
| | Breakdown Pressure: 1165 | Breakdown Rate: 9.4 | Perfs Open: |
| | ScreenOut: No | Tracer: (None) | |
| Zones: | Perf Date | SPF | Perf Interval: From To |
| 12 | 08/03/2014 | 3 | 4,535 4,536 |
| 11 | 08/03/2014 | 3 | 4,550 4,551 |
| 10 | 08/03/2014 | 3 | 4,560 4,561 |
| 9 | 08/03/2014 | 3 | 4,571 4,572 |
| 8 | 08/03/2014 | 3 | 4,579 4,580 |
| 7 | 08/03/2014 | 3 | 4,608 4,609 |
| 6 | 08/03/2014 | 3 | 4,619 4,620 |
| 5 | 08/03/2014 | 3 | 4,633 4,634 |
| 4 | 08/03/2014 | 3 | 4,657 4,658 |
| 3 | 08/03/2014 | 3 | 4,669 4,670 |
| 2 | 08/03/2014 | 3 | 4,684 4,685 |
| 1 | 08/03/2014 | 3 | 4,704 4,706 |

Hydraulic Fracturing Fluid Product Component Information Disclosure

| | |
|--------------------------------|-------------------------|
| Job Start Date: | 8/2/2014 |
| Job End Date: | 8/3/2014 |
| State: | Utah |
| County: | Uintah |
| API Number: | 43-047-54269-00-00 |
| Operator Name: | Ultra Resources |
| Well Name and Number: | Three Rivers 16-42L-820 |
| Longitude: | -109.66595000 |
| Latitude: | 40.12440000 |
| Datum: | NAD27 |
| Federal/Tribal Well: | NO |
| True Vertical Depth: | 7,500 |
| Total Base Water Volume (gal): | 1,250,118 |
| Total Base Non Water Volume: | 0 |



Hydraulic Fracturing Fluid Composition:

| Trade Name | Supplier | Purpose | Ingredients | Chemical Abstract Service Number (CAS #) | Maximum Ingredient Concentration in Additive (% by mass)** | Maximum Ingredient Concentration in HF Fluid (% by mass)** | Comments |
|--------------------------|-------------|----------------------|--|--|--|--|-----------------|
| Fresh Water | Operator | Base Fluid | | | | | |
| | | | Fresh Water | 7732-18-5 | 100.00000 | 90.42618 | Density = 8.330 |
| SAND - PREMIUM WHITE | Halliburton | Proppant | | | | | |
| | | | Crystalline silica, quartz | 14808-60-7 | 100.00000 | 8.60021 | |
| HYDROCHLORIC ACID 10-30% | Halliburton | Solvent | | | | | |
| | | | Hydrochloric acid | 7647-01-0 | 30.00000 | 0.18652 | |
| LoSurf-300D | Halliburton | Non-ionic Surfactant | | | | | |
| | | | Ethanol | 64-17-5 | 60.00000 | 0.05015 | |
| | | | Heavy aromatic petroleum naphtha | 64742-94-5 | 30.00000 | 0.02508 | |
| | | | Naphthalene | 91-20-3 | 5.00000 | 0.00418 | |
| | | | Poly(oxy-1,2-ethanediyl), alpha-(4-nonylphenyl)-omega-hydroxy-, branched | 127087-87-0 | 5.00000 | 0.00418 | |
| | | | 1,2,4 Trimethylbenzene | 95-63-6 | 1.00000 | 0.00084 | |
| WVG-36 GELLING AGENT | Halliburton | Gelling Agent | | | | | |
| | | | Guar gum | 9000-30-0 | 100.00000 | 0.04918 | |
| BC-140 | Halliburton | Crosslinker | | | | | |
| | | | Monoethanolamine borate | 26038-87-9 | 60.00000 | 0.02688 | |

| | | | | | | | |
|--|-------------|---------------------|--|--------------|-----------|---------|-----------------|
| | | | Ethylene glycol | 107-21-1 | 30.00000 | 0.01344 | |
| Cla-Web™ | Halliburton | Additive | | | | | |
| | | | Ammonium salt | Confidential | 60.00000 | 0.03040 | |
| MC MX 2-2822 | Multi-Chem | Scale Inhibitor | | | | | |
| | | | Phosphonate of a Diamine, Sodium Salt | Proprietary | 30.00000 | 0.01306 | |
| | | | Methyl alcohol | 67-56-1 | 30.00000 | 0.01306 | Density = 8.765 |
| FR-66 | Halliburton | Friction Reducer | | | | | |
| | | | Hydrotreated light petroleum distillate | 64742-47-8 | 30.00000 | 0.01258 | |
| FE-1A ACIDIZING COMPOSITION | Halliburton | Additive | | | | | |
| | | | Acetic anhydride | 108-24-7 | 100.00000 | 0.00623 | |
| | | | Acetic acid | 64-19-7 | 60.00000 | 0.00374 | |
| MC B-8614 | Multi-Chem | Biocide | | | | | |
| | | | Glutaraldehyde | 111-30-8 | 30.00000 | 0.00613 | |
| | | | Alkyl (C12-16) dimethylbenzylammonium chloride | 68424-85-1 | 5.00000 | 0.00102 | |
| OPTIFLO-HTE | Halliburton | Breaker | | | | | |
| | | | Walnut hulls | NA | 100.00000 | 0.00258 | |
| | | | Crystalline silica, quartz | 14808-60-7 | 30.00000 | 0.00077 | |
| BA-40L BUFFERING AGENT | Halliburton | Buffer | | | | | |
| | | | Potassium carbonate | 584-08-7 | 60.00000 | 0.00260 | |
| SP BREAKER | Halliburton | Breaker | | | | | |
| | | | Sodium persulfate | 7775-27-1 | 100.00000 | 0.00157 | |
| BA-20 BUFFERING AGENT | Halliburton | Buffer | | | | | |
| | | | Ammonium acetate | 631-61-8 | 100.00000 | 0.00112 | |
| | | | Acetic acid | 64-19-7 | 30.00000 | 0.00033 | |
| HAI-404M™ | Halliburton | Corrosion Inhibitor | | | | | |
| | | | Methanol | 67-56-1 | 30.00000 | 0.00034 | |
| | | | Aldehyde | Confidential | 30.00000 | 0.00034 | |
| | | | Isopropanol | 67-63-0 | 30.00000 | 0.00034 | |
| | | | Quaternary ammonium salt | Confidential | 10.00000 | 0.00011 | |
| | | | 1-(Benzyl)quinolinium chloride | 15619-48-4 | 10.00000 | 0.00011 | |
| Ingredients shown above are subject to 29 CFR 1910.1200(i) and appear on Material Safety Data Sheets (MSDS). Ingredients shown below are Non-MSDS. | | | | | | | |
| | | Other Ingredient(s) | | | | | |
| | | | Water | 7732-18-5 | | 0.72419 | |
| | | Other Ingredient(s) | | | | | |
| | | | Oxyalkylated phenolic resin | Confidential | | 0.02508 | |
| | | Other Ingredient(s) | | | | | |
| | | | Polyacrylamide copolymer | Confidential | | 0.01258 | |
| | | Other Ingredient(s) | | | | | |
| | | | Oxyalkylated phenolic resin | Confidential | | 0.00836 | |
| | | Other Ingredient(s) | | | | | |

| | | | | | | | |
|--|--|---------------------|--|--------------|--|---------|--|
| | | | Sodium chloride | 7647-14-5 | | 0.00463 | |
| | | Other Ingredient(s) | | | | | |
| | | | Quaternary amine | Confidential | | 0.00253 | |
| | | Other Ingredient(s) | | | | | |
| | | | Bentonite, benzyl(hydrogenated tallow alkyl) dimethylammonium stearate complex | 121888-68-4 | | 0.00246 | |
| | | Other Ingredient(s) | | | | | |
| | | | Alcohols, C12-16, ethoxylated | 68551-12-2 | | 0.00221 | |
| | | Other Ingredient(s) | | | | | |
| | | | Fatty acid tall oil amide | Confidential | | 0.00210 | |
| | | Other Ingredient(s) | | | | | |
| | | | Ammonium chloride | 12125-02-9 | | 0.00210 | |
| | | Other Ingredient(s) | | | | | |
| | | | Cured acrylic resin | Confidential | | 0.00077 | |
| | | Other Ingredient(s) | | | | | |
| | | | Quaternary amine | Confidential | | 0.00051 | |
| | | Other Ingredient(s) | | | | | |
| | | | Silica gel | 112926-00-8 | | 0.00049 | |
| | | Other Ingredient(s) | | | | | |
| | | | Surfactant mixture | Confidential | | 0.00049 | |
| | | Other Ingredient(s) | | | | | |
| | | | Surfactant mixture | Confidential | | 0.00049 | |
| | | Other Ingredient(s) | | | | | |
| | | | Sorbitan, mono-9-octadecenoate, (Z) | 1338-43-8 | | 0.00042 | |
| | | Other Ingredient(s) | | | | | |
| | | | Sorbitan monooleate polyoxyethylene derivative | 9005-65-6 | | 0.00042 | |
| | | Other Ingredient(s) | | | | | |
| | | | Naphthenic acid ethoxylate | 68410-62-8 | | 0.00034 | |
| | | Other Ingredient(s) | | | | | |
| | | | Enzyme | Confidential | | 0.00013 | |
| | | Other Ingredient(s) | | | | | |
| | | | Fatty acids, tall oil | Confidential | | 0.00011 | |
| | | Other Ingredient(s) | | | | | |
| | | | Polyethoxylated fatty amine salt | 61791-26-2 | | 0.00011 | |
| | | Other Ingredient(s) | | | | | |
| | | | Ethoxylated amine | Confidential | | 0.00006 | |
| | | Other Ingredient(s) | | | | | |
| | | | Amine salts | Confidential | | 0.00005 | |
| | | Other Ingredient(s) | | | | | |
| | | | Quaternary amine | Confidential | | 0.00005 | |
| | | Other Ingredient(s) | | | | | |
| | | | Amine salts | Confidential | | 0.00005 | |
| | | Other Ingredient(s) | | | | | |
| | | | Crystalline Silica, Quartz | 14808-60-7 | | 0.00005 | |

| | | | | | | | |
|--|--|---------------------|---------------------|--------------|--|---------|--|
| | | Other Ingredient(s) | | | | | |
| | | | Methanol | 67-56-1 | | 0.00003 | |
| | | Other Ingredient(s) | | | | | |
| | | | Cured acrylic resin | Confidential | | 0.00003 | |
| | | Other Ingredient(s) | | | | | |
| | | | C.I. Pigment Red 5 | 6410-41-9 | | 0.00003 | |
| | | Other Ingredient(s) | | | | | |
| | | | Ammonium phosphate | 7722-76-1 | | 0.00001 | |
| | | Other Ingredient(s) | | | | | |
| | | | Sodium iodide | 7681-82-5 | | 0.00001 | |
| | | Other Ingredient(s) | | | | | |
| | | | Phosphoric Acid | 7664-38-2 | | 0.00000 | |
| | | Other Ingredient(s) | | | | | |
| | | | Sodium sulfate | 7757-82-6 | | 0.00000 | |

* Total Water Volume sources may include fresh water, produced water, and/or recycled water

** Information is based on the maximum potential for concentration and thus the total may be over 100%

Note: For Field Development Products (products that begin with FDP), MSDS level only information has been provided.

Ingredient information for chemicals subject to 29 CFR 1910.1200(i) and Appendix D are obtained from suppliers Material Safety Data Sheets (MSDS)

Simulation Design Worksheet

Company Ultra Petroleum
Formation Three Rivers 16-42L-820
Perfs 6168 - 6299
Zone #1
Fluid System: 16-42L-820 (13) Hybrid
Temperature 163 °F
API 43-047-54269

Liquid Additives

| Stage | Fluid | Fluid | Prop Conc | Prop | Slurry Vol | Slurry Rate | Treating Pressure | Stage Pump Time | Exposure Time | WG-36 Gel | LoSurf-300D Surfactant | CLA-Web Clay Control | B-8514 Biocide | MX-2-2822 Scale Inh. | BC-140 Crosslinker | Optifo-HTE Breaker | SP Breaker | FR-66 Frict. Red. |
|-------|-------------------------|-------|-----------|-------|------------|-------------|-------------------|-----------------|---------------|-----------|------------------------|----------------------|----------------|----------------------|--------------------|--------------------|------------|-------------------|
| 1 | Load & Break | 342 | | | 8.1 | 6.3 | 1477 | 0:01:18 | 0:58:44 | | 1.00 | 0.50 | 0.20 | | | | | 0.50 |
| 2 | 15% HCl Acid | 1000 | | | 23.8 | 9.9 | 2223 | 0:02:24 | 0:57:26 | | | | | | | | | |
| 3 | Pad | 37445 | | | 891.5 | 53.0 | 2630 | 0:16:49 | 0:55:02 | | 1.00 | 0.50 | 0.20 | 0.73 | | | | 0.50 |
| 4 | 0.35#/gal 20/40 White | 49141 | 0.35 | 17160 | 1188.6 | 60.8 | 2488 | 0:19:33 | 0:38:12 | | 1.00 | 0.50 | 0.20 | 0.73 | | | | 0.50 |
| 5 | 0.35#/gal 20/40 White | 5045 | 0.33 | 1680 | 121.9 | 60.7 | 2514 | 0:02:01 | 0:18:40 | | 1.00 | 0.50 | 0.20 | 2.00 | | | | 0.50 |
| 6 | 0.35#/gal 20/40 White | 5087 | 0.32 | 1650 | 122.9 | 60.7 | 2535 | 0:02:01 | 0:16:39 | 7.08 | 1.00 | 0.50 | 0.20 | 0.25 | 0.71 | 0.39 | 0.20 | |
| 7 | Pad | 3631 | | | | 60.9 | 2570 | | 0:14:38 | 18.00 | 1.00 | 0.50 | 0.20 | 0.25 | 1.80 | 1.00 | 0.50 | |
| 8 | 2.0 #/gal 20/40 White | 11408 | 1.93 | 21950 | 295.3 | 61.0 | 2645 | 0:04:50 | 0:14:38 | 18.00 | 1.00 | 0.50 | 0.20 | 0.25 | 1.80 | 1.00 | 0.50 | |
| 9 | 4.0 #/gal 20/40 White | 6491 | 3.82 | 24780 | 181.2 | 61.3 | 2523 | 0:02:57 | 0:09:47 | 18.00 | 1.00 | 0.50 | 0.20 | 0.25 | 1.80 | 1.00 | 0.50 | |
| 10 | 6.0 #/gal 20/40 White | 5985 | 4.50 | 26940 | 171.5 | 61.0 | 2327 | 0:02:49 | 0:06:50 | 18.00 | 1.00 | 0.50 | 0.20 | 0.25 | 1.80 | 1.00 | 0.50 | |
| 11 | Flush (top perf+3 bbls) | 6257 | | | 149.0 | 37.1 | 2257 | 0:04:01 | 0:04:01 | | 1.00 | 0.50 | 0.20 | | 1.80 | 1.00 | 0.50 | |
| 13 | Growler Tub Variance | 2238 | | | | | | | | 48.00 | 1.00 | 0.50 | 0.20 | | | | | 0.50 |

| | | |
|-------------------------|---------|-----|
| 15% HCl Acid: | 1,000 | gal |
| Slickwater: | 101,317 | gal |
| 18# DeltaFrac 140 (13): | 29,515 | gal |
| Total Fluid: | 131,832 | gal |
| Total Slurry: | 132,465 | gal |
| 20/40 White: | 94,200 | lbs |
| Total Proppant: | 94,200 | lbs |

94,200 3153.9
Average Rate 48.4

| | | | | | | | | | |
|--------|-------|-------|------|------|------|------|------|------|------|
| Used | 638.7 | 133.1 | 66.5 | 26.5 | 80.0 | 53.1 | 29.5 | 14.8 | 49.1 |
| % diff | 670 | 135 | 67 | 30 | 80 | 54 | 30 | 15 | 49 |
| Prime | | 1% | | 13% | | | | | |
| Total | 670 | 135 | 67 | 30 | 92 | 54 | 34 | 15 | 55 |

| | |
|-------------|-------|
| TOP PERF | 6,168 |
| BOTTOM PERF | 6,299 |
| MID PERF | |
| BHT | |

BHT GRAD [°F/100-ft (+60°)]

43-047-54269

API #

AFE#

Sec. / Twp. / Ring.

Well Name

Company

Formation

Fluid Systems

Date

Base Fluid, lb/gal

Sales Order #

County and State

S:16 / T:8S / R:20E

Three Rivers 16-42L-820

Ultra Petroleum

18# DeltaFrac 140 (13) Hybrid

August 1, 2014

8.33

901549841

Utah, UT

Zone #1

| Total Perfs: 36 | | | |
|-----------------|-------------|-----|------------|
| Top Perf | Bottom Perf | SPF | # of shots |
| 6168 | 6169 | 3 | 3 |
| 6178 | 6179 | 3 | 3 |
| 6189 | 6190 | 3 | 3 |
| 6202 | 6203 | 3 | 3 |
| 6207 | 6208 | 3 | 3 |
| 6229 | 6230 | 3 | 3 |
| 6236 | 6237 | 3 | 3 |
| 6242 | 6243 | 3 | 3 |
| 6267 | 6268 | 3 | 3 |
| 6290 | 6291 | 3 | 3 |
| 6297 | 6299 | 3 | 6 |

| | |
|-------------|-----------------|
| Start Time: | 1:32 PM |
| End Time: | 2:30 PM |
| Customer: | Andy Hutchinson |

Company Ultra Petroleum
 Formations Three Rivers 16-42L-820 API 43-047-54269
 Zone #2 Temperature 160 °F
 Fluid System: 16-42L-820 Hybrid

Liquid Additives

| Stage | Fluid | Fluid | Prop Conc | Prop | Slurry Vol | Slurry Rate | Treating Pressure | Pump Time | Stage | Exposure Time | WG-36 Gel | LoSurf-300D Surfactant | CLA-Web Clay Control | B-8614 Biocide | MX 2-2822 Scale Inh. | BC-140 Crosslinker | OptiFlo-HTE Breaker | SP Breaker | FR-66 Frict. Red. |
|--------|-------------------------|-------|-----------|-------|------------|-------------|-------------------|-----------|---------|---------------|-----------|------------------------|----------------------|----------------|----------------------|--------------------|---------------------|------------|-------------------|
| 1 | Lead & Break | 212 | | | 5.0 | 4.7 | 1385 | 0:01:04 | 1:22:36 | 1:22:36 | | 1.00 | 0.50 | 0.20 | | | | | 0.50 |
| 2 | 15% HCl Acid | 1000 | | | 23.8 | 9.7 | 1552 | 0:02:27 | 1:21:31 | 1:21:31 | | | | | | | | | |
| 3 | Pad | 57075 | | | 1358.9 | 59.3 | 2845 | 0:22:55 | 1:19:04 | 1:19:04 | | 1.00 | 0.50 | 0.20 | 0.44 | | | | 0.50 |
| 4 | 0.35#/gal 20/40 White | 82030 | 0.32 | 26260 | 1981.4 | 60.7 | 2460 | 0:32:39 | 0:56:09 | 0:56:09 | | 1.00 | 0.50 | 0.20 | 0.44 | | | | 0.50 |
| 5 | 0.35#/gal 20/40 White | 5023 | 0.33 | 1670 | 121.4 | 60.8 | 2380 | 0:02:00 | 0:23:31 | 0:23:31 | | 1.00 | 0.50 | 0.20 | 2.00 | | | | 0.50 |
| 6 | 0.35#/gal 20/40 White | 5052 | 0.34 | 1700 | 122.1 | 60.8 | 2387 | 0:02:01 | 0:21:31 | 0:21:31 | 10.89 | 1.00 | 0.50 | 0.20 | 0.25 | 1.07 | 0.59 | 0.30 | |
| 7 | Pad | 484 | 0.35 | 170 | 11.7 | 61.1 | 2386 | 0:00:11 | 0:19:30 | 0:19:30 | 18.00 | 1.00 | 0.50 | 0.20 | 0.25 | 1.80 | 1.00 | 0.50 | |
| 8 | 2.0 #/gal 20/40 White | 17727 | 1.98 | 35100 | 459.9 | 60.9 | 2301 | 0:07:33 | 0:19:19 | 0:19:19 | 18.00 | 1.00 | 0.50 | 0.20 | 0.25 | 1.80 | 1.00 | 0.50 | |
| 9 | 4.0 #/gal 20/40 White | 10105 | 3.92 | 39600 | 283.3 | 60.9 | 2124 | 0:04:39 | 0:11:46 | 0:11:46 | 18.00 | 1.00 | 0.50 | 0.20 | 0.25 | 1.80 | 1.00 | 0.50 | |
| 10 | 6.0 #/gal 20/40 White | 8188 | 5.18 | 42400 | 240.6 | 60.7 | 1998 | 0:03:58 | 0:07:07 | 0:07:07 | 18.00 | 1.00 | 0.50 | 0.20 | | 1.80 | 1.00 | 0.50 | |
| 11 | Flush (top perf+3 bbls) | 6332 | | | 150.8 | 47.9 | 2096 | 0:03:09 | 0:03:09 | 0:03:09 | | 1.00 | 0.50 | 0.20 | | | | 0.50 | |
| 13 | Growler Tub Variance | | | | | | | | | | 50.00 | 1.00 | 0.50 | 0.20 | | | | | 0.50 |
| | | | | | | | | | | | 711.1 | 192.2 | 96.1 | 38.4 | 80.0 | 71.1 | 39.5 | 19.8 | 75.3 |
| Used | | | | | | | | | | | 747 | 195 | 96 | 42 | 80 | 72 | 40 | 20 | 82 |
| % diff | | | | | | | | | | | 5% | 1% | | 9% | | | | | 9% |
| Prime | | | | | | | | | | | | | | | | | | | |
| Total | | | | | | | | | | | 747 | 195 | 96 | 42 | 80 | 72 | 40 | 20 | 82 |

| | | |
|-------------------------|---------|-----|
| 15% HCl Acid: | 1,000 | gal |
| Slickwater: | 152,724 | gal |
| 16# DeltaFrac 140 (13): | 39,504 | gal |
| Total Fluid: | 193,228 | gal |
| Total Slurry: | 199,663 | gal |
| 20/40 White: | 146,900 | lbs |
| Total Proppant: | 146,900 | lbs |

Average Rate 49.8

146,900 4753.9

| | |
|-------------|-------|
| TOP PERF | 5,984 |
| BOTTOM PERF | 6,144 |
| MID PERF | |
| BHT | |

BHT GRAD [*F/100-ft (+60°F)]

API # 43-047-54269
 AFE#
 Sec. / Twp. / Rng. S:16 / T:8S / R:20E
 Well Name Three Rivers 16-42L-820
 Company Ultra Petroleum
 Formation 16# DeltaFrac 140 (13) Hybrid
 Fluid Systems August 1, 2014
 Date
 Base Fluid, lb/gal 8.33
 Sales Order # 901549841
 County and State Uintah, UT

Zone #2

| Total Perfs: 39 | | | |
|-----------------|-------------|-----|------------|
| Top Perf | Bottom Perf | SPF | # of shots |
| 5984 | 5985 | 3 | 3 |
| 6005 | 6006 | 3 | 3 |
| 6010 | 6011 | 3 | 3 |
| 6024 | 6025 | 3 | 3 |
| 6052 | 6053 | 3 | 3 |
| 6064 | 6065 | 3 | 3 |
| 6073 | 6074 | 3 | 3 |
| 6091 | 6092 | 3 | 3 |
| 6103 | 6104 | 3 | 3 |
| 6110 | 6111 | 3 | 3 |
| 6120 | 6121 | 3 | 3 |
| 6129 | 6130 | 3 | 3 |
| 6143 | 6144 | 3 | 3 |

| | |
|-------------|-----------------|
| Start Time: | 4:09 PM |
| End Time: | 5:30 PM |
| Customer: | Brett Stringham |

Company Ultra Petroleum
 Formation Three Rivers 16-42L-820
 Zone #3 Zone 157
 Fluid System: 18# DeltaFrac 140 (13) Hybrid
 5737 - 5961

API 43-047-54269
 Temperature 157 °F

Liquid Additives

| Stage | Fluid | Fluid | Prop Conc | Prop | Slurry Vol | Slurry Rate | Treating Pressure | Pump Time | Stage | Exposure | WG-36 | LoSurf-300D | CL-A-Web | BioCide | MX 2-2822 | BC-140 | OptiLo-HTE | SP Breaker | FR-86 |
|-------|-------------------------|-------|-----------|-------|------------|-------------|-------------------|--------------|-------|--------------|-------|-------------|----------|---------|-----------|--------|------------|------------|-------|
| | (gal) | (gal) | (ppg) | (lbs) | (bbls) | (gpm) | (psi) | (hr:min:sec) | | (hr:min:sec) | (ppg) | (gpt) | (gpt) | (gpt) | (gpt) | (gpt) | (gpt) | (gpt) | (gpt) |
| 1 | Load & Break | 179 | | | 4.3 | 5.9 | 1604 | 0:00:43 | | 1:20:41 | | 1.00 | 0.50 | 0.20 | | | | | |
| 2 | 15% HCl Acid | 1001 | | | 23.8 | 9.8 | 2099 | 0:02:26 | | 1:19:58 | | | | | | | | | |
| 3 | Pad | 50028 | | | 1191.1 | 49.4 | 2721 | 0:24:07 | | 1:17:32 | | 1.00 | 0.50 | 0.20 | 0.52 | | | | 0.50 |
| 4 | 0.35#/gal 20/40 White | 70176 | 0.33 | 23500 | 1696.2 | 60.6 | 2532 | 0:27:59 | | 0:53:26 | | 1.00 | 0.50 | 0.20 | 0.52 | | | | 0.50 |
| 5 | 0.35#/gal 20/40 White | 5022 | 0.35 | 1780 | 121.5 | 60.5 | 2614 | 0:02:00 | | 0:25:26 | | 1.00 | 0.50 | 0.20 | 2.00 | | | | 0.50 |
| 6 | 0.35#/gal 20/40 White | 4941 | 0.37 | 1840 | 119.6 | 60.9 | 2598 | 0:01:58 | | 0:23:26 | 18.00 | 1.00 | 0.50 | 0.20 | 0.25 | 1.80 | 1.00 | 0.50 | |
| 8 | 2.0 #/gal 20/40 White | 15447 | 1.94 | 29910 | 400.0 | 60.9 | 2558 | 0:06:34 | | 0:21:28 | 18.00 | 1.00 | 0.50 | 0.20 | 0.25 | 1.80 | 1.00 | 0.50 | |
| 9 | 4.0 #/gal 20/40 White | 8791 | 3.82 | 33590 | 245.5 | 61.0 | 2613 | 0:04:01 | | 0:14:54 | 18.00 | 1.00 | 0.50 | 0.20 | 0.25 | 1.80 | 1.00 | 0.50 | |
| 10 | 6.0 #/gal 20/40 White | 7258 | 4.61 | 33480 | 208.9 | 46.1 | 2795 | 0:04:32 | | 0:10:52 | 18.00 | 1.00 | 0.50 | 0.20 | | 1.80 | 1.00 | 0.50 | |
| 11 | Flush (top perf+3 bbls) | 5671 | | | 135.0 | 21.3 | 3927 | 0:06:20 | | 0:06:20 | 50.00 | 1.00 | 0.50 | 0.20 | | | | 0.50 | |
| 13 | Growler Tub Variance | | | | | | | | | | | | | | | | | | |

| | | | | |
|-------------------------|---------|-----|---------|--------|
| 15% HCl Acid: | 1,000 | gal | 124,100 | 4141.7 |
| Slickwater: | 131,077 | gal | | |
| 18# DeltaFrac 140 (13): | 36,437 | gal | | |
| Total Fluid: | 168,514 | gal | | |
| Total Slurry: | 173,950 | gal | | |
| 20/40 White: | 124,100 | lbs | | |
| Total Proppant: | 124,100 | lbs | | |

Used

% diff

Prime

Total

Average Rate

43.6

| | |
|-------------|-------|
| TOP PERF | 5,737 |
| BOTTOM PERF | 5,961 |
| MID PERF | 5,849 |
| BHT | 5,849 |

BHT GRAD (°F/100-ft (+60°))

43-047-54269
 S:16 / T:8S / R:20E
 Three Rivers 16-42L-820
 Ultra Petroleum
 18# DeltaFrac 140 (13) Hybrid
 August 2, 2014
 Base Fluid, lb/gal
 Sales Order # 901549841
 County and State Utah, UT

Zone #3

| Total Perfs: 39 | | | |
|-----------------|-------------|-----|------------|
| Top Perf | Bottom Perf | SPF | # of shots |
| 5737 | 5738 | 3 | 3 |
| 5744 | 5745 | 3 | 3 |
| 5774 | 5775 | 3 | 3 |
| 5816 | 5817 | 3 | 3 |
| 5834 | 5835 | 3 | 3 |
| 5844 | 5845 | 3 | 3 |
| 5855 | 5856 | 3 | 3 |
| 5880 | 5881 | 3 | 3 |
| 5894 | 5895 | 3 | 3 |
| 5905 | 5906 | 3 | 3 |
| 5932 | 5933 | 3 | 3 |
| 5959 | 5961 | 3 | 6 |

| | |
|-------------|------------|
| Start Time: | 8:14 PM |
| End Time: | 9:35 PM |
| Customer: | Joe Duncan |

| Stage | Fluid | Fluid | Prop Conc | Prop | Slurry Vol | Slurry | Treating | Stage | Exposure | WG-36 | LoSurf-300D | CLA-Web | B-4514 | MX 2-2822 | BC-140 | Optifo-HTE | SP Breaker | FR-66 |
|-------|-------------------------|-------|-----------|-------|------------|--------|----------------|-----------------------|------------------|-----------|------------------|--------------------|---------------|------------------|-------------------|---------------|------------------|-------|
| | | (gal) | (ppg) | (lbs) | (bbls) | (bpm) | Pressure (psi) | Pump Time (h:min:sec) | Time (h:min:sec) | Gel (ppt) | Surfactant (gpt) | Clay Control (gpt) | Bloodie (gpt) | Scale Inh. (gpt) | Crosslinker (gpt) | Breaker (ppt) | Ficld. Red (gpt) | |
| 1 | Load & Break | 83 | | | 2.0 | 5.7 | 2157 | 0:00:21 | 1:29:00 | | 1.00 | 0.50 | 0.20 | | | | | 0.50 |
| 2 | 15% HCl Acid | 1048 | | | 25.0 | 9.0 | 1974 | 0:02:46 | 1:28:39 | | | | | | | | | |
| 3 | Pad | 56960 | | | | | | | | | | | | | | | | |
| 4 | 0.5#/gal 20/40 White | 91731 | 0.47 | 43040 | 2230.4 | 67.5 | 2681 | 0:23:35 | 1:25:53 | | 1.00 | 0.50 | 0.20 | 0.41 | | | | 0.50 |
| 5 | 0.5#/gal 20/40 White | 5005 | 0.50 | 2480 | 121.8 | 60.6 | 2843 | 0:02:01 | 0:25:22 | 6.00 | 1.00 | 0.50 | 0.20 | 2.00 | | | | 0.65 |
| 6 | 0.5#/gal 20/40 White | 4987 | 0.51 | 2530 | 121.5 | 60.9 | 3226 | 0:02:00 | 0:23:21 | 18.00 | 1.00 | 0.50 | 0.20 | 0.25 | 1.60 | 1.00 | 0.50 | 0.70 |
| 8 | 2.0 #/gal 20/40 White | 19990 | 1.97 | 39290 | 518.3 | 60.7 | 3400 | 0:08:32 | 0:21:22 | 18.00 | 1.00 | 0.50 | 0.20 | 0.25 | 1.60 | 1.00 | 0.50 | |
| 9 | 4.0 #/gal 20/40 White | 11353 | 3.85 | 43750 | 317.4 | 61.0 | 3342 | 0:05:12 | 0:12:49 | 18.00 | 1.00 | 0.50 | 0.20 | 0.25 | 1.60 | 1.00 | 0.50 | |
| 10 | 6.0 #/gal 20/40 White | 10365 | 4.77 | 48410 | 300.0 | 61.0 | 3132 | 0:04:55 | 0:07:37 | 18.00 | 1.00 | 0.50 | 0.20 | 0.20 | 1.60 | 1.00 | 0.50 | |
| 11 | Flush (top perf+3 bbls) | 5429 | | | 129.3 | 47.9 | 2838 | 0:02:42 | 0:02:42 | | 1.00 | 0.50 | 0.20 | | | | | 0.70 |
| 13 | Growler Tub Variance | | | | | | | | | 50.00 | 1.00 | 0.50 | 0.20 | | | | | |

Average Rate **5119.9**

| | |
|-------------|-------|
| TOP PERF | 5,451 |
| BOTTOM PERF | 5,706 |
| MID PERF | 5,579 |
| BHT | 552 |

BHT GRAD [°F/100-ft (+60°)]API #

AFE#

Two. / Rnd.Well Name

CONFIDENTIAL

Company

Formation

Solid Systems 16# DeDate _____Fluid, lb/gales Order #

and State

Zone #4

Chances

| Total Perfs: 39 | | | |
|-----------------|-------------|-----|------------|
| Top Perf | Bottom Perf | SPF | # of shots |
| 5451 | 5452 | 3 | 3 |
| 5468 | 5469 | 3 | 3 |
| 5501 | 5502 | 3 | 3 |
| 5545 | 5546 | 3 | 3 |
| 5582 | 5583 | 3 | 3 |
| 5586 | 5587 | 3 | 3 |
| 5624 | 5625 | 3 | 3 |
| 5639 | 5640 | 3 | 3 |
| 5650 | 5651 | 3 | 3 |
| 5667 | 5668 | 3 | 3 |
| 5679 | 5680 | 3 | 3 |
| 5699 | 5700 | 3 | 3 |
| 5705 | 5706 | 3 | 3 |

| | |
|-------------|------------|
| Start Time: | 12:39 AM |
| End Time: | 2:10 AM |
| Customer: | Joe Duncan |

Company Ultra Petroleum
 Formation Three Rivers 16-42L-820
 Perfs 5277 - 5423 Zone #5
 Fluid System: 16# DeltaFrac 140 (13) Hybrid

API 43-047-54269
 Temperature 148 °F

Liquid Additives

| Stage | Fluid | Fluid | Prop Conc | Prop | Slurry Vol | Slurry Rate | Treating Pressure | Stage Pump Time | Exposure Time | WG-36 Gel | LoSurf-3000 Surfactant | CLA-Web Clay Control | B-8514 Biocide | MX 2-2822 Scale Inh. | BC-140 Crosslinker | Optillo-HTE Breaker | SP Breaker | FR-66 Frict Red |
|-------|-------------------------|-------|-----------|-------|------------|-------------|-------------------|-----------------|---------------|-----------|------------------------|----------------------|----------------|----------------------|--------------------|---------------------|------------|-----------------|
| 1 | Load & Break | 243 | | | 5.8 | 7.6 | 1922 | 0:00:46 | 1:37:35 | | 1.00 | 0.50 | 0.20 | | | | | 0.70 |
| 2 | 15% HCl Acid | 2000 | | | 47.5 | 9.8 | 2139 | 0:04:52 | 1:36:49 | | | | | | | | | |
| 3 | Pad | 57632 | | | 1372.2 | 53.6 | 3864 | 0:25:36 | 1:31:58 | | 1.00 | 0.50 | 0.20 | 0.39 | | | | 0.70 |
| 4 | 0.5#/gal 20/40 White | 83024 | 0.46 | 42880 | 2261.1 | 60.8 | 3036 | 0:37:11 | 1:06:22 | | 1.00 | 0.50 | 0.20 | 0.39 | | | | 0.70 |
| 5 | 0.5#/gal 20/40 White | 4951 | 0.50 | 2467 | 120.5 | 60.8 | 3010 | 0:01:59 | 0:29:11 | | 1.00 | 0.50 | 0.20 | 2.00 | | | | 0.70 |
| 6 | 0.5#/gal 20/40 White | 5904 | 0.51 | 3026 | 143.8 | 60.9 | 3059 | 0:02:22 | 0:27:12 | 16.00 | 1.00 | 0.50 | 0.20 | 0.25 | 1.60 | 1.00 | 0.50 | 0.70 |
| 7 | Pad | 5663 | 0.00 | 8 | 134.8 | 60.7 | 3191 | 0:02:13 | 0:24:50 | 16.00 | 1.00 | 0.50 | 0.20 | 0.25 | 1.60 | 1.00 | 0.50 | |
| 8 | 2.0 #/gal 20/40 White | 20266 | 1.97 | 39850 | 525.5 | 60.5 | 3121 | 0:08:41 | 0:22:37 | 16.00 | 1.00 | 0.50 | 0.20 | 0.25 | 1.60 | 1.00 | 0.50 | |
| 9 | 4.0 #/gal 20/40 White | 11518 | 3.83 | 44150 | 321.8 | 60.5 | 2826 | 0:05:19 | 0:13:55 | 16.00 | 1.00 | 0.50 | 0.20 | 0.25 | 1.60 | 1.00 | 0.50 | |
| 10 | 6.0 #/gal 20/40 White | 10084 | 4.80 | 48430 | 292.5 | 60.4 | 2863 | 0:04:51 | 0:08:36 | 16.00 | 1.00 | 0.50 | 0.20 | 0.25 | 1.60 | 1.00 | 0.50 | |
| 11 | Flush (top perf+3 bbls) | 5041 | | | 120.0 | 31.9 | 2364 | 0:03:46 | 0:03:46 | 50.00 | 1.00 | 0.50 | 0.20 | | | | | 0.70 |
| 13 | Growler Tub Variance | | | | | | | | | | | | | | | | | |

| | | |
|-------------------------|---------|-----|
| 15% HCl Acid: | 2,000 | gal |
| Slickwater: | 160,891 | gal |
| 16# DeltaFrac 140 (11): | 53,445 | gal |
| Total Fluid: | 216,336 | gal |
| Total Slurry: | 224,275 | gal |
| 20/40 White: | 180,821 | lbs |
| Total Proppant: | 180,821 | lbs |

180,821

5339.9

Average Rate

48.0

Used

% diff

Prime

Total

1055

218

108

47

80

87

53

27

123

5%

| | |
|-------------|-------|
| TOP PERF | 5,277 |
| BOTTOM PERF | 5,423 |
| MID PERF | |
| BHT | |

BHT GRAD [°F/100-ft (+60°F)]

43-047-54269

S-16 / T-8S / R-20E

Three Rivers 16-42L-820

Ultra Petroleum

16# DeltaFrac 140 (13) Hybrid

August 2, 2014

8.33

901549841

Uintah, UT

Zone #5

| Total Perfs: 39 | | | |
|-----------------|-------------|-----|------------|
| Top Perf | Bottom Perf | SPF | # of shots |
| 5277 | 5278 | 3 | 3 |
| 5288 | 5289 | 3 | 3 |
| 5305 | 5306 | 3 | 3 |
| 5328 | 5329 | 3 | 3 |
| 5339 | 5340 | 3 | 3 |
| 5356 | 5357 | 3 | 3 |
| 5365 | 5366 | 3 | 3 |
| 5374 | 5375 | 3 | 3 |
| 5382 | 5383 | 3 | 3 |
| 5391 | 5392 | 3 | 3 |
| 5401 | 5402 | 3 | 3 |
| 5421 | 5423 | 3 | 6 |
| | | 3 | |

| | |
|-------------|------------|
| Start Time: | 5:00 AM |
| End Time: | 6:34 AM |
| Customer: | Joe Duncan |

Simulation Design Worksheet

Company Ultra Petroleum
 Formation Three Rivers 16-42L-820
 Zone #6
 Fluid System: aFrac 140 (13) Hybrid
 Perfs 4740 - 5041

43-047-54269
 °F

Liquid Additives

| Stage | Fluid | Fluid | Prop Conc | Prop | Slurry Vol | Slurry Rate | Treating Pressure | Pump Time | Stage | Exposure Time | WG-36 Gal | LoSurf-300D Surfactant | CLAWeb Clay Control | B-8814 Biocide | MX 2-2822 Scale Inh. | BC-140 Crosslinker | Conflo-HTE Breaker | SP Breaker | FR-66 Frict. Red. | BA-20 Buffer |
|--------|-------------------------|-------|-----------|-------|------------|-------------|-------------------|-----------|-------|---------------|-----------|------------------------|---------------------|----------------|----------------------|--------------------|--------------------|------------|-------------------|--------------|
| 1 | Load & Break | 246 | | | 5.9 | 6.5 | 1694 | 0:00:54 | | 1:14:42 | | 1.00 | 0.50 | 0.20 | | | | | 0.70 | |
| 2 | 15% HCl Acid | 1000 | | | 23.8 | 9.7 | 2235 | 0:02:27 | | 1:13:48 | | | | | | | | | | |
| 3 | Pad | 40877 | | | 973.3 | 54.4 | 2576 | 0:17:53 | | 1:11:21 | | 1.00 | 0.50 | 0.20 | 0.57 | | | | 0.70 | |
| 4 | 0.5#/gal 20/40 White | 62160 | 0.50 | 30770 | 1513.2 | 60.4 | 2399 | 0:25:03 | | 0:53:28 | | 1.00 | 0.50 | 0.20 | 0.57 | | | | 0.35 | |
| 5 | 0.5#/gal 20/40 White | 5022 | 0.55 | 2742 | 122.5 | 60.3 | 2683 | 0:02:02 | | 0:28:24 | | 1.00 | 0.50 | 0.20 | 2.00 | | | | 0.30 | |
| 6 | 0.5#/gal 20/40 White | 5029 | 0.55 | 2790 | 122.7 | 60.2 | 2781 | 0:02:02 | | 0:28:23 | 16.00 | 1.00 | 0.50 | 0.20 | 0.25 | 1.60 | 1.00 | 0.50 | | 0.10 |
| 7 | Pad | 16598 | 0.02 | 334 | 395.5 | 60.2 | 2768 | 0:06:34 | | 0:24:20 | 16.00 | 1.00 | 0.50 | 0.20 | 0.25 | 1.60 | 1.00 | 0.50 | | 0.10 |
| 8 | 2.0 #/gal 20/40 White | 14500 | 2.00 | 29000 | 376.5 | 50.0 | 2514 | 0:07:32 | | 0:17:46 | 16.00 | 1.00 | 0.50 | 0.20 | 0.25 | 1.60 | 1.00 | 0.50 | | 0.10 |
| 9 | 4.0 #/gal 20/40 White | 8088 | 3.83 | 30970 | 225.9 | 60.1 | 2657 | 0:03:46 | | 0:10:14 | 16.00 | 1.00 | 0.50 | 0.20 | 0.25 | 1.60 | 1.00 | 0.50 | | 0.10 |
| 10 | 6.0 #/gal 20/40 White | 6978 | 4.77 | 33270 | 202.0 | 60.0 | 2462 | 0:03:22 | | 0:06:29 | 16.00 | 1.00 | 0.50 | 0.20 | 0.25 | 1.60 | 1.00 | 0.50 | | 0.10 |
| 11 | Flush (top perf-3 bbls) | 5008 | | | 119.2 | 38.3 | 2118 | 0:03:07 | | 0:03:07 | | 1.00 | 0.50 | 0.20 | | 1.60 | 1.00 | 0.50 | 0.30 | |
| 13 | Growler Tub Variance | | | | | | | | | | 50.00 | 1.00 | 0.50 | 0.20 | | | | | | 0.10 |
| | | | | | | | | | | | 819.1 | 164.5 | 82.3 | 32.9 | 80.0 | 81.9 | 51.2 | 25.6 | 53.5 | 5.1 |
| Used | | | | | | | | | | | 846 | 167 | 83 | 36 | 80 | 83 | 51 | 26 | 58 | |
| % diff | | | | | | | | | | | 3% | 2% | | 9% | | 1% | | | 8% | |
| Prime | | | | | | | | | | | | | | | | | | | | |
| Total | | | | | | | | | | | 846 | 167 | 83 | 36 | 80 | 83 | 51 | 26 | 58 | |

| | | |
|-------------------------|---------|-----|
| 15% HCl Acid: | 1,000 | gal |
| Slickwater: | 113,311 | gal |
| 16# DeltaFrac 140 (11): | 51,191 | gal |
| Total Fluid: | 165,502 | gal |
| Total Slurry: | 171,133 | gal |
| 20/40 White: | 129,876 | lbs |
| Total Proppant: | 129,876 | lbs |

129,876

4074.6

Average Rate

47.3

Used
 % diff
 Prime
 Total

| | |
|-------------|-------|
| TOP PERF | 4,740 |
| BOTTOM PERF | 5,041 |
| MID PERF | 4,891 |
| BHT | 4,891 |

BHT GRAD (TF/100-R (+60°))

| | |
|--------------------|-------------------------------|
| API # | 43-047-54269 |
| AFE# | |
| Sec. / Twp. / Rng. | S:16 / T:6S / R:20E |
| Well Name | Three Rivers 16-42L-820 |
| Company | Ultra Petroleum |
| Formation | |
| Fluid Systems | 16# DeltaFrac 140 (13) Hybrid |
| Date | August 1, 2014 |
| Base Fluid, lb/gal | 8.33 |
| Sales Order # | |
| County and State | Utah, UT |
| Zone #6 | |

| Total Perfs: 39 | | | |
|-----------------|-------------|-----|------------|
| Top Perf | Bottom Perf | SPF | # of shots |
| 4740 | 4741 | 3 | 3 |
| 4762 | 4763 | 3 | 3 |
| 4776 | 4777 | 3 | 3 |
| 4801 | 4802 | 3 | 3 |
| 4822 | 4823 | 3 | 3 |
| 4860 | 4861 | 3 | 3 |
| 4875 | 4876 | 3 | 3 |
| 4883 | 4884 | 3 | 3 |
| 4936 | 4937 | 3 | 3 |
| 4980 | 4981 | 3 | 3 |
| 4992 | 4993 | 3 | 3 |
| 5021 | 5022 | 3 | 3 |
| 5040 | 5041 | 3 | 3 |

| | |
|-------------|------------|
| Start Time: | 10:44 AM |
| End Time: | 12:00 PM |
| Customer: | Joe Duncan |

Company Ultra Petroleum
 Formation Three Rivers 16-42L-820
 Perfs Zone #7 Temperature 136
 Fluid System: aFrac 140 (13) Hybrid
 4535 - 4706

API 43-047-54269
 °F

Liquid Additives

| Stage | Fluid | Fluid | Prop Conc | Prop | Slurry Vol | Slurry Rate | Treating Pressure | Stage Pump Time | Exposure Time | WG-36 Gel | LeSurf-300D Surfactant | CLA-Web Clay Control | B-8514 Biocide | MX 2-2822 Scale inh. | BC-140 Crosslinker | OptiG-HTE Breaker | SP Breaker | FR-56 Fict. Red | BA-20 Buffer |
|-------|-------------------------|-------|-----------|-------|------------|-------------|-------------------|-----------------|---------------|-----------|------------------------|----------------------|----------------|----------------------|--------------------|-------------------|------------|-----------------|--------------|
| 1 | Load & Break | 269 | (gal) | (lbs) | 6.4 | 6.4 | 1108 | 0:01:00 | 1:10:55 | (ppt) | (gpt) | (gpt) | (gpt) | (gpt) | (gpt) | (ppt) | (ppt) | (gpt) | (gpt) |
| 2 | 15% HCl Acid | 1000 | | | 23.8 | 9.9 | 1193 | 0:02:24 | 1:09:55 | | 1.00 | 0.50 | 0.20 | | | | | 0.30 | |
| 3 | Pad | 43694 | | | 1040.3 | 57.8 | 2026 | 0:16:00 | 1:07:31 | | 1.00 | 0.50 | 0.20 | 0.56 | | | | 0.30 | |
| 4 | 0.5#/gal 20/40 White | 67299 | 0.45 | 30510 | 1635.2 | 60.6 | 1995 | 0:26:59 | 0:49:31 | | 1.00 | 0.50 | 0.20 | 0.56 | | | | 0.30 | |
| 5 | 0.5#/gal 20/40 White | 5018 | 0.45 | 2268 | 121.9 | 60.5 | 2016 | 0:02:01 | 0:22:32 | | 1.00 | 0.50 | 0.20 | 2.00 | | | | 0.30 | |
| 6 | 0.5#/gal 20/40 White | 5051 | 0.05 | 240 | 120.5 | 59.4 | 2009 | 0:02:02 | 0:20:31 | 9.50 | 1.00 | 0.50 | 0.20 | 0.25 | 0.95 | 0.59 | 0.30 | | 0.06 |
| 7 | Pad | 2080 | 0.40 | 826 | 50.4 | 56.4 | 1920 | 0:00:54 | 0:18:29 | 16.00 | 1.00 | 0.50 | 0.20 | 0.25 | 1.60 | 1.00 | 0.50 | | 0.10 |
| 8 | 2.0 #/gal 20/40 White | 15166 | 1.94 | 28390 | 392.8 | 59.9 | 2021 | 0:06:33 | 0:17:36 | 16.00 | 1.00 | 0.50 | 0.20 | 0.25 | 1.60 | 1.00 | 0.50 | | 0.10 |
| 9 | 4.0 #/gal 20/40 White | 8660 | 3.81 | 33000 | 241.7 | 60.2 | 1950 | 0:04:01 | 0:11:02 | 16.00 | 1.00 | 0.50 | 0.20 | 0.25 | 1.60 | 1.00 | 0.50 | | 0.10 |
| 10 | 6.0 #/gal 20/40 White | 7149 | 5.27 | 37666 | 210.8 | 60.1 | 1753 | 0:03:30 | 0:07:01 | 16.00 | 1.00 | 0.50 | 0.20 | | 1.60 | 1.00 | 0.50 | | 0.10 |
| 11 | Flush (top perf+3 bbls) | 4369 | | | 104.0 | 29.6 | 1575 | 0:03:31 | | | 1.00 | 0.50 | 0.20 | | | | 0.50 | | |
| 13 | Growler Tub Variance | | | | | | | | | 50.00 | 1.00 | 0.50 | 0.20 | | | | | 0.30 | 0.10 |
| | | | | | | | | | | 576.9 | 158.8 | 79.4 | 31.8 | 80.0 | 57.7 | 36.1 | 18.0 | 36.2 | 3.6 |
| | | | | | | | | | | 664 | 161 | 80 | 35 | 80 | 59 | 36 | 18 | 39 | 5 |
| | | | | | | | | | | 15% | 1% | | 10% | | 2% | | 8% | | 39% |
| | | | | | | | | | | Used | | | | | | | | | |
| | | | | | | | | | | % diff | | | | | | | | | |
| | | | | | | | | | | Prime | | | | | | | | | |
| | | | | | | | | | | Total | | | | | | | | | |
| | | | | | | | | | | 564 | 161 | 80 | 35 | 80 | 59 | 36 | 18 | 39 | 5 |

| | | |
|-------------------------|---------|-----|
| 15% HCl Acid: | 1,000 | gal |
| Slickwater: | 122,700 | gal |
| 16# DeltaFrac 140 (11): | 36,065 | gal |
| Total Fluid: | 159,765 | gal |
| Total Slurry: | 165,545 | gal |
| 20/40 White: | 133,900 | lbs |
| Total Proppant: | 133,900 | lbs |

| | |
|-------------|-------|
| TOP PERF | 4,535 |
| BOTTOM PERF | 4,706 |
| MID PERF | 4,621 |
| BHT | 1,046 |

BHT GRAD [°F/100-R (+60°)]

43-047-54269
 API #
 AFE#
 S:16 / T:8S / R:20E
 Three Rivers 16-42L-820
 Ultra Petroleum
 Formation
 Fluid Systems
 Date
 Base Fluid, lb/gal
 Sales Order #
 County and State

16# DeltaFrac 140 (13) Hybrid
 August 1, 2014
 8.33
 901549841
 Uintah, UT

Zone #7

| Total Perfs: 39 | | | |
|-----------------|-------------|-----|------------|
| Top Perf | Bottom Perf | SPF | # of shots |
| 4535 | 4536 | 3 | 3 |
| 4550 | 4551 | 3 | 3 |
| 4560 | 4561 | 3 | 3 |
| 4571 | 4572 | 3 | 3 |
| 4579 | 4580 | 3 | 3 |
| 4608 | 4609 | 3 | 3 |
| 4619 | 4620 | 3 | 3 |
| 4633 | 4634 | 3 | 3 |
| 4657 | 4658 | 3 | 3 |
| 4669 | 4670 | 3 | 3 |
| 4684 | 4685 | 3 | 3 |
| 4704 | 4706 | 3 | 6 |

| | |
|-------------|------------|
| Start Time: | 1:30 PM |
| End Time: | 2:40 PM |
| Customer: | Joe Duncan |

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 6

ENTITY ACTION FORM

Operator: Ultra Petroleum Inc. Operator Account Number: N 4045
Address: 116 Inverness Drive East Suite 400
city Denver
state CO zip 80112 Phone Number: (307) 367-5041

Well 1

| API Number | Well Name | | QQ | Sec | Twp | Rng | County |
|--|-----------------------|-------------------|-----------|-----|-----|----------------------------------|--------|
| | Multiple Wells | | | | | | Uintah |
| Action Code | Current Entity Number | New Entity Number | Spud Date | | | Entity Assignment Effective Date | |
| D | See List | 19892 | | | | 8/10/15 | |
| Comments: Assign multiple wells to a new common entity number. List of wells attached. <u>TR16 CTB North</u> | | | | | | | |

Well 2

| API Number | Well Name | | QQ | Sec | Twp | Rng | County |
|---|-----------------------|-------------------|-----------|-----|-----|----------------------------------|--------|
| | | | | | | | |
| Action Code | Current Entity Number | New Entity Number | Spud Date | | | Entity Assignment Effective Date | |
| D | See List | 19893 | | | | 8/10/15 | |
| Comments: <u>TR16 CTB South</u> | | | | | | | |

Well 3

| API Number | Well Name | | QQ | Sec | Twp | Rng | County |
|------------------|-----------------------|-------------------|-----------|-----|-----|----------------------------------|--------|
| | | | | | | | |
| Action Code | Current Entity Number | New Entity Number | Spud Date | | | Entity Assignment Effective Date | |
| | | | | | | | |
| Comments: | | | | | | | |

ACTION CODES:

- A - Establish new entity for new well (single well only)
- B - Add new well to existing entity (group or unit well)
- C - Re-assign well from one existing entity to another existing entity
- D - Re-assign well from one existing entity to a new entity
- E - Other (Explain in 'comments' section)

Jasmine Allison

Name (Please Print)



Signature

Sr. Permitting Analyst

8/6/2015

Title

Date

| WellCode | WellName | API | Current Entity Number | QtrQtr | Section | Township | Range | County | SpudDate |
|-----------------------|-------------------------|------------|-----------------------|--------|---------|----------|--------|-----------|----------|
| TR16 CTB North | | | | | | | | | |
| TR16-11-820 | THREE RIVERS 16-11-820 | 4304753474 | 19262 | SWNW | 16 8S | 20E | UINTAH | 28-Dec-13 | |
| TR16-11T-820 | THREE RIVERS 16-11T-820 | 4304754352 | 19557 | NWNW | 16 8S | 20E | UINTAH | 29-Jun-14 | |
| TR16-12-820 | THREE RIVERS 16-12-820 | 4304753475 | 19263 | SWNW | 16 8S | 20E | UINTAH | 06-Jan-14 | |
| TR16-12T-820 | THREE RIVERS 16-12T-820 | 4304754353 | 19558 | NWNW | 16 8S | 20E | UINTAH | 23-Jun-14 | |
| TR16-21-820 | THREE RIVERS 16-21-820 | 4304753229 | 19024 | NENW | 16 8S | 20E | UINTAH | 25-May-13 | |
| TR16-21T-820 | THREE RIVERS 16-21T-820 | 4304754364 | 19578 | SENW | 16 8S | 20E | UINTAH | 30-Jul-14 | |
| TR16-22A-820 | THREE RIVERS 16-22A-820 | 4304754365 | 19579 | SENW | 16 8S | 20E | UINTAH | 26-Jul-14 | |
| TR16-31-820 | THREE RIVERS 16-31-820 | 4304753495 | 19269 | NWNE | 16 8S | 20E | UINTAH | 13-Jan-14 | |
| TR16-41-820 | THREE RIVERS 16-41-820 | 4304752110 | 18356 | NENE | 16 8S | 20E | UINTAH | 31-Jan-12 | |
| TR16-42L-820 | THREE RIVERS 16-42L-820 | 4304754269 | 19491 | SENE | 16 8S | 20E | UINTAH | 20-Jul-14 | |
| TR16-42T-820 | THREE RIVERS 16-42T-820 | 4304754292 | 19471 | NENE | 16 8S | 20E | UINTAH | 06-May-14 | |
| TR16-44T-820 | THREE RIVERS 16-44T-820 | 4304754356 | 19561 | SENE | 16 8S | 20E | UINTAH | 15-Jul-14 | |
| TR16 CTB South | | | | | | | | | |
| TR16-13T-820 | THREE RIVERS 16-13T-820 | 4304754339 | 19492 | NWSW | 16 8S | 20E | UINTAH | 02-Jun-14 | |
| TR16-14T-820 | THREE RIVERS 16-14T-820 | 4304754340 | 19493 | NWSW | 16 8S | 20E | UINTAH | 06-Jun-14 | |
| TR16-22-820 | THREE RIVERS 16-22-820 | 4304753230 | 18961 | NENW | 16 8S | 20E | UINTAH | 31-May-13 | |
| TR16-23-820 | THREE RIVERS 16-23-820 | 4304753231 | 19037 | SESW | 16 8S | 20E | UINTAH | 15-Jun-13 | |
| TR16-24-820 | THREE RIVERS 16-24-820 | 4304753232 | 19038 | SESW | 16 8S | 20E | UINTAH | 08-Jun-13 | |
| TR16-26T-820 | THREE RIVERS 16-26T-820 | 4304754351 | 19556 | NESW | 16 8S | 20E | UINTAH | 16-Jul-14 | |
| TR16-32-820 | THREE RIVERS 16-32-820 | 4304753494 | 19185 | SWNE | 16 8S | 20E | UINTAH | 27-Sep-13 | |
| TR16-32T-820 | THREE RIVERS 16-32T-820 | 4304754290 | 19470 | NWNE | 16 8S | 20E | UINTAH | 01-May-14 | |
| TR16-33-820 | THREE RIVERS 16-33-820 | 4304753496 | 19161 | SWNE | 16 8S | 20E | UINTAH | 12-Nov-13 | |
| TR16-33T-820 | THREE RIVERS 16-33T-820 | 4304754354 | 19559 | NWSE | 16 8S | 20E | UINTAH | 04-Jul-14 | |
| TR16-34-820 | THREE RIVERS 16-34-820 | 4304753472 | 19278 | SWSE | 16 8S | 20E | UINTAH | 24-Jun-14 | |
| TR16-34T-820 | THREE RIVERS 16-34T-820 | 4304754355 | 19560 | NWSE | 16 8S | 20E | UINTAH | 11-Jul-14 | |
| TR16-36T-820 | THREE RIVERS 16-36T-820 | 4304754289 | 19529 | SESE | 16 8S | 20E | UINTAH | 16-Jun-14 | |
| TR16-43-820 | THREE RIVERS 16-43-820 | 4304752057 | 18683 | NESE | 16 8S | 20E | UINTAH | 09-Aug-12 | |
| TR16-44-820 | THREE RIVERS 16-44-820 | 4304753473 | 19268 | SESE | 16 8S | 20E | UINTAH | 19-Jun-14 | |
| TR16-46T-820 | THREE RIVERS 16-46T-820 | 4304754348 | 19530 | SESE | 16 8S | 20E | UINTAH | 11-Jun-14 | |

| | | |
|--|--|--|
| STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING | | FORM 9 |
| SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals. | | 5. LEASE DESIGNATION AND SERIAL NUMBER: ML-49319 |
| 1. TYPE OF WELL Oil Well | | 6. IF INDIAN, ALLOTTEE OR TRIBE NAME: |
| 2. NAME OF OPERATOR: ULTRA RESOURCES INC | | 7. UNIT or CA AGREEMENT NAME: |
| 3. ADDRESS OF OPERATOR: 116 Inverness Drive East, Suite #400, Englewood, CO, 80112 | | 8. WELL NAME and NUMBER: Three Rivers 16-42L-820 |
| 4. LOCATION OF WELL FOOTAGES AT SURFACE: 2006 FNL 0607 FEL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: SENE Section: 16 Township: 08.0S Range: 20.0E Meridian: S | | 9. API NUMBER: 43047542690000 |
| PHONE NUMBER: 303 645-9809 Ext | | 9. FIELD and POOL or WILDCAT: THREE RIVERS |
| COUNTY: UTAH | | STATE: UTAH |
| 11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA | | |
| TYPE OF SUBMISSION | TYPE OF ACTION | |
| <input type="checkbox"/> NOTICE OF INTENT Approximate date work will start: | <input type="checkbox"/> ACIDIZE | |
| <input checked="" type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: 2/9/2017 | <input type="checkbox"/> ALTER CASING | |
| <input type="checkbox"/> SPUD REPORT Date of Spud: | <input type="checkbox"/> CASING REPAIR | |
| <input type="checkbox"/> DRILLING REPORT Report Date: | <input type="checkbox"/> CHANGE TO PREVIOUS PLANS | |
| | <input type="checkbox"/> CHANGE TUBING | |
| | <input type="checkbox"/> CHANGE WELL STATUS | |
| | <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS | |
| | <input type="checkbox"/> DEEPEN | |
| | <input type="checkbox"/> FRACTURE TREAT | |
| | <input type="checkbox"/> OPERATOR CHANGE | |
| | <input type="checkbox"/> PLUG AND ABANDON | |
| | <input checked="" type="checkbox"/> PRODUCTION START OR RESUME | |
| | <input type="checkbox"/> RECLAMATION OF WELL SITE | |
| | <input type="checkbox"/> REPERFORATE CURRENT FORMATION | |
| | <input type="checkbox"/> SIDETRACK TO REPAIR WELL | |
| | <input type="checkbox"/> TUBING REPAIR | |
| | <input type="checkbox"/> VENT OR FLARE | |
| | <input type="checkbox"/> WATER SHUTOFF | |
| | <input type="checkbox"/> SI TA STATUS EXTENSION | |
| | <input type="checkbox"/> WILDCAT WELL DETERMINATION | |
| | <input type="checkbox"/> OTHER: <input style="width: 100px;" type="text"/> | |
| 12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. This well resumed production on February 7, 2017. | | |
| Accepted by the Utah Division of Oil, Gas and Mining FOR RECORD ONLY February 10, 2017 | | |
| NAME (PLEASE PRINT) Carla Molliconi | PHONE NUMBER 303-645-9877 | TITLE Permit Specialist |
| SIGNATURE N/A | DATE 2/9/2017 | |